



## Old Dillon Reservoir Enlargement Project

Town of Dillon

Substantially Complete April 1, 2015



### PROJECT DESCRIPTION

The Town of Dillon participated in the enlargement of the Old Dillon Reservoir. In 2004, the Town, Summit County and Town of Silverthorne signed an agreement to enlarge the Reservoir to 286 AF. The Town's participation cost was approximately 27% of the construction costs and 20% of the engineering costs. The Reservoir was originally a 46 AF raw water storage reservoir filled via the Dillon Ditch, which diverts water from Salt Lick Gulch to the site. The reservoir was drained in 2008 due to dam safety concerns. This project included two new dams and a pipeline system from the new Salt Lick Gulch diversion structure. The Reservoir is located southwest of the Dillon Reservoir Dam.

P R O J E C T   D A T A		
<i>Sponsor:</i> Town of Dillon	<i>County:</i> Summit	<i>Water Source:</i> Salt Lick Gulch
<i>Type of Loan:</i> Reservoir Rehabilitation		<i>Board Approval Date:</i> May 19, 2009
<i>Terms of Loan:</i> \$1,515,000 at 4.0% for 30 years		
<i>Project Manager:</i> Colorado River WCD, Glenwood Springs, CO		
<i>Design Engineer:</i> Tetra Tech Inc, Longmont, CO		
<i>Contractor:</i> Fiore & Sons Inc, Denver, CO		
<i>Project Elements:</i> 120,000CY excavation, 80,000CY of fill, 10,000CY riprap, and 7,000 feet of 24" HDPE pipe, an inverted siphon under I-70 and a new headgate		