



## Lake Otonowanda Rehabilitation Project

Town of Ridgway

Substantially Complete January 1, 2016



### Project Description

The rehabilitation improvements and enlargement of Lake Otonowanda was to ensure a reliable water supply of raw water that would be available under future drought conditions. Otonowanda is the primary storage facility for the town, responsible for treating and delivering potable water to 695 SFE. Otonowanda. During 2002, all of the Town's water rights fell out of priority due to extended drought conditions and the Town was dangerously close to running out of water. The improvements to the reservoir, including: replacement of the outlet works, reservoir lining and a 254-AF enlargement, provided the Town the ability to store more of its adjudicated water rights and a controlled means to release the water, firming the Town's water supply in the event of future call outs.

P R O J E C T   D A T A		
<i>Sponsor:</i> Town of Ridgway	<i>County:</i> Ouray	<i>Water Source:</i> Ridgway Ditch
<i>Type of Project:</i> Reservoir Enlargement		<i>Board Approval Date:</i> September 2012
<i>Loan Terms: (Original)</i> \$606,000 @ 3.0% for 30 years <i>(Final)</i> \$606,000		
<i>Design Engineer:</i> Joanne Fagan, PE, City Engineer		
<i>Contractor:</i> Rundle Construction, Hotchkiss CO		
<i>Project Elements:</i> replacment of outlet works, earthwork, and reservoir lining		