



NOTES:

1. COMPACTED SOIL LINER FILL OR OTHER FILL APPROVED BY THE MANAGER TO BACKFILL ANCHOR TRENCH. ANCHOR TRENCHES INTERNAL TO THE VLF WILL BE BACKFILLED WITH SOIL LINER FILL FOR THE UPPER 1FT (MIN.).
2. REFER TO PROJECT SPECIFICATIONS REGARDING MINIMUM DRAIN COVER FILL DEPTHS FOR WORKING OVER GEOSYNTHETICS AND PIPING WITH RUBBER TIRE OR TRACK MOUNTED EQUIPMENT.
3. TOP 2 FEET OF EMBANKMENT FILL SHALL HAVE A RESISTANCE (R) VALUE OF 40. SEE STATE HIGHWAY 67 RELOCATION DRAWINGS.



1	02/13/14	REVISED LINER LIMITS/RE-ISSUED FOR CONSTRUCTION	MEN	PBS
0	01/07/13	ISSUED FOR CONSTRUCTION	JNM	CMT

DISCLAIMER

AMEC PRODUCED THE INFORMATION PRESENTED ON THIS DRAWING THROUGH THE USE OF TECHNICAL INFORMATION AND PRACTICAL EXPERIENCE SPECIFIC TO ITS EFFORTS. RECEIVING THIS DRAWING DOES NOT GUARANTEE ANY RIGHTS TO SUCH TECHNICAL INFORMATION AND PRACTICAL EXPERIENCE. ANY ALTERATION OR ADAPTATION OF THE DATA OR CONTENTS OF THIS DRAWING SHALL BE AT USER'S SOLE RISK AND WITHOUT ANY LIABILITY OR LEGAL RESPONSIBILITY TO AMEC.

CLIENT				CRIPPLE CREEK & VICTOR GOLD MINING COMPANY			
PROJECT				SQUAW GULCH VLF			
TITLE				PSSA SECTIONS AND DETAILS SHEET 4 OF 4			
DESIGNED BY	JNM	CHECKED BY	JNM	DRAWN BY	DS	APPROVED BY	KFM
FILENAME				DRAWING No.		REV	
1125GD36				A320		1	

