

May 22, 2019

Mr. Eric Scott
Environmental Protection Specialist
Division of Reclamation, Mining and Safety
Department of Natural Resources
1313 Sherman St. Room 215
Denver, Colorado 80203

RE: Climax Mine, Permit No. M-1977-493, Technical Revision 29 – Adequacy Review Response

Dear Mr. Scott,

Climax Molybdenum Company – Climax Mine (Climax) has prepared a response to the item raised in the April 2, 2018 Adequacy Review letter in regard to Technical Revision 29. DRMS comments are in italics font, followed by the Climax response.

Comment #1: These proposed modifications will be conducted on facilities that are considered Environmental Protection Facilities (EPFs) by the Division. As such, DRMS will require that the provided design drawings be signed and stamped by the Engineer of Record (EOR) for the facilities to be modified, as well as a commitment to submit similarly certified as-built reports upon completion. DRMS also will require notice when construction is to commence for the proposed work, so that in process inspections may take place.

Response: Climax has attached stamped/signed construction drawings for the Mayflower Flood Bypass Tunnel – Phase II and soil excavation and stabilization for the future riser structure titled “Mayflower Flood Bypass Tunnel System, Phase II Tunnel – Construction Drawings” and “Mayflower Flood Bypass Tunnel, Phase II Vertical Intake Structure, Portal Construction Plans”. TR-29 referred to a tower riser structure; however, construction drawings for that facility are not available at this point in time so those drawings will be submitted as a separate Technical Revision in early 2020. Once Phase II of the tunnel is complete, Climax will submit a certification for this facility from the EOR.

Climax has also attached a memo titled “REV 0 – Mayflower Tailings Storage Facility Leadoff Clarification, Climax Mine, Permit No. M-1977-493” from the tailings EOR clarifying that the addition of a fourth leadoff on the Mayflower Tailings Storage Facility (TSF) was always part of the planned development of the TSF, along with additional leadoffs in the future. Each year, Climax submits a certification for the TSF from the EOR for the previous year’s construction and the additional leadoff will be included in the certification submitted for 2019.

In the most recent EPP update (TR-28) Climax described the clean water interceptor system in Section T-5 as follows:

“Climax recognizes their importance to the overall water management system, but notes that the clean water interceptors do not appear to meet the definition of an EPF since they carry only un-impacted water around the site and do not contain or control designated chemicals or process solutions. As agreed upon with DRMS, although these systems are considered to be pre-EPF systems and do not contain or control designated chemicals or process solutions, they will be managed by Climax as internal EPFs. The interceptor systems are closely monitored, inspected and maintained as part of routine site monitoring activities. Other than repair and maintenance/upgrades, any future expansion or modifications of the interceptors will be subject to review by DRMS, consistent with Section 6.4.21(10)(a)(ii) of the Rules.”

In accordance with TR-28, Climax is providing stamped/signed construction drawings for the West Interceptor Phase D improvement project titled “Interceptor Rehabilitation Project, West Interceptor Culvert Replacement (Phase D) Downstream of Searle Gulch”. Once construction is complete, Climax will submit a certification for this facility from the EOR.

The Division also verbally asked a question about the hydraulic capacity of the West Interceptor once the Phase D improvements were complete as it relates to the evaluation that Climax completed in 2014 as requested as part of TR-18. The Division originally requested that Climax complete a hydrologic analysis to determine if the interceptor systems could safely pass a 10-yr/24-hr rainfall event and it was determined that there were portions of the West Interceptor that could not pass this size event. A 10-yr/24-hr rainfall event for the West Interceptor System at Searle Gulch is estimated to be about 145cfs. After the Phase D improvements are made to the West Interceptor, the overall capacity will increase to 106cfs from the current 86cfs for the section downstream of Searle Gulch. Additional improvements downstream from Phase D are planned for the future that will pass 145cfs; in the meantime, a gate will be used at the upstream end of Phase D to limit the flow to 106cfs.

Please contact Raymond Lazuk at 719-486-7584 or me at 719-486-7525 if you need additional information.

Sincerely,

A handwritten signature in cursive script that reads "Diana Kelts".



Diana Kelts
Chief Environmental Scientist

MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM PHASE II TUNNEL - CONSTRUCTION DRAWINGS

APRIL 2019

REVISION - 2


ISSUED FOR CONSTRUCTION



Not to Scale

DRAWING INDEX	
TUNNEL CONSTRUCTION DRAWINGS	
DRAWING No.	DRAWING TITLE
MFT-C-01	COVER SHEET / PROJECT LOCATION MAP
MFT-C-02	LEGEND AND GENERAL NOTES
MFT-C-03	EXISTING PHASE I TUNNEL ALIGNMENT AND TUNNEL STAGING AREAS
MFT-C-04	EXISTING PHASE I TUNNEL AS-BUILT PROFILE
MFT-C-05	PHASE I TUNNEL TYPICAL CROSS-SECTION
MFT-C-06	EXISTING OUTLET PORTAL FACILITIES AND PROPOSED CAMP AREA
MFT-C-07	PROPOSED PHASE II TUNNEL EXTENSION ALIGNMENTS AND STAGING AREAS
MFT-C-08	PROPOSED PHASE II MAIN TUNNEL EXTENSION PROFILE
MFT-C-09	PROPOSED NO. 2, NO. 3 AND NO. 4 SPUR PROFILES
MFT-C-10	TYPICAL GROUND SUPPORT DETAILS RMR CLASS I & II GROUND
MFT-C-11	TYPICAL GROUND SUPPORT DETAILS RMR CLASS III GROUND
MFT-C-12	TYPICAL GROUND SUPPORT DETAILS RMR CLASS IV GROUND
MFT-C-13	TYPICAL GROUND SUPPORT DETAILS RMR CLASS V GROUND
MFT-C-14	TYPICAL GROUND SUPPORT DETAILS RMR CLASS VI GROUND
MFT-C-15	TYPICAL GROUND SUPPORT DETAILS RMR CLASS I-II GROUND 12-20 FT WIDE
MFT-C-16	TYPICAL GROUND SUPPORT DETAILS RMR CLASS III GROUND 12-20 FT WIDE
MFT-C-17	TYPICAL GROUND SUPPORT DETAILS 3-WAY TUNNEL INTERSECTION RMR CLASS I-III
MFT-C-18	TYPICAL TUNNEL INTERSECTION DETAILS FUTURE SPUR INTERSECTIONS
MFT-C-19	TYPICAL TUNNEL CUTOUT DETAILS ELECTRICAL SUBSTATION
MFT-C-20	TYPICAL TUNNEL CUTOUT DETAILS SAFETY BAY
MFT-C-21	TYPICAL PROBE HOLE AND GROUT HOLE GEOMETRY


REV	DESCRIPTION OF REVISION	BY	DATE
1	ISSUED FOR CONSTRUCTION	RLM	4/19
2	ISSUED FOR BID	RLM	10/18
3	ISSUED FOR CLIENT REVIEW	RLM	9/18



DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
COVER SHEET / PROJECT LOCATION MAP

REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-01
SHEET	1 OF 1




NOTES


LEGEND

GENERAL NOTES:

1. THIS DRAWING SET IS BASED ON INFORMATION PROVIDED BY OTHERS. ALL LOCATIONS ARE BELIEVED TO BE ACCURATE. AJAX IS NOT RESPONSIBLE FOR THE ACCURACY OF THE DRAWINGS OR THE DESIGN CALCULATIONS USED TO SUPPORT THE DESIGNS CONTAINED HEREIN.
2. BASE TOPOGRAPHY PROVIDED BY FMI-CLIMAX. TOPOGRAPHY INSIDE DASH-DOT LINE FROM 2016 AERIAL. TOPOGRAPHY OUTSIDE DASH-DOT LINE FROM 2006 AERIAL.
3. HISTORIC MINING ACTIVITY LOCATIONS PROVIDED BY AECOM (legacy URS) 3/25/13. LOCATIONS ARE APPROXIMATE AND FIELD SURVEY HAS NOT BEEN PROVIDED FOR VERIFICATION OF MINING ACTIVITY.
4. BEDROCK STRUCTURE AND SURFACE GEOLOGY INTERPRETED BY AECOM (legacy URS).
5. MASTER SURVEY PLAT OVERLAY IS AN APPROXIMATE LOCATION AND FIELD SURVEY HAS NOT BEEN PROVIDED FOR VERIFICATION OF LOCATION OF MINING CLAIM OR MINING ACTIVITY.
6. NOTES FOR THE HISTORIC MINING CLAIMS DEPICTED ON THE MASTER SURVEY PLAT WERE PROVIDED BY THE BLM TO AECOM (legacy URS) OCTOBER, 2011.
7. REVISED GROUND REINFORCEMENT PLANS, DETAILS AND ENGINEERING CALCULATIONS FOR GROUND SUPPORT CLASSIFICATIONS PROVIDED BY LANGSTON & ASSOCIATES TO CLIMAX AND HENDERSON DURING PHASE I TUNNELING OPERATIONS. REFINEMENTS TO THE GROUND SUPPORT PLANS AND DETAILS ARE REQUIREMENTS OF CLIMAX MOLYBDENUM CORPORATION.



GEOLOGIC LEGEND




RMR LEGEND




NOTES:

1. TUNNEL PROFILE VERTICAL SCALE EXAGGERATED.
2. GEOLOGIC CONTACTS AND FAULT LOCATIONS ARE APPROXIMATE



REVISIONS	<div><div></div><div></div><div></div><div></div><div></div><div></div></div>			
	<div><div></div><div></div><div></div><div></div><div></div><div></div></div>			
	<div><div></div><div></div><div></div><div></div><div></div><div></div></div>			
	<div><div>2</div><div></div><div></div><div></div><div></div><div></div></div>	ISSUED FOR CONSTRUCTION	RLM	4/19
	<div><div>1</div><div></div><div></div><div></div><div></div><div></div></div>	ISSUED FOR BID	RLM	10/18
	<div><div>0</div><div></div><div></div><div></div><div></div><div></div></div>	ISSUED FOR CLIENT REVIEW	RLM	9/18
	REV	DESCRIPTION OF REVISION	BY	DATE





DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE


MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM

LEGEND AND GENERAL NOTES

REVISION	
PROJECT NO.	12235
DRAWING	MFT-C-02
SHEET	1 OF 1




△			
△			
△	ISSUED FOR CONSTRUCTION	RLM	4/19
△	ISSUED FOR BID	RLM	10/18
△	ISSUED FOR CLIENT REVIEW	RLM	9/18
REV	DESCRIPTION OF REVISION	BY	DATE




DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
EXISTING PHASE I TUNNEL ALIGNMENT AND TUNNEL STAGING AREAS



REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-03
SHEET	1 OF 1



GEOLOGIC PROFILE - PHASE I

(N.T.S.)

GEOLOGIC LEGEND


Ti INTRUSIVE QUARTZ MONZONITE PORPHYRY OR SIMILAR ROCK; SILLS INTRUDED INTO PALEOZOIC SEDIMENTS ARE THE MOST COMMON FORM OF OCCURRENCE.

Ppm MINTURN FORMATION: PREDOMINANTLY THICK SEQUENCES OF ARKOSIC SANDSTONE LOCALLY METAMORPHOSED TO QUARTZITE NEAR INTRUSIVE QUARTZ MONZONITE PORPHYRY.

Ti/Ppm MIXED FACE: INCLUDES BOTH QUARTZ MONZONITE AND PRECAMBRIAN QUARTZITE OR HORNFELS DEPOSITS;

Qatc UNDIFFERENTIATED QUATERNARY ALLUVIUM, TILL, AND COLLUVIUM.

/ APPROXIMATE FAULT LOCATION



ROCK MASS RATING (RMR) - PHASE I

(N.T.S.)

RMR LEGEND

RMR 1 RMR - CLASS I


RMR 2 RMR - CLASS II

RMR 3 RMR - CLASS III

RMR 4 RMR - CLASS IV

RMR 5 RMR - CLASS V


RMR 6 RMR - CLASS VI



TUNNEL GROUND SUPPORT - PHASE I

(N.T.S.)

- NOTES:**
- 1. TUNNEL PROFILE VERTICAL SCALE EXAGGERATED.
 - 2. GEOLOGIC CONTACTS AND FAULT LOCATIONS ARE APPROXIMATE



AutoCAD FILE: MFT Stage II Construction

REV	DESCRIPTION OF REVISION	BY	DATE
1	ISSUED FOR CONSTRUCTION	RLM	4/19
2	ISSUED FOR BID	RLM	10/18
3	ISSUED FOR CLIENT REVIEW	RLM	9/18



WARNING

0 0.5 1

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19


CLIMAX MINE

MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM

EXISTING PHASE I TUNNEL


AS-BUILT PROFILE

REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-04
SHEET	1 OF 1




TYPICAL TUNNEL CROSS-SECTION GEOMETRY

NOT TO SCALE




REV	DESCRIPTION OF REVISION	BY	DATE
1	ISSUED FOR CONSTRUCTION	RLM	4/19
2	ISSUED FOR BID	RLM	10/18
3	ISSUED FOR CLIENT REVIEW	RLM	9/18




DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
PHASE I TUNNEL TYPICAL CROSS-SECTION

REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-05
SHEET	1 OF 1





REV	DESCRIPTION OF REVISION	BY	DATE
1	ISSUED FOR CONSTRUCTION	RLM	4/19
2	ISSUED FOR BID	RLM	10/18
3	ISSUED FOR CLIENT REVIEW	RLM	9/18




DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
EXISTING OUTLET PORTAL FACILITIES AND PROPOSED CAMP AREA

REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-06
SHEET	1 OF 1




▲			
▲			
▲	ISSUED FOR CONSTRUCTION	RLM	4/19
▲	ISSUED FOR BID	RLM	10/18
▲	ISSUED FOR CLIENT REVIEW	RLM	9/18
REV	DESCRIPTION OF REVISION	BY	DATE




DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19



CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
PROPOSED STAGE II TUNNEL EXTENSION ALIGNMENTS AND STAGING AREAS




REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-07
SHEET	1 OF 1



MAIN TUNNEL PROFILE - PHASE II




REV	DESCRIPTION OF REVISION	BY	DATE
1	ISSUED FOR CONSTRUCTION	RLM	4/19
2	ISSUED FOR BID	RLM	10/18
3	ISSUED FOR CLIENT REVIEW	RLM	9/18




DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
PROPOSED STAGE II
MAIN TUNNEL EXTENSION PROFILE


REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-08
SHEET	1 OF 1




NO. 2 SPUR PROFILE - STAGE II




NO. 3 SPUR PROFILE - STAGE II



NO. 4 SPUR PROFILE - STAGE III



REV	DESCRIPTION OF REVISION	BY	DATE
1	ISSUED FOR CONSTRUCTION	RLM	4/19
2	ISSUED FOR BID	RLM	10/18
3	ISSUED FOR CLIENT REVIEW	RLM	9/18






DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
PROPOSED NO. 2, NO. 3
AND NO. 4 SPUR PROFILES

REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-09
SHEET	1 OF 1

THIS DESIGN, IN ITS ENTIRETY, INCLUDING GROUND REINFORCEMENT PLANS, DETAILS AND ENGINEERING CALCULATIONS FOR GROUND SUPPORT CLASSIFICATIONS PROVIDED BY LANGSTON & ASSOCIATES TO CLIMAX AND HENDERSON DURING PHASE I TUNNELING OPERATIONS. REFINEMENTS TO THE GROUND SUPPORT PLANS AND DETAILS ARE REQUIREMENTS OF CLIMAX MOLYBDENUM CORPORATION.

RMR CLASS I & II GROUND SUPPORT
GOOD GROUND UP TO 12' WIDE




ROCK REINFORCEMENT IN BACK
-7 FT, 46mm GALVANIZED SPLIT SET BOLTS ON A SYSTEMATIC 4 FT GRID

SURFACE SUPPORT
-MINIMUM 3 IN SHOTCRETE APPLIED PRIOR TO ROCK REINFORCEMENT

RIB SUPPORT
-TWO ROWS 6 FT ROCK REINFORCEMENT
-UPPER ROWS BOLTS INSTALLED 2 FT ABOVE 8 FT SPRING LINE
-LOWER ROWS BOLTS INSTALLED 6 FT OFF SILL

7 FT, 46mm GALVANIZED SPLIT SET BOLT WITH PLATE
NOTE: NOT COATED, NOT INSTALLED, NOT MEASURED, NOT TESTED, NOT TIED, NOT TIED



△			
△			
△	ISSUED FOR CONSTRUCTION	RLM	4/19
△	ISSUED FOR BID	RLM	10/18
△	ISSUED FOR CLIENT REVIEW	RLM	9/18
REV	DESCRIPTION OF REVISION	BY	DATE

Climax Molybdenum
A Freeport-McMoRan Company

AJAX
PROJECT & CONSTRUCTION MANAGEMENT
ENGINEERING, GEOLOGY, SURVEYING

WARNING
0 0.5 1
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE




DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
TYPICAL GROUND SUPPORT DETAILS
RMR CLASS I & II GROUND

REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-10
SHEET	1 OF 1


THIS DESIGN, IN ITS ENTIRETY, INCLUDING GROUND REINFORCEMENT PLANS, DETAILS AND ENGINEERING CALCULATIONS FOR GROUND SUPPORT CLASSIFICATIONS PROVIDED BY LANGSTON & ASSOCIATES TO CLIMAX AND HENDERSON DURING PHASE I TUNNELING OPERATIONS. REFINEMENTS TO THE GROUND SUPPORT PLANS AND DETAILS ARE REQUIREMENTS OF CLIMAX MOLYBDENUM CORPORATION.

RMR CLASS III GROUND SUPPORT
FAIR GROUND UP TO 12' WIDE




- ROCK REINFORCEMENT IN BACK**
-7 FT, 46mm GALVANIZED SPLIT SET BOLTS ON A SYSTEMATIC 4 FT GRID
- SURFACE SUPPORT**
-MINIMUM 3 IN SHOTCRETE APPLIED PRIOR TO ROCK REINFORCEMENT ON ENTIRE EXCAVATION PERIMETER
- RIB SUPPORT**
-THREE ROWS 7 FT ROCK REINFORCEMENT
-TOP ROWS BOLTS INSTALLED 2 FT ABOVE 8 FT SPRING LINE
-MID ROWS BOLTS INSTALLED 1 FT BELOW 8 FT SPRING LINE
-LOWER ROWS BOLTS INSTALLED 4 FT OFF SILL.

7 FT, 46mm GALVANIZED SPLIT SET BOLT WITH PLATE
NOTES: 1. IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE. 2. IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE.



REV	DESCRIPTION OF REVISION	BY	DATE
1	ISSUED FOR CONSTRUCTION	RLM	4/19
2	ISSUED FOR BID	RLM	10/18
3	ISSUED FOR CLIENT REVIEW	RLM	9/18





DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
TYPICAL GROUND SUPPORT DETAILS
RMR CLASS III GROUND

REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-11
SHEET	1 OF 1

THIS DESIGN, IN ITS ENTIRETY, INCLUDING GROUND REINFORCEMENT PLANS, DETAILS AND ENGINEERING CALCULATIONS FOR GROUND SUPPORT CLASSIFICATIONS PROVIDED BY LANGSTON & ASSOCIATES TO CLIMAX AND HENDERSON DURING PHASE I TUNNELING OPERATIONS. REFINEMENTS TO THE GROUND SUPPORT PLANS AND DETAILS ARE REQUIREMENTS OF CLIMAX MOLYBDENUM CORPORATION.

RMR CLASS IV GROUND SUPPORT
POOR GROUND UP TO 12' WIDE



RIB SUPPORT

-FOUR ROWS 7 FT ROCK REINFORCEMENT

TOP ROW BOLTS INSTALLED 2 FT ABOVE 8 FT SPRING LINE

MID ROW BOLTS INSTALLED 1 FT BELOW 8 FT SPRING LINE

LOWER ROW BOLTS INSTALLED 4 FT OFF SILL


BOTTOM ROW: BOLTS INSTALLED 1 FT OFF SILL TO SECURE WWM

PRE-SUPPORT ON ADVANCE MAY BE REQUIRED DEPENDING ON CONDITIONS

-INSTALL 12 FT Ø9 THREADBAR SPILING ON 12 IN CENTERS AROUND EXCAVATION PERIMETER

-6 FT MAXIMUM ROUND LENGTH ON ADVANCE THEN INSTALL ANOTHER ROUND OF SPILING.

NOTE: T O O W I ECTIO C O R S I G O I C E T E R S M E S T I T E D I T T E R




- INITIAL ROCK REINFORCEMENT**
-7 FT, 46mm SPLIT SET BOLTS ON A SYSTEMATIC 4 FT GRID WITH WELDED WIRE REINFORCEMENT INSTALLED UPON INITIAL EXCAVATION.

NOTE: TO THE COATED SWEET M E S T I T E D I T T E R
- INITIAL SURFACE SUPPORT**
-MINIMUM 3 IN SHOTCRETE APPLIED PRIOR TO FINAL ROCK REINFORCEMENT ON ENTIRE EXCAVATION PERIMETER.
- FINAL ROCK REINFORCEMENT**
-INSTALL 7 FT, 46mm GALVANIZED SPLIT SET BOLTS ON A SYSTEMATIC 4 FT GRID BETWEEN SHOTCRETE LAYERS AS SHOWN.

NOTE: TO THE COATED SWEET M E S T I T E D I T T E R
- FINAL SURFACE SUPPORT**
-MINIMUM 3 IN SHOTCRETE APPLIED AFTER FINAL ROCK REINFORCEMENT ON ENTIRE EXCAVATION PERIMETER.

7 FT, 46mm GALVANIZED SPLIT SET BOLT WITH PLATE



△			
△			
△	ISSUED FOR CONSTRUCTION	RLM	4/19
△	ISSUED FOR BID	RLM	10/18
△	ISSUED FOR CLIENT REVIEW	RLM	9/18
REV	DESCRIPTION OF REVISION	BY	DATE

Climax Molybdenum
A Freeport-McMoRan Company

AJAX
PROJECT & CONSTRUCTION MANAGEMENT
ENGINEERING, GEOLOGY, SURVEYING

WARNING
0 0.5 1
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE




DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
TYPICAL GROUND SUPPORT DETAILS
RMR CLASS IV GROUND

REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-12
SHEET	1 OF 1

THIS DESIGN, IN IT'S ENTIRETY, INCLUDING GROUND REINFORCEMENT PLANS, DETAILS AND ENGINEERING CALCULATIONS FOR GROUND SUPPORT CLASSIFICATIONS PROVIDED BY LANGSTON & ASSOCIATES TO CLIMAX AND HENDERSON DURING PHASE I TUNNELING OPERATIONS. REFINEMENTS TO THE GROUND SUPPORT PLANS AND DETAILS ARE REQUIREMENTS OF CLIMAX MOLYBDENUM CORPORATION.

RMR CLASS V GROUND SUPPORT
VERY POOR GROUND UP TO 12' WIDE



RIB SUPPORT

-FOUR ROWS 7 FT ROCK REINFORCEMENT

TOPER ROWS BOLTS INSTALLED 2 FT ABOVE 8 FT SPRING LINE

MID ROWS BOLTS INSTALLED 1 FT BELOW 8 FT SPRING LINE

LOWER ROWS BOLTS INSTALLED 4 FT OFF SILL

BOTTOM ROWS: BOLTS INSTALLED 1 FT OFF SILL TO SECURE WWM


TWO ROWS: 7 FT, 24 TONNE SWELLEX BOLTS AS SHOWN

PRE-SUPPORT ON ADVANCE

-INSTALL 12 FT #9 THREADBAR SPILING ON 12 IN CENTERS AROUND PERIMETER AS SHOWN

-6 FT MAXIMUM ROUND LENGTH ON ADVANCE THEN INSTALL ANOTHER ROUND OF SPILING.

NOTE: TO THE CONTRACTOR FOR SWEET MEASUREMENTS
MEASURE STITCHED INTER



1) INITIAL ROCK REINFORCEMENT

-7 FT, 39mm SPLIT SET BOLTS ON A SYSTEMATIC 4 FT GRID WITH WELDED WIRE REINFORCEMENT INSTALLED UPON INITIAL EXCAVATION.

NOTE: TO THE CONTRACTOR FOR SWEET MEASUREMENTS

2) INITIAL SURFACE SUPPORT

-MINIMUM 3 IN SHOTCRETE APPLIED PRIOR TO FINAL ROCK REINFORCEMENT ON ENTIRE EXCAVATION PERIMETER.

3) FINAL ROCK REINFORCEMENT

-INSTALL 7 FT, 24 TONNE COATED SWELLEX BOLTS ON A SYSTEMATIC 4 FT GRID BETWEEN SHOTCRETE LAYERS AS SHOWN.


4) FINAL SURFACE SUPPORT

-MINIMUM 3 IN SHOTCRETE APPLIED AFTER FINAL ROCK REINFORCEMENT ON ENTIRE EXCAVATION PERIMETER.

- 7 FT, 39mm SPLIT SET BOLT WITH PLATE
7 FT, 24 TONNE COATED SWELLEX BOLT WITH PLATE



REV	DESCRIPTION OF REVISION	BY	DATE
1	ISSUED FOR CONSTRUCTION	RLM	4/19
2	ISSUED FOR BID	RLM	10/18
3	ISSUED FOR CLIENT REVIEW	RLM	9/18




DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
TYPICAL GROUND SUPPORT DETAILS RMR CLASS V GROUND


REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-13
SHEET	1 OF 1

THIS DESIGN, IN ITS ENTIRETY, INCLUDING GROUND REINFORCEMENT PLANS, DETAILS AND ENGINEERING CALCULATIONS FOR GROUND SUPPORT CLASSIFICATIONS PROVIDED BY LANGSTON & ASSOCIATES TO CLIMAX AND HENDERSON DURING PHASE I TUNNELING OPERATIONS. REFINEMENTS TO THE GROUND SUPPORT PLANS AND DETAILS ARE REQUIREMENTS OF CLIMAX MOLYBDENUM CORPORATION.


RMR CLASS VI GROUND SUPPORT
EXTREMELY POOR GROUND UP TO 12' WIDE



TUNNEL CROSS-SECTION SPILING DETAIL



TUNNEL CROSS-SECTION VIEW



PLAN VIEW OF BACK

RIB SUPPORT

-THREE ROWS 7 FT ROCK REINFORCEMENT


- TOP ROWS BOLTS INSTALLED 2 FT ABOVE 8 FT SPRING LINE
- MID ROWS BOLTS INSTALLED 1 FT BELOW 8 FT SPRING LINE
- LOWER ROWS BOLTS INSTALLED 4 FT OFF SILL
- LOWEST ROW BOLTS INSTALLED 18 IN FROM SILL TO ANCHOR STEEL SETS

THREE ROWS: 7 FT, 24 TONNE SWELLEX BOLTS AS SHOWN

PRE-SUPPORT ON ADVANCE

- INSTALL 12 FT #9 THREADBAR SPILING ON 12 IN CENTERS AROUND PERIMETER AS SHOWN
- 6 FT MAXIMUM ROUND LENGTH ON ADVANCE THEN INSTALL ANOTHER ROUND OF SPILING AND ARCHED STEEL SETS

NOTE: TYPICAL TUNNEL AS-BUILT LINE




LONG SECTION VIEW OF RIBS


- 1) INITIAL ROCK REINFORCEMENT
-7 FT, 39mm SPLIT SET BOLTS ON A SYSTEMATIC 4 FT GRID WITH WELDED WIRE REINFORCEMENT INSTALLED UPON INITIAL EXCAVATION.
- 2) INITIAL SURFACE SUPPORT
-MINIMUM 3 IN SHOTCRETE APPLIED PRIOR TO FINAL ROCK REINFORCEMENT ON ENTIRE EXCAVATION PERIMETER.
- 3) FINAL ROCK REINFORCEMENT
-INSTALL 7 FT, 24 TONNE SWELLEX BOLTS ON A SYSTEMATIC 4 FT GRID BETWEEN SHOTCRETE LAYERS AS SHOWN.
-INSTALL W6X25 ARCHED STEELS SETS ON 2 FT CENTERS AS SHOWN.
- 4) FINAL SURFACE SUPPORT
-MINIMUM 3 IN SHOTCRETE APPLIED AFTER FINAL ROCK REINFORCEMENT ON ENTIRE EXCAVATION PERIMETER.

NOTE: RRS ARCHES MAY BE SUBSTITUTED WITH DESIGN SUBMITTAL APPROVAL.

- 7 FT, 39mm SPLIT SET BOLT WITH PLATE
- 7 FT, 24 TONNE SWELLEX BOLT WITH PLATE



REV	DESCRIPTION OF REVISION	BY	DATE
1	ISSUED FOR CONSTRUCTION	RLM	4/19
2	ISSUED FOR BID	RLM	10/18
3	ISSUED FOR CLIENT REVIEW	RLM	9/18




DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
TYPICAL GROUND SUPPORT DETAILS
RMR CLASS VI GROUND


REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-14
SHEET	1 OF 1

RMR CLASS I & II GROUND SUPPORT
GOOD GROUND 12 FT - 20 FT WIDE

THIS DESIGN, IN ITS ENTIRETY, INCLUDING GROUND REINFORCEMENT PLANS, DETAILS AND ENGINEERING CALCULATIONS FOR GROUND SUPPORT CLASSIFICATIONS PROVIDED BY LANGSTON & ASSOCIATES TO CLIMAX AND HENDERSON DURING PHASE I TUNNELING OPERATIONS. REFINEMENTS TO THE GROUND SUPPORT PLANS AND DETAILS ARE REQUIREMENTS OF CLIMAX MOLYBDENUM CORPORATION.



TUNNEL CROSS-SECTION VIEW



PLAN VIEW OF BACK

ROCK REINFORCEMENT IN BACK

- 12 FT COATED 24T INFLATABLE BOLTS ACROSS ENTIRE SPAN IN BACK ON A 6 FT X 4 FT STAGGERED GRID AS SHOWN
- 7 FT, 46mm GALVANIZED SPLIT SET BOLTS ON A SYSTEMATIC 4 FT GRID
- OTE SPANS WIDER THAN 20 FT MAY REQUIRE CABLE BOLTS

SURFACE SUPPORT

- MINIMUM 3 IN SHOTCRETE APPLIED TO ENTIRE EXCAVATION PRIOR TO ROCK REINFORCEMENT


RIB SUPPORT

- THREE ROWS 7 FT ROCK REINFORCEMENT
- ER ROWS BOLTS INSTALLED 2 FT ABOVE 8 FT SPRING LINE
- MID ROWS BOLTS INSTALLED 1 FT BELOW 8 FT SPRING LINE
- OWER ROWS BOLTS INSTALLED 4 FT OFF SILL.


7 FT, 46mm GALVANIZED SPLIT SET BOLT WITH PLATE

OTE T COATED T I T T T E O TS M E S STIT TED I TTER


12 FT COATED 24T INFLATABLE BOLT WITH PLATE



LONG SECTION VIEW OF RIBS



ISSUED FOR CONSTRUCTION	RLM	4/19
ISSUED FOR BID	RLM	10/18
ISSUED FOR CLIENT REVIEW	RLM	9/18
REV	DESCRIPTION OF REVISION	BY DATE




DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
TYPICAL GROUND SUPPORT DETAILS
RMR CLASS I-II GROUND 12-20 FT WIDE


REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-15
SHEET	1 OF 1

RMR CLASS III GROUND SUPPORT
FAIR GROUND 12- 20 FT WIDE

THIS DESIGN, IN IT'S ENTIRETY, INCLUDING GROUND REINFORCEMENT PLANS, DETAILS AND ENGINEERING CALCULATIONS FOR GROUND SUPPORT CLASSIFICATIONS PROVIDED BY LANGSTON & ASSOCIATES TO CLIMAX AND HENDERSON DURING PHASE I TUNNELING OPERATIONS. REFINEMENTS TO THE GROUND SUPPORT PLANS AND DETAILS ARE REQUIREMENTS OF CLIMAX MOLYBDENUM CORPORATION.



TUNNEL CROSS-SECTION VIEW



PLAN VIEW OF BACK

ROCK REINFORCEMENT IN BACK

- 12 FT COATED 24T INFLATABLE BOLTS ACROSS ENTIRE SPAN IN BACK ON A 6 FT X 4 FT STAGGERED GRID AS SHOWN
- 7 FT, 46mm GALVANIZED SPLIT SET BOLTS ON A SYSTEMATIC 4 FT GRID
- NOTE SPANS WIDER THAN 20 FT MAY REQUIRE CABLE BOLTS

SURFACE SUPPORT

- MINIMUM 3 IN SHOTCRETE APPLIED TO ENTIRE EXCAVATION PRIOR TO ROCK REINFORCEMENT

RIB SUPPORT

- THREE ROWS 7 FT ROCK REINFORCEMENT, 1 ROW 12 FT ROCK REINFORCEMENT AS SHOWN ABOVE

UPPER ROWS BOLTS INSTALLED 2 FT ABOVE 8 FT SPRING LINE

MID ROWS BOLTS INSTALLED 1 FT BELOW 8 FT SPRING LINE


8 FT COATED INFLATABLE BOLTS INSTALLED AT SPRING LINE

LOWER ROWS BOLTS INSTALLED 4 FT OFF SILL


7 FT, 46mm GALVANIZED SPLIT SET BOLT WITH PLATE

NOTE NOT COATED NOT INSTALLED IN STITCHED IN PATTERN


12 FT COATED 24T INFLATABLE BOLT WITH PLATE



LONG SECTION VIEW OF RIBS



REV	DESCRIPTION OF REVISION	BY	DATE
1	ISSUED FOR CONSTRUCTION	RLM	4/19
2	ISSUED FOR BID	RLM	10/18
3	ISSUED FOR CLIENT REVIEW	RLM	9/18




DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
TYPICAL GROUND SUPPORT DETAILS
RMR CLASS III GROUND 12-20 FT WIDE

REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-16
SHEET	1 OF 1

THIS DESIGN, IN ITS ENTIRETY, INCLUDING GROUND REINFORCEMENT PLANS, DETAILS AND ENGINEERING CALCULATIONS FOR GROUND SUPPORT CLASSIFICATIONS PROVIDED BY LANGSTON & ASSOCIATES TO CLIMAX AND HENDERSON DURING PHASE I TUNNELING OPERATIONS. REFINEMENTS TO THE GROUND SUPPORT PLANS AND DETAILS ARE REQUIREMENTS OF CLIMAX MOLYBDENUM CORPORATION.

THREE WAY INTERSECTION GROUND SUPPORT
RMR GROUND CLASS I - III



ROCK REINFORCEMENT IN BACK
- 12 FT COATED INFLATABLE BOLTS ACROSS ENTIRE SPAN IN BACK ON A STAGGERED 4' X 6' GRID
- 7 FT, 46mm GALVANIZED SPLIT SET BOLTS ON A SYSTEMATIC 4' GRID
NOTE: SPACINGS WIDER THAN 6' MAY REQUIRE CLOSERS

SURFACE SUPPORT
- MINIMUM 3 IN SHOTCRETE APPLIED TO ENTIRE EXCAVATION PRIOR TO ROCK REINFORCEMENT

RIB SUPPORT
AS SHOWN IN SUPPORT STANDARD DRAWINGS

- 7 FT, 46mm GALVANIZED SPLIT SET BOLT WITH PLATE
- △ 12 FT COATED 24T INFLATABLE BOLT WITH PLATE

△			
△			
△	ISSUED FOR CONSTRUCTION	RLM	4/19
△	ISSUED FOR BID	RLM	10/18
△	ISSUED FOR CLIENT REVIEW	RLM	9/18
REV	DESCRIPTION OF REVISION	BY	DATE






WARNING
0 0.5 1
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE


DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
TYPICAL GROUND SUPPORT DETAILS
3-WAY TUNNEL INTERSECTION RMR CLASS I-III

REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-17
SHEET	1 OF 1






△			
△			
△	ISSUED FOR CONSTRUCTION	RLM	4/19
△	ISSUED FOR BID	RLM	10/18
△	ISSUED FOR CLIENT REVIEW	RLM	9/18
REV	DESCRIPTION OF REVISION	BY	DATE



DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
TYPICAL TUNNEL INTERSECTION DETAILS
FUTURE SPUR INTERSECTIONS

REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-18
SHEET	1 OF 1



△			
△			
△	ISSUED FOR CONSTRUCTION	RLM	4/19
△	ISSUED FOR BID	RLM	10/18
△	ISSUED FOR CLIENT REVIEW	RLM	9/18
REV	DESCRIPTION OF REVISION	BY	DATE



WARNING

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19




CLIMAX MINE

MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM

TYPICAL TUNNEL CUTOUT DETAILS

ELECTRICAL SUBSTATION

REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-19
SHEET	1 OF 1



△			
△			
△	ISSUED FOR CONSTRUCTION	RLM	4/19
△	ISSUED FOR BID	RLM	10/18
△	ISSUED FOR CLIENT REVIEW	RLM	9/18
REV	DESCRIPTION OF REVISION	BY	DATE




WARNING

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE


DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
TYPICAL TUNNEL CUTOUT DETAILS
SAFETY BAY



REVISION	△
PROJECT NO.	12235
DRAWING	MFT-C-20
SHEET	1 OF 1



TYPICAL GROUT HOLE PROFILE



TYPICAL PROBE/GROUT HOLE CROSS-SECTION GEOMETRY



REV	DESCRIPTION OF REVISION	BY	DATE
1	ISSUED FOR CONSTRUCTION	RLM	4/19
2	ISSUED FOR BID	RLM	10/18
3	ISSUED FOR CLIENT REVIEW	RLM	9/18



WARNING
0 0.5 1
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	VARIOUS
DRAWN	RLM
CHECKED	AJH
REVIEWED	DL
CLIENT	MM/RV
DATE	4/5/19

CLIMAX MINE
MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM
TYPICAL PROBE HOLE AND GROUT HOLE GEOMETRY

REVISION	2
PROJECT NO.	12235
DRAWING	MFT-C-21
SHEET	1 OF 1

AutoCAD FILE: MFT Stage II Construction.dwg

MAYFLOWER FLOOD BYPASS TUNNEL PHASE II VERTICAL INTAKE STRUCTURE GROUND STABILIZATION CONSTRUCTION PLANS

CLIMAX, COLORADO

PREPARED FOR
CLIMAX MOLYBDENUM COMPANY

PREPARED BY
AECOM
MAY 2019

AECOM

PROJECT
PHASE II VERTICAL
INTAKE STRUCTURE

CLIENT

Climax Molybdenum
A Freeport-McMoRan Company

CONSULTANT

AECOM
804 COLORADO AVE.
Suite 201
GLENWOOD SPRINGS, CO. 81601

www.aecom.com

CONSULTANTS

REGISTRATION



KEY PLAN

PROJECT NUMBER


60591226

SHEET TITLE


COVER SHEET

SHEET NUMBER

G-01



STATE MAP
NOT TO SCALE



VICINITY MAP
NOT TO SCALE

SHEET INDEX	
DRAWING NO.	DESCRIPTION
G-01	COVER SHEET WITH VICINITY MAP, PROJECT LOCATION AND DRAWING INDEX
G-02	GENERAL NOTES, LEGEND AND ABBREVIATIONS
C-02	PROPOSED ALIGNMENTS AND STAGING AREAS
C-03	VERTICAL TOWER INTAKE PLAN
C-04	VERTICAL TOWER INTAKE PROFILE
C-05	VERTICAL TOWER INTAKE WALL SECTIONS
C-06	STABILIZATION AND FOUNDATION EXCAVATION
C-07	STABILIZATION DETAILS
C-08	DRAINAGE DETAILS

PROJECT DESIGN TEAM APPROVALS

AECOM PROJECT MANAGER
DESIGN

John Sikora
John Sikora, P.E.

05/20/2019
DATE

CLIMAX PROJECT MANAGER
CONSTRUCTION OVERSIGHT

Miles McElhinney
Miles McElhinney, P.E.

5/20/19
DATE

ABBREVIATIONS

APPROX.	APPROXIMATE	N	NORTHING
AC-FT	ACRE - FEET	NO.	NUMBER
BOH	BOTTOM OF HOLE	NA	NOT APPLICABLE
BOW	BOTTOM OF WALL	O.C.	ON CENTER
CFS	CUBIC FEET PER SECOND	O.W.	OUTLET WORKS
CL	CENTERLINE	PC	POINT OF CURVATURE
DIA.	DIAMETER	PM	MINTURN FORMATION
D/S	DOWNSTREAM	PT	POINT OF TANGENCY
E	EASTING	PVI	POINT OF VERTICAL INTERSECTION
EA.	EACH	Qal	ALLUVIUM
ELEV, EL.	ELEVATION	Qm	MORaine
EOC	EDGE OF CONCRETE	R	RADIUS
EST.	ESTIMATED	S	SLOPE, FT./FT.
EX.	EXAMPLE	STA.	STATION
EXIST.	EXISTING	STD	STANDARD
FT.	FEET	Ti	INTRUSIVE COMPLEX
FTG.	FOOTING	TH	TEST HOLE
GDR	GEOTECHNICAL DATA REPORT	TOW	TOP OF WALL
GBR	GEOTECHNICAL BASELINE REPORT	TP	TEST PIT
H, HORIZONTAL	HORIZONTAL	TYP.	TYPICAL
IN.	INCHES	U/S	UPSTREAM
INV.	INVERT	V, VERT	VERTICAL
Ld	DEVELOPMENT LENGTH	WL	WATER LEVEL
MAX.	MAXIMUM	WS	WATERSTOP
MIN.	MINIMUM	WSE	WATER SERVICE ELEVATION
M.E.	MATCH EXISTING		

GENERAL NOTES:

- GROUND SURFACE TOPOGRAPHY COMPILED FROM 2010 URS SURVEY (SEPTEMBER 2010) MERGED WITH 2006 AND 2013 BASE TOPOGRAPHY PROVIDED BY CLIMAX.
- GEOLOGY HAS BEEN INTERPRETED USING PUBLISHED REPORTS AND MAPS, AND DATE COLLECTED FROM VARIOUS FIELD INVESTIGATIONS. SURFACE AND BEDROCK GEOLOGY MAY VARY DURING EXCAVATION AND CONSTRUCTION. SEE MAYFLOWER TUNNEL GDR AND GBR (URS 2012) FOR ADDITIONAL INFORMATION.
- ALL TUNNEL CONSTRUCTION ACTIVITIES MUST COMPLY WITH THE STORM WATER MANAGEMENT PLAN "MAYFLOWER FLOOD BYPASS TUNNEL SYSTEM STORM WATER MANAGEMENT PLAN", DRAWING NOS. SWMP-01, SWMP-02, SWMP-03, AND SWMP-04.

LEGEND

	EXISTING UTILITY POLE
	APPROXIMATE LOCATION OF VERTICAL TEST HOLE (URS, 2011)
	APPROXIMATE LOCATION OF INCLINED TEST HOLE (URS, 2011)
	APPROXIMATE LOCATION OF TEST PIT (URS, 2011)
	SEISMIC LINE SL1
	VERTICAL TEST HOLE BY HENDERSON, 2012
	HORIZONTAL TEST HOLE BY URS, 2012
	INDICATES CROSS SECTION LOCATION. B REFERS TO THE CROSS SECTION DESIGNATION. C-02 REFERS TO THE DRAWING NUMBER WHERE THE SECTION IS SHOWN. WHEN SHOWN ON THE SECTION LABEL, THIS NUMBER REFERS TO THE DRAWING NUMBER WHERE THE SECTION IS CUT.
	INDICATES DETAIL LOCATION. 1 REFERS TO THE DETAIL DESIGNATION. C-04 REFERS TO THE DRAWING NUMBER WHERE THE DETAIL IS SHOWN. WHEN SHOWN ON THE DETAIL, THIS NUMBER REFERS TO THE DRAWING NUMBER WHERE THE DETAIL IS TAKEN.
	INDEX CONTOURS (10' INTERVAL)
	INTERMEDIATE CONTOURS (2' INTERVAL)
	FINAL GRADING CONTOURS (10' INTERVAL)
	FINAL GRADING CONTOURS (2' INTERVAL)
	INDICATES DIRECTION OF FLOW
	EXISTING FENCE
	WATER SURFACE
	PROPOSED SURVEY BENCHMARK
	EXISTING HOUSE OR STRUCTURE
	CULVERT
	TREE LINE/SHRUB
	GAS METER
	FILL SLOPE
	CUT SLOPE
	GUY WIRE
	POWER POLE
	UTILITY MARKER
	TELEPHONE RISER BOX

	UE	UNDERGROUND ELECTRIC LINE
	FO	UNDERGROUND FIBER OPTIC LINE
	OT	UNDERGROUND TELEPHONE LINE
	OHE	OVERHEAD ELECTRIC LINE

	EXISTING SOIL OR GRADE
	LIMIT OF SOIL EXCAVATION
	ESTIMATED BEDROCK SURFACE
	CONCRETE



PROJECT

PHASE II VERTICAL INTAKE STRUCTURE

CLIENT



CONSULTANT

AECOM
804 COLORADO AVE.
Suite 201
GLENWOOD SPRINGS, CO. 81601

www.aecom.com

CONSULTANTS

REGISTRATION



PLAN

PROJECT NUMBER

60591226

SHEET TITLE

GENERAL NOTES,
LEGEND AND
ABBREVIATIONS


SHEET NUMBER

G-02

Pro act Management Initials: _____ Designer: _____ Checker: _____ Approver: _____
ANSI D 22" x 34"

Last saved by: MICHAEL RAU (2019-05-20) Last Plotted: 2019-05-20
Filename: M:\DCSP\PROJECTS\WTR60591226 CLX\WY2000 CAD GIS\910 CAD\20-SHEETS\C-02 PROPOSED ALIGNMENTS AND STAGING AREAS.DWG

Printed on _____ Post-Consumer Recycled Content Paper



PLAN VIEW



LEGEND:

- STAGING AREA
- SPOIL/MUCK DISPOSAL AREA
- REGRAIDING OF DAM FACE
- TUNNEL ALIGNMENT STAGE 1
- ANTICIPATED ACCESS ROADS DURING CONSTRUCTION
- APPROXIMATE LOCATIONS OF PROPOSED SURVEY BENCHMARKS/CONTROL

AECOM

PROJECT

PHASE II VERTICAL
INTAKE STRUCTURE

CLIENT

Climax Molybdenum
A Freeport-McMoRan Company

CONSULTANT

AECOM
804 COLORADO AVE.
Suite 201
GLENWOOD SPRINGS, CO. 81601

www.aecom.com

CONSULTANTS

REGISTRATION



PLAN

PROJECT NUMBER


60591226

SHEET TITLE

PROPOSED ALIGNMENTS
AND STAGING AREAS

SHEET NUMBER

C-02



PROJECT

PHASE II VERTICAL INTAKE STRUCTURE

CLIENT

CONSULTANT

AECOM
804 COLORADO AVE.
Suite 201
GLENWOOD SPRINGS, CO. 81601

www.aecom.com

CONSULTANTS

REGISTRATION



PLAN

PROJECT NUMBER


60591226

SHEET TITLE

VERTICAL TOWER INTAKE PLAN

SHEET

C-03



GENERAL NOTES:

1. ROCK SLOPE AND SOIL NAIL SHORING WALL BATTER APPROXIMATELY 1H:10V.
2. REINFORCED SHOTCRETE FACING USING WELDED WIRE MESH, STRIP DRAINS ON 4' CENTERS, 6" SHOTCRETE THICKNESS.
3. SOIL NAILS - NO. 8 WILLIAMS THREADBAR, FULLY GROUTED AND CENTRALIZED, 15-DEG. INCLINATION FROM HORIZONTAL, 5X5' STAGGERED PATTERN FIRST ROW OF NAILS 1-FT. BELOW BROW, SEE DETAIL C-06.

AECOM

PROJECT

**PHASE II VERTICAL
INTAKE STRUCTURE**

CLIENT

Climax Molybdenum
A Freeport-McMoRan Company

CONSULTANT

AECOM
804 COLORADO AVE.
Suite 201
GLENWOOD SPRINGS, CO. 81601

www.aecom.com

CONSULTANTS

REGISTRATION



PLAN

PROJECT NUMBER


60591226

SHEET TITLE

VERTICAL TOWER INTAKE PROFILE

SHEET

C-04




GENERAL NOTES:

1. ROCK SLOPE AND SOIL NAIL SHORING WALL BATTER APPROXIMATELY 1H:10V.
2. REINFORCED SHOTCRETE FACING USING WELDED WIRE MESH, STRIP DRAINS ON 4' CENTERS, 6" SHOTCRETE THICKNESS.
3. SOIL NAILS - NO. 8 WILLIAMS THREADBAR, FULLY GROUTED AND CENTRALIZED, 15-DEG. INCLINATION FROM HORIZONTAL, 5' X 5' STAGGERED PATTERN FIRST ROW OF NAILS 1-FT. BELOW BROW, SEE DETAIL C-06.

TOWER INTAKE SOIL NAIL WALL AND ROCK BOLT WALL PROFILE



B
C-03



AECOM

PROJECT

**PHASE II VERTICAL
INTAKE STRUCTURE**

CLIENT

Climax Molybdenum
A Freeport-McMoRan Company

CONSULTANT

AECOM
804 COLORADO AVE.
Suite 201
GLENWOOD SPRINGS, CO. 81601

www.aecom.com

CONSULTANTS

REGISTRATION



PLAN

PROJECT NUMBER


60591226

SHEET TITLE


TOWER INTAKE WALL PROFILE

SHEET

C-05



RAISED BORE FOUNDATION



TOWER/RAISED BORE FOUNDATION



GENERAL NOTES:

1. ROCK SLOPE AND SOIL NAIL SHORING WALL BATTER APPROXIMATELY 1H:10V.
2. REINFORCED SHOTCRETE FACING USING WELDED WIRE MESH, STRIP DRAINS ON 4' CENTERS, 6" SHOTCRETE THICKNESS.
3. SOIL NAILS - NO. 8 WILLIAMS THREADBAR, FULLY GROUTED AND CENTRALIZED, 15-DEG. INCLINATION FROM HORIZONTAL, 5X5' STAGGERED PATTERN FIRST ROW OF NAILS 1-FT. BELOW BROW, SEE DETAIL C-06.

AECOM

PROJECT

PHASE II VERTICAL
INTAKE STRUCTURE

CLIENT

Climax Molybdenum
A Freeport-McMoRan Company

CONSULTANT

AECOM
804 COLORADO AVE.
Suite 201
GLENWOOD SPRINGS, CO. 81601

www.aecom.com

CONSULTANTS

REGISTRATION



PLAN

PROJECT NUMBER



60591226

SHEET TITLE


STABILIZATION AND FOUNDATION
EXCAVATION

SHEET

C-06



NOTES:
MESH INSTALLED ON ROCK CUT OF INLET PORTAL AS DIRECTED BY ENGINEER.



GEOCOMPOSITE STRIP DRAINAGE DETAIL

SOIL NAIL WALL, TUNNEL LINER AND ROCK SLOPE STABILIZATION
NOT TO SCALE

VERIFICATION TEST SCHEDULE


Load	Hold Time
AL(.05 DL max)	1 Minute
0.25DL	10 Minute
0.50DL	10 Minute
0.75DL	10 Minute
1.00DL	10 Minute
1.25DL	10 Minute
1.50DL (creep test)	60 Minute
1.75DL	10 Minute
2.00DL (max. test load)	10 Minute

AL - alignment load
DL - ground nail design load

PROOF TEST SCHEDULE


Load	Hold Time
AL(.05 DL max)	Until Stable
0.25DL	Until Stable
0.50DL	Until Stable
0.75DL	Until Stable
1.00DL	Until Stable
1.25DL	Until Stable
1.33DL(max. test load)	10 Minute

AL - alignment load
DL - ground nail design load




TYPICAL ROCK BOLT/SHOTCRETE ANCHORAGE DETAIL

OPTION A - DOUBLE NUT & PLATE
NOT TO SCALE



TYPICAL ROCK BOLT/SHOTCRETE ANCHORAGE DETAIL

OPTION B - NELSON STUD PLATES
NOT TO SCALE



PROJECT

PHASE II VERTICAL INTAKE STRUCTURE

CLIENT



CONSULTANT

AECOM
804 COLORADO AVE.
Suite 201
GLENWOOD SPRINGS, CO. 81601

www.aecom.com

CONSULTANTS

REGISTRATION



PLAN

PROJECT NUMBER


60591226

SHEET TITLE

SIDE HILL INTAKE SOIL STABILIZATION DETAILS

SHEET NUMBER

C-07



April 18, 2019

Ms. Diana Kelts
Climax Molybdenum Company- Climax Mine
Highway 91 – Fremont Pass
Climax, CO 80429

Subject: REV 0 – Mayflower Tailings Storage Facility Leadoff Clarification, Climax Mine,
Permit No. M-1977-493

Dear Ms. Kelts:

AECOM, through its legacy company URS Corporation, serves as the Engineer of Record (EOR) for the Mayflower Tailings Storage Facility (TSF) at the Climax Mine, located near Fremont Pass Colorado. It is our understanding that DRMS has requested clarification on the number of leadoffs required following a submittal by Climax showing the proposed 5 Dam crest raise configuration prepared by W. W. Wheeler & Associates, Inc. (Wheeler). On this drawing it showed increasing the number of leadoffs from three to four.

Leadoff Clarification

The *Mayflower Tailings Storage Facility and 5 Dam Operations and Maintenance Manual (O&M), Revision 1.1 plan dated May 2014* discusses leadoffs and the use of leadoffs several times throughout the O&M manual. Leadoffs are used for winter deposition to fill in storage created during the summer months. One reference in the O&M manual under Section 4.5.2 discusses and shows in Figure 3-2 three leadoffs for the Mayflower TSF at startup.

The three leadoffs referenced in the O&M manual depicts conditions at startup and was not meant to imply only three leadoffs should be used throughout the life of the TSF. As the dam is raised, the crest length will continue to increase and the number of leadoffs (plus location) will need to be adjusted to effectively fill the storage developed through the spigot season. The plan developed by Wheeler titled “2019 5 Dam Crest Line Raise, General Arrangement” dated 12/18 has increased the number of leadoffs to four leadoffs in accordance with this approach.

General information and Closing

AECOM represents that our services are performed within the limits prescribed by the Client in a manner consistent with the level and skill ordinarily exercised by other consultants under similar circumstances. No representation to the Client, expressed or implied, and no other warranty or guarantee is included or intended.



Ms. Diana Kelts
Climax Molybdenum Company
April 18, 2019
Page 2

Please do not hesitate to call us with any questions or comments.

Sincerely,


A handwritten signature in blue ink, appearing to read "Lisa Yenne".

Lisa R. Yenne, PE
Project Manager


A handwritten signature in blue ink, appearing to read "Richard Davidson".

Richard R. Davidson, PE
Senior Principal Engineer



INTERCEPTOR REHABILITATION PROJECT
WEST INTERCEPTOR CULVERT REPLACEMENT (PHASE D)
DOWNSTREAM OF SEARLE GULCH
CLIMAX MINE
CLIMAX, CO



DRAWING INDEX	
DRAWING NO.	DRAWING TITLE
GENERAL	
3-520-00401	COVER SHEET, DRAWING INDEX, AND LOCATION MAP
3-520-00402	WEST INTERCEPTOR - GENERAL ARRANGEMENT - SITE PLAN
CIVIL	
3-520-00403	CHDPE CULVERT - PLAN & PROFILE - STA. 160+00 TO 169+00
3-520-00404	CHDPE CULVERT - PLAN & PROFILE - STA. 169+00 TO 178+00
3-520-00405	CHDPE CULVERT - PLAN & PROFILE - STA. 178+00 TO 187+00
3-520-00406	CHDPE CULVERT - PLAN & PROFILE - STA. 187+00 TO 196+00
3-520-00407	CHDPE CULVERT - PLAN & PROFILE - STA. 196+00 TO END
3-520-00408	CULVERT TRENCH & SEEPAGE BARRIER - PLANS, SECTIONS, & DETAILS
3-520-00409	CULVERT INLET STRUCTURE - CIVIL PLANS, SECTIONS, & DETAILS
3-520-00410	TRANSITION STRUCTURE - CIVIL PLANS, SECTIONS, & DETAILS
3-520-00411	DRAINAGE INLETS & GABIONS - TYPICAL PLAN, SECTIONS, & DETAIL
STRUCTURAL	
3-520-00412	CULVERT DRAINAGE INLETS - STRUCTURAL PLAN, SECTIONS, & DETAILS
3-520-00413	CULVERT INLET STRUCTURE - STRUCTURAL PLANS, SECTIONS, & DETAILS
3-520-00414	TRANSITION STRUCTURE - STRUCTURAL PLANS, SECTIONS, & DETAILS
3-520-00415	TRANSITION STEEL REDUCER DETAILS
3-520-00416	MISCELLANEOUS STRUCTURAL DETAILS




R:\1000\10611051.07.02\DRAWINGS\Phase D - West Int. Pipeline DS of Searle (2018)\FC\SheetFiles\10510702D-001_4-05-19_04:08pm_DwgM_XREFS: Climax24x36 20111229_SMM_Climax_4C

REVISIONS	NO.	DATE	MADE BY	CHKD. BY	REMARKS	"This drawing together with any and all additions, corrections, changes and alterations thereof is the property of Climax Molybdenum Company and is furnished on the express condition that it shall not be reproduced, copied, lent, or disposed of directly or indirectly, nor used for any other purpose than for which it is specifically furnished without the prior written consent of said Climax Molybdenum Company."	REFERENCE DWGS	DRAWING NO.	REFERENCE		 Climax Molybdenum A Freeport-McMoRan Company	INTERCEPTOR REHABILITATION PROJECT		Climax Molybdenum Climax Mine Climax, CO		
	△	05/18	TEM	SMM	ISSUED FOR BID							WEST INTERCEPTOR CULVERT REPLACEMENT (PHASE D)		MADE BY DCM	9/1/16	SCALE As Noted
	△	03/19	DCM	SMM	ISSUED FOR CONSTRUCTION									CHECKED BY SMM	12/16/16	DRAWING NO. 3-520-00401
	△											COVER SHEET		ACCEPTED BY ...		
	△											DRAWING INDEX, LOCATION MAP				
	△															
								 W. W. WHEELER & ASSOCIATES, INC. Water Resources Engineers	3700 S. INCA STREET ENGLEWOOD, CO 80110-3405 303-761-4130 FAX 303-761-2802							

R:\1000\10611061\07.02\DRAWINGS\Phase D - West Int. Pipeline DS of Searle (2018)\FCISheetFiles\10510702D-002 3-29-19 03:29pm Scott.XREFS.Climax24x36 29400 Climax Mine Interior with lidar water 4.5 Climax 4C

CONTROL POINT TABLE			
POINT	NORTHING	EASTING	ELEVATION
WS2	23940.89	655.14	10974.61
GS-136	23888.50	3405.40	10771.37
WS3	21737.32	7340.12	11101.52



REVISIONS	NO.	DATE	MADE BY	CKD. BY	REMARKS
	△	05/18	TEM	SMM	ISSUED FOR BID
	△	03/19	DCM	SMM	ISSUED FOR CONSTRUCTION
	△				
	△				
	△				
	△				

"This drawing together with any and all additions, corrections, changes and alterations thereof is the property of Climax Molybdenum Company and is furnished on the express condition that it shall not be reproduced, copied, lent, or disposed of directly or indirectly, nor used for any other purpose than for which it is specifically furnished without the prior written consent of said Climax Molybdenum Company."

REFERENCE DWGS	DRAWING NO.	REFERENCE



Climax Molybdenum
A Freeport-McMoRan Company




W. W. WHEELER & ASSOCIATES, INC.
Water Resources Engineers

3700 S. INDA STREET
ENGLEWOOD, CO 80110-3405
303-761-4130
FAX 303-761-2802

INTERCEPTOR REHABILITATION PROJECT		Climax Molybdenum Climax Mine Climax, CO		
WEST INTERCEPTOR CULVERT REPLACEMENT (PHASE D)		MADE BY DCM	9/1/16	SCALE As Noted
GENERAL ARRANGEMENT		CHECKED BY SMM	12/1/16	DRAWING NO.
SITE PLAN		ACCEPTED BY ...		3-520-00402

R:\1000\10611061\07\02\DRAWINGS\Phase D - West Int. Pipeline DS of Searle (2018)\Climax Mine Interior with Lidar water 4.5; Climax 4C; 3-29-19 03:30pm Scott XREFS: Climax2438; 29400



- NOTES:
1. HORIZONTAL AND VERTICAL CONTROL DATA IS BASED ON CLIMAX COORDINATE SYSTEM.
 2. CONTRACTOR IS RESPONSIBLE FOR UTILITY LOCATES.
 3. BASE TOPOGRAPHY MAPPING FROM AERO-METRIC, INC. SEPT. 2006 AERIAL SURVEY.
 4. MINOR FIELD ADJUSTMENTS OF ALIGNMENT ALLOWED WITH FIELD ENGINEER'S APPROVAL.
 5. VERTICAL ALIGNMENT OF TOP OF NEW 60" DIA. PIPE TO APPROXIMATELY MATCH ELEVATION OF EXISTING 46" PIPE.
 6. INVERT OF NEW 60" DIA. PIPE AT INLET STRUCTURE APPROX. 1.5' LOWER THAN EXISTING PIPE INVERT.

REVISIONS	NO.	DATE	MADE BY	CHKD. BY	REMARKS
	1	05/18	TEM	SMM	ISSUED FOR BID
	2	03/19	DCM	SMM	ISSUED FOR CONSTRUCTION
	3				
	4				
	5				
	6				

"This drawing together with any and all additions, corrections, changes and alterations thereof is the property of Climax Molybdenum Company and is furnished on the express condition that it shall not be reproduced, copied, lent, or disposed of directly or indirectly, nor used for any other purpose than for which it is specifically furnished without the prior written consent of said Climax Molybdenum Company."

REFERENCE DWGS	DRAWING NO.	REFERENCE



Climax Molybdenum
A Freeport-McMoRan Company




W. W. WHEELER & ASSOCIATES, INC.
Water Resources Engineers


3700 S. INDA STREET
ENGLEWOOD, CO 80110-3405
303-761-4130
FAX 303-761-2802

INTERCEPTOR REHABILITATION PROJECT		Climax Molybdenum Climax Mine	
WEST INTERCEPTOR CULVERT REPLACEMENT (PHASE D)		MADE BY DCM	9/1/16
PLAN AND PROFILE		CHECKED BY SMM	12/1/16
STA. 160+00 TO 169+00		ACCEPTED BY ...	
		SCALE As Noted	DRAWING NO. 3-520-00403

R:\100\00\1108\11081\07\1051_07_02\DRAWINGS\Phase D - West Int. Pipeline DS of Seale (2018)\11081\07\1051_07_02\02-D-002 3-29-19 03:31pm Scott_XREFS.Climax24x36 29x00 Climax Mine Interior with lidar water 4.5 Climax 4C



HORIZONTAL ALIGNMENT OF NEW 60" PIPE TO FOLLOW ALIGNMENT OF EXISTING 46" PIPE. EXPOSE EXISTING PIPE AT 100' INTERVALS AND SURVEY PRIOR TO REMOVAL. FIELD ADJUSTMENTS MUST BE APPROVED BY THE ENGINEER.



- NOTES:
1. HORIZONTAL AND VERTICAL CONTROL DATA IS BASED ON CLIMAX COORDINATE SYSTEM.
 2. CONTRACTOR IS RESPONSIBLE FOR UTILITY LOCATES.
 3. BASE TOPOGRAPHY MAPPING FROM AERO-METRIC, INC. SEPT. 2006 AERIAL SURVEY.
 4. MINOR FIELD ADJUSTMENTS OF ALIGNMENT ALLOWED WITH FIELD ENGINEER'S APPROVAL.
 5. VERTICAL ALIGNMENT OF TOP OF NEW 60" PIPE TO MATCH ELEVATION OF EXISTING 46" PIPE.

REVISIONS	NO.	DATE	MADE BY	CHKD. BY	REMARKS
	△	05/18	TEM	SMM	ISSUED FOR BID
△	△	03/19	DCM	SMM	ISSUED FOR CONSTRUCTION
△					
△					
△					
△					

"This drawing together with any and all additions, corrections, changes and alterations thereof is the property of Climax Molybdenum Company and is furnished on the express condition that it shall not be reproduced, copied, lent, or disposed of directly or indirectly, nor used for any other purpose than for which it is specifically furnished without the prior written consent of said Climax Molybdenum Company."

REFERENCE DWGS	DRAWING NO.	REFERENCE



A Freeport-McMoRan Company




Water Resources Engineers

3700 S. INDA STREET
ENGLEWOOD, CO 80110-3405
303-761-4130
FAX 303-761-2802

INTERCEPTOR REHABILITATION PROJECT		Climax Molybdenum Climax Mine	
WEST INTERCEPTOR CULVERT REPLACEMENT (PHASE D)		MADE BY DCM	9/1/16
PLAN AND PROFILE		CHECKED BY SMM	12/1/16
STA. 169+00 TO 178+00		ACCEPTED BY ...	As Noted
			DRAWING NO.
			3-520-00404

R:\1000\10611061\07\1061_07\02\DRAWINGS\Phase D - West Int. Pipeline DS of Seerie (2018)\FCI\Sheet\F1es10510702D-002 3-29-19 03:32pm Scott XREFS: Climax2438 29400 Climax Mine Interior with lidar water 4.5 Climax 4C



- NOTES:
1. HORIZONTAL AND VERTICAL CONTROL DATA IS BASED ON CLIMAX COORDINATE SYSTEM.
 2. CONTRACTOR IS RESPONSIBLE FOR UTILITY LOCATES.
 3. BASE TOPOGRAPHY MAPPING FROM AERO-METRIC, INC. SEPT. 2006 AERIAL SURVEY.
 4. MINOR FIELD ADJUSTMENTS OF ALIGNMENT ALLOWED WITH FIELD ENGINEER'S APPROVAL.
 5. VERTICAL ALIGNMENT OF TOP OF NEW 60" PIPE TO MATCH ELEVATION OF EXISTING 46" PIPE.

REVISIONS	NO.	DATE	MADE BY	CHKD. BY	REMARKS
	1	05/18	TEM	SMM	ISSUED FOR BID
	2	03/19	DCM	SMM	ISSUED FOR CONSTRUCTION
	3				
	4				
	5				
	6				

"This drawing together with any and all additions, corrections, changes and alterations thereof is the property of Climax Molybdenum Company and is furnished on the express condition that it shall not be reproduced, copied, lent, or disposed of directly or indirectly, nor used for any other purpose than for which it is specifically furnished without the prior written consent of said Climax Molybdenum Company."

REFERENCE DWGS	DRAWING NO.	REFERENCE



Climax Molybdenum
A Freeport-McMoRan Company





W. W. WHEELER & ASSOCIATES, INC.
Water Resources Engineers


3700 S. INDA STREET
ENGLEWOOD, CO 80110-3405
303-761-4130
FAX 303-761-2802

INTERCEPTOR REHABILITATION PROJECT		Climax Molybdenum Climax Mine	
WEST INTERCEPTOR CULVERT REPLACEMENT (PHASE D)		MADE BY DCM	9/1/16
PLAN AND PROFILE		CHECKED BY SMM	12/1/16
STA. 178+00 TO 187+00		ACCEPTED BY
		SCALE As Noted	DRAWING NO. 3-520-00405


R:\1000\1001\1051.07.02\DRAWINGS\Phase D - West Int. Pipeline DS of Seale (2018)\IFC\Sheet\1051.07.02\DWG-002 3-29-19 03:33pm Scott XREFS: Climax24x38 29400 Climax Mine Interior with lidar water 4.5 Climax 4C



- NOTES:
1. HORIZONTAL AND VERTICAL CONTROL DATA IS BASED ON CLIMAX COORDINATE SYSTEM.
 2. CONTRACTOR IS RESPONSIBLE FOR UTILITY LOCATES.
 3. BASE TOPOGRAPHY MAPPING FROM AERO-METRIC, INC. SEPT. 2006 AERIAL SURVEY.
 4. MINOR FIELD ADJUSTMENTS OF ALIGNMENT ALLOWED WITH FIELD ENGINEER'S APPROVAL.
 5. VERTICAL ALIGNMENT OF INVERT OF NEW 60" PIPE TO MATCH ELEVATION OF EXISTING 50" PIPE AT TRANSITION.

REVISIONS	NO.	DATE	MADE BY	CKD. BY	REMARKS	"This drawing together with any and all additions, corrections, changes and alterations thereof is the property of Climax Molybdenum Company and is furnished on the express condition that it shall not be reproduced, copied, lent, or disposed of directly or indirectly, nor used for any other purpose than for which it is specifically furnished without the prior written consent of said Climax Molybdenum Company."	REFERENCE DWGS	DRAWING NO.	REFERENCE		 Climax Molybdenum A Freeport-McMoRan Company	INTERCEPTOR REHABILITATION PROJECT			Climax Molybdenum Climax Mine				

R:\100\006\1108\107\1051\07\02\DRAWINGS\Phase D - West Int. Pipeline DS of Searle (2018)\IFC\Sheet\1051\07\02\003-3-28-19 03:35pm Scott.XREFS.Climax24x38 2016 July 20 03:35 Searle.Climax 4C:



- NOTES:
1. INSTALL 12 GAGE LOCATING (TRACER) WIRE ON TOP OF ALL CHDPE PIPE. DAYLIGHT MIN. 6" AT EACH END AND AT EACH INLET.
 2. INSTALL WARNING TAPE ABOVE PIPE, 12" BELOW GROUND SURFACE.
 3. BED PIPE PER PROJECT SPECIFICATION 2330: EARTHWORK.
 4. ACCESS ROAD POSITION RELATIVE TO THE CULVERT VARIES WITH STATION. ACCESS ROAD MUST REMAIN OUTSIDE OF THE MIN. LIMITS OF FINISH GRADE AROUND PIPE.

REVISIONS	NO.	DATE	MADE BY	CHKD. BY	REMARKS
	1	05/18	TEM	SMM	ISSUED FOR BID
	2	03/19	DCM	SMM	ISSUED FOR CONSTRUCTION
	3				
	4				
	5				
	6				
	7				

"This drawing together with any and all additions, corrections, changes and alterations thereof is the property of Climax Molybdenum Company and is furnished on the express condition that it shall not be reproduced, copied, lent, or disposed of directly or indirectly, nor used for any other purpose than for which it is specifically furnished without the prior written consent of said Climax Molybdenum Company."

DRAWING NO.	REFERENCE



Climax Molybdenum
A Freeport-McMoRan Company




W. W. WHEELER & ASSOCIATES, INC.
Water Resources Engineers

3700 S. INDA STREET
ENGLEWOOD, CO 80110-3405
303-761-4130
FAX 303-761-2802



INTERCEPTOR REHABILITATION PROJECT		Climax Molybdenum Climax Mine	
WEST INTERCEPTOR CULVERT REPLACEMENT (PHASE D)		MADE BY DCM	9/1/16
CULVERT TRENCH AND SEEPAGE BARRIER		CHECKED BY SMM	12/1/16
CIVIL PLANS, SECTIONS, AND DETAILS		ACCEPTED BY ...	3-520-00408

R:\1000\08\11051.07\02\DRAWINGS\Phase D - West Int. Pipeline DS of Searle (2018)\FC\Sheet\10510702D-002 3-29-19 03:36pm Scott.XREFS.Climax24x36 29400 Climax Mine Interior with lidar water 4.5 Climax 4C



1 CULVERT INLET STRUCTURE
PLAN VIEW

Scale in Feet



REVISIONS	NO.	DATE	MADE BY	CHKD. BY	REMARKS
	△	05/18	TEM	SMM	ISSUED FOR BID
	△	03/19	DCM	SMM	ISSUED FOR CONSTRUCTION
	△				
	△				
	△				
	△				

"This drawing together with any and all additions, corrections, changes and alterations thereof is the property of Climax Molybdenum Company and is furnished on the express condition that it shall not be reproduced, copied, lent, or disposed of directly or indirectly, nor used for any other purpose than for which it is specifically furnished without the prior written consent of said Climax Molybdenum Company."

REFERENCE DWGS	DRAWING NO.	REFERENCE



Climax Molybdenum
A Freeport-McMoRan Company




W. W. WHEELER & ASSOCIATES, INC.
Water Resources Engineers


3700 S. INCA STREET
ENGLEWOOD, CO 80110-3405
303-761-4130
FAX 303-761-2802

INTERCEPTOR REHABILITATION PROJECT		Climax Molybdenum Climax Mine Climax, CO		
WEST INTERCEPTOR CULVERT REPLACEMENT (PHASE D)		MADE BY DCM	9/1/16	SCALE As Noted
CULVERT INLET STRUCTURE		CHECKED BY SMM	12/1/16	DRAWING NO.
CIVIL PLANS, SECTIONS, AND DETAILS		ACCEPTED BY ...		3-520-00409


R:\100\001\001\1051.07\02\DRAWINGS\Phase D - West Int. Pipeline DS of Searle (2018)\FC\Sheet\F1es10510702D-002 3-29-19 03:37pm Scott.XREFS: Climax24x38 29400 Climax Mine Interior with lidar water 4.5 Climax 4C




1 TRANSITION STRUCTURE
PLAN VIEW
Scale in Feet



TRANSITION STRUCTURE
SECTION
Scale in Feet



TRANSITION STRUCTURE
SECTION
Scale in Feet



OVERFLOW OUTFALL
SECTION
Scale in Feet

NO.	DATE	MADE BY	CKD. BY	REMARKS
1	05/18	TEM	SMM	ISSUED FOR BID
2	03/19	DCM	SMM	ISSUED FOR CONSTRUCTION
3				
4				
5				
6				

"This drawing together with any and all additions, corrections, changes and alterations thereof is the property of Climax Molybdenum Company and is furnished on the express condition that it shall not be reproduced, copied, lent, or disposed of directly or indirectly, nor used for any other purpose than for which it is specifically furnished without the prior written consent of said Climax Molybdenum Company."

DRAWING NO.	REFERENCE



A Freeport-McMoRan Company



Water Resources Engineers

3700 S. INDA STREET
ENGLEWOOD, CO 80110-3405
303-761-4130
FAX 303-761-2802

INTERCEPTOR REHABILITATION PROJECT		Climax Molybdenum Climax Mine	
WEST INTERCEPTOR CULVERT REPLACEMENT (PHASE D)		MADE BY DCM	9/1/16
TRANSITION STRUCTURE		CHECKED BY SMM	12/1/16
CIVIL PLANS, SECTIONS, AND DETAILS		ACCEPTED BY ...	SCALE As Noted DRAWING NO. 3-520-00410

R:\1000\10611051.07.02\DRAWINGS\Phase D - West Int. Pipeline DS of Searle (2018)\FC\Sheet\F1es10510702D-003 3-29-19 03:39pm Scott_XREFS Climax24x38 2016 July 20 053 SEARLE Climax 4C

EXAMPLE OF GABIONS IN
ADEQUATE CONDITIONS
(NO REPAIR NEEDED)




EXAMPLE OF GABIONS IN
DISREPAIR. RESHAPE AND
REINFORCE STEEL BASKET.



1 GABION WALL REPAIR


NOTES:

- REPAIR OR REPLACE GABION BASKETS
AS DIRECTED BY ENGINEER.
- GABION SECTIONS HAVE 1 TO 4 LEVELS.





2 GABION WALL COMPLETE REPLACEMENT

TYPICAL SECTION
Scale in Feet



DRAINAGE INLET LOCATIONS	
NUMBER	STATION
1	163+48
2	168+19
3	178+97
4	184+14
5	190+62



REVISIONS	NO.	DATE	MADE BY	CHKD. BY	REMARKS
	1	05/18	TEM	SMM	ISSUED FOR BID
	2	03/19	DCM	SMM	ISSUED FOR CONSTRUCTION
	3				
	4				
	5				
	6				
	7				

"This drawing together with any and all additions, corrections, changes and alterations thereof is the property of Climax Molybdenum Company and is furnished on the express condition that it shall not be reproduced, copied, lent, or disposed of directly or indirectly, nor used for any other purpose than for which it is specifically furnished without the prior written consent of said Climax Molybdenum Company."

REFERENCE DWGS	DRAWING NO.	REFERENCE



A Freeport-McMoRan Company




Water Resources Engineers


3700 S. INCA STREET
ENGLEWOOD, CO 80110-3405
303-761-4130
FAX 303-761-2802

INTERCEPTOR REHABILITATION PROJECT		Climax Molybdenum Climax Mine	
WEST INTERCEPTOR CULVERT REPLACEMENT (PHASE D)		MADE BY DCM	SCALE As Noted
DRAINAGE INLETS AND GABIONS		CHECKED BY SMM	DRAWING NO.
TYPICAL PLANS, SECTIONS, AND DETAILS		ACCEPTED BY ...	3-520-00411

R:\100\001\0811\051.07.02\DRAWINGS\Phase D - West Int. Pipeline.DS of Searle (2018)\FC\Sheet\F10510702D-003 3-29-19 03:39pm Scott_XREFS.Climax24x38 2016 JULY 20 03: SEARLE.Climax 4C




1 DRAIN INLET CONCRETE
PLAN VIEW
Scale in Feet
0 1/2 1 2 3





38-W-4 GRATING
2" X $\frac{3}{8}$ " BARS (2-3/8" C-C)
HOT-DIP GALVANIZED

2 GRATING
DETAIL
N.T.S.




CONCRETE COLLAR
SECTION
Scale in Feet
0 1/2 1 2 3
A 412

- NOTES:
1. REINFORCE WITH 6x6xW4xW4 WIRE FABRIC IN WALLS (NOT SHOWN).
 2. ANGLE OF 42"x 24" REDUCING CHDPE TEE MAY BE VARIED AS REQUIRED, 45° MAX.
 3. CHAMFER EXPOSED CORNERS OF CONCRETE $\frac{3}{4}$ " (NOT SHOWN)

REVISIONS	NO.	DATE	MADE BY	CKD. BY	REMARKS	REFERENCE DWGS	DRAWING NO.	REFERENCE	<div><div></div><div></div></div>	INTERCEPTOR REHABILITATION PROJECT		Climax Molybdenum Climax Mine Climax, CO		
	Δ	05/18	TEM	SMM	ISSUED FOR BID					WEST INTERCEPTOR CULVERT REPLACEMENT (PHASE D)		MADE BY DCM	4/1/16	SCALE As Noted
	Δ	03/19	DCM	SMM	ISSUED FOR CONSTRUCTION					CULVERT DRAINAGE INLETS		CHECKED BY SMM	4/1/16	DRAWING NO.
	Δ									STRUCTURAL PLANS, SECTIONS, AND DETAILS		ACCEPTED BY ...		3-520-00412
	Δ													
	Δ													
"This drawing together with any and all additions, corrections, changes and alterations thereof is the property of Climax Molybdenum Company and is furnished on the express condition that it shall not be reproduced, copied, lent, or disposed of directly or indirectly, nor used for any other purpose than for which it is specifically furnished without the prior written consent of said Climax Molybdenum Company."														

R:\1000\0611\0611\07\02\DRAWINGS\Phase D - West Int. Pipe\Int. Pipe\DCM\Sheet\10510702D-004 3-29-19 03:43pm Scott.XREFS.Climax24x36 2016-05-24 02:56:22 Climax 4C



REVISIONS	NO.	DATE	MADE BY	CHKD. BY	REMARKS
	1	05/18	TEM	SMM	ISSUED FOR BID
	2	03/19	DCM	SMM	ISSUED FOR CONSTRUCTION
	3				
	4				
	5				
	6				
	7				

"This drawing together with any and all additions, corrections, changes and alterations thereof is the property of Climax Molybdenum Company and is furnished on the express condition that it shall not be reproduced, copied, lent, or disposed of directly or indirectly, nor used for any other purpose than for which it is specifically furnished without the prior written consent of said Climax Molybdenum Company."

DRAWING NO.	REFERENCE



Climax Molybdenum
A Freeport-McMoRan Company




W. W. WHEELER & ASSOCIATES, INC.
Water Resources Engineers


3700 S. INDA STREET
ENGLEWOOD, CO 80110-3405
303-761-4130
FAX 303-761-2802

INTERCEPTOR REHABILITATION PROJECT		Climax Molybdenum Climax Mine	
WEST INTERCEPTOR CULVERT REPLACEMENT (PHASE D)		MADE BY DCM	9/1/16
CULVERT INLET STRUCTURE		CHECKED BY SMM	12/1/16
STRUCTURAL PLANS, SECTIONS, AND DETAILS		ACCEPTED BY ...	
		SCALE As Noted	DRAWING NO. 3-520-00413


R:\1000\06\11\051.07\1051.07\02\DRAWINGS\Phase D - West Int. Piping\DCS of Seale (2018)\FC\Sheet\1051.07\02\004 3-29-19 03:43pm Scott.XREFS.Climax24x38 2016-05-24 02:56:22 Climax 4C:





- NOTES:
1. CONSTRUCT PER SPECIFICATION 03300: CAST-IN-PLACE CONCRETE.
 2. CHAMFER EXPOSED CONCRETE CORNERS $\frac{3}{8}$ " (NOT SHOWN).
 3. DAYLIGHT 12 G COPPER HDPE LOCATING WIRE AT MANHOLE, LEAVE. MIN. 6" EXPOSED.




NOTE:
50" CMP INVERT ELEV. IS APPROXIMATE. SET 60" CHDPE INVERT AT EXISTING 50" CMP INVERT.




REVISIONS	NO.	DATE	MADE BY	CHKD. BY	REMARKS	<i>"This drawing together with any and all additions, corrections, changes and alterations thereof is the property of Climax Molybdenum Company and is furnished on the express condition that it shall not be reproduced, copied, lent, or disposed of directly or indirectly, nor used for any other purpose than for which it is specifically furnished without the prior written consent of said Climax Molybdenum Company."</i>	REFERENCE DWGS	DRAWING NO.	REFERENCE	<div> A Freeport-McMoRan Company</div> <div> W. W. WHEELER & ASSOCIATES, INC. Water Resources Engineers</div> <div>3700 S. INCA STREET ENGLEWOOD, CO 80110-3405 303-761-4130 FAX 303-761-2802</div>	INTERCEPTOR REHABILITATION PROJECT		Climax Molybdenum Climax Mine		
		05/18	TEM	SMM	ISSUED FOR BID						WEST INTERCEPTOR CULVERT REPLACEMENT (PHASE D)		MADE BY DCM	9/1/16	SCALE As Noted
		03/19	DCM	SMM	ISSUED FOR CONSTRUCTION						TRANSITION STRUCTURE		CHECKED BY SMM	12/1/16	DRAWING NO.
											STRUCTURAL PLANS, SECTIONS, AND DETAILS		ACCEPTED BY ...		3-520-00414

R:\100\10611\10611\07.02\DRAWINGS\Phase D - West Int. Pipint.DS of Searle (2018)\FC\Sheet\F1es10510702D-004 3-29-19 03:43pm Scott.XREFS: Climax24x38 2016-05-24 02:56:22; Climax_4C;



1 TRANSITION STEEL REDUCER
PLAN VIEW
Scale in Feet




2 END RING
DETAIL
Scale in Feet


MAKE ONE EACH FROM
1/4" A36 PLATE

NOTES:

1. FABRICATED FROM 1/4"-THICK A36 STEEL PLATE.
2. ALL WELDED CONSTRUCTION.
3. USE E70XX ELECTRODES.
4. PRIME AND PAINT PER SPECIFICATIONS.



TRANSITION STEEL REDUCER
SECTION
Scale in Feet



TRANSITION STEEL REDUCER
SECTION
Scale in Feet

END RING,
REF. DETAIL
THIS DWG.

REVISIONS	NO.	DATE	MADE BY	CKD. BY	REMARKS
	△	05/18	TEM	SMM	ISSUED FOR BID
	△	03/19	DCM	SMM	ISSUED FOR CONSTRUCTION
	△				
	△				
	△				
	△				

"This drawing together with any and all additions, corrections, changes and alterations thereof is the property of Climax Molybdenum Company and is furnished on the express condition that it shall not be reproduced, copied, lent, or disposed of directly or indirectly, nor used for any other purpose than for which it is specifically furnished without the prior written consent of said Climax Molybdenum Company."

REFERENCE DWGS	DRAWING NO.	REFERENCE



Climax Molybdenum
A Freeport-McMoRan Company




W. W. WHEELER & ASSOCIATES, INC.
Water Resources Engineers

3700 S. INDA STREET
ENGLEWOOD, CO 80110-3405
303-761-4130
FAX 303-761-2802


INTERCEPTOR REHABILITATION PROJECT			Climax Molybdenum Climax Mine Climax, CO	
WEST INTERCEPTOR CULVERT REPLACEMENT (PHASE D)			MADE BY DCM	9/1/16
TRANSITION STEEL REDUCER			CHECKED BY SMM	12/1/16
STRUCTURAL DETAILS			ACCEPTED BY ...	
			SCALE As Noted	
			DRAWING NO. 3-520-00415	

R:\1000\10511051\07.02\DRAWINGS\Phase D - West Int. Piping DS of Seale (2018)\MFC\SheetFiles\10510702D-004_3-29-19_03.45pm_Scott_XREFS:Climax24-36_2016-05-24_02.56.22:Climax_4C:




MAKE 2 EACH ASSEMBLY


1 TRASHRAC
DETAILS
Scale in Feet




3 SAFETY RAIL
DETAIL
Scale in Feet




4 VENT PIPE
DETAIL
Scale in Feet




5 BOLLARD
DETAIL
Scale in Feet




2 SAFETY RAIL
PLAN VIEW
Scale in Feet



SAFETY RAIL
SECTION
Scale in Feet



6 MOUNTING PLATE
DETAIL
N.T.S.



MAKE FROM 1-1/2" X 3/8" 15-W-4 STEEL GRATING

7 GRATING
DETAIL
Scale in Feet

- NOTES:
1. FABRICATE SAFETY RAIL FROM 1-1/2" SCH 40 A53 PIPE.
 2. ALL WELDED CONSTRUCTION.
 3. USE E70XX ELECTRODES.
 4. GRATING TO BE 1-1/2" X 3/8" 15-W-4 STEEL GRATING.
 5. PAINT SAFETY RAILS AND VENT PIPE PER SPECIFICATION 05120: MISCELLANEOUS METALWORK.
 6. TRASHRACK AND GRATING SECTION TO BE HOT-DIPPED GALVANIZED.

REVISIONS	NO.	DATE	MADE BY	CKD. BY	REMARKS
	Δ	05/18	TEM	SMM	ISSUED FOR BID
	Δ	03/19	DCM	SMM	ISSUED FOR CONSTRUCTION
	Δ				
	Δ				
	Δ				
	Δ				

"This drawing together with any and all additions, corrections, changes and alterations thereof is the property of Climax Molybdenum Company and is furnished on the express condition that it shall not be reproduced, copied, lent, or disposed of directly or indirectly, nor used for any other purpose than for which it is specifically furnished without the prior written consent of said Climax Molybdenum Company."

REFERENCE DWGS	DRAWING NO.	REFERENCE



A Freeport-McMoRan Company



Water Resources Engineers

3700 S. INDA STREET
ENGLEWOOD, CO 80110-3405
303-761-4130
FAX 303-761-2802

INTERCEPTOR REHABILITATION PROJECT		Climax Molybdenum Climax Mine Climax, CO		
WEST INTERCEPTOR CULVERT REPLACEMENT (PHASE D)		MADE BY DCM	9/1/16	SCALE As Noted
MISCELLANEOUS		CHECKED BY SMM	12/1/16	DRAWING NO.
STRUCTURAL DETAILS		ACCEPTED BY ...		3-520-00416