

RECLAMATION PLAN

SCALE 1" = 200 FT

BARNETT'S PIT

AFTER MINING PRACTICES
IS COMPLETED WORKING FROM
SOUTHEAST TO NORTHWEST, WE
WILL PUSH OVERBURN OF TOP SOIL
INTO PIT AT A MAXIMUM DEPTH OF 15' MINIMUM
WE WILL MAKE STEEP SLOPES
OR LESS. WE WILL REMOVE TOP SOIL
AND OVERBURN AS NEEDED TO GET
GRAVEL

Estimated Costs for reclamation

240 hrs Dozer =	14,400.00	
240 hrs Loader =	12,000.00	
100 hrs grader =	5,000.00	
tillage + planting =	375.00	
Seed =	750.00	
580 man hours =	4,599.40	
Total \$7,124.40 using Micros + wages		

PIT Depth ESTIMATED 15 TO 20 FT DEEP

