C&J Gravel private property reclamation cost (see map 4 for reference) -9.98 acres: this area is only covering the batch plant, office, mechanic shop and lay down yard.

- Rip the existing floor
 D10T: 10 hours \$2,500

 A. 9.98 acres
 B. 12" rip depth
- 2. Place overburden over the disturbed area
- -D10T: 5.15 hours \$1,287.50
- -A35-C: 18.71 hours \$1,440.67
- -Cat 982M: 3.38 hours \$559.39
 - A. 9.98 acres
 - B. 9.98 acres @ 6" = 7,728.51 yds3 dirt
 - C. 1,000' maximum haul distance from loadout zone; using a Volvo A35-C
 - D. 7,728.51 ÷ 19 = 406.76 loads @ 2.76 min per load
 - I. 30 second load time. 2 passes with a Cat 982M
 - II. 1.51 minutes round trip @15mph
 - III. 45 seconds to dump
 - E. Cat 982M: 406.76 loads @30 seconds per load = 3.38 hours
 - F. Cat D10T: 7,728.51 yds @ 1,500 hour = 5.15 hours
- 3. Seeding
- -10 hours labor \$250
- -225.54 pounds \$2,255.40
 - A. 9.98 acres
 - B. 225.54 pounds of seed hand broadcasted @ 22.6 pounds per acre

4. We also plan on leaving all existing roads and will not be reclaiming those for future access and development purposes

Summary Cat D10T: \$3,787.50 Cat 982M: \$559.39 Volvo A-35: \$1,440.67 Labor: \$250 Seed: \$ 2,255.40

\$8,292.96