

EXHIBIT L: RECLAMATION COSTS

Martin Marietta is applying to the Colorado Division of Reclamation, Mining and Safety (DRMS) for an Amendment to the existing 112 Reclamation Permit No. M-1977-439 to change the final reclamation for Stage G of the Home Office site from one open water lake to two sealed water storage reservoirs using compacted clay embankment liners. Table 1 summarizes the estimated construction costs.

Table 1: Liner Construction Costs

#	Item	Units	Qty	Rate	Total
1	Mobilization, Bonding and Insurance	LS	1	150,900	\$150,900
2	Slope Liner Excavation	CY	378,500	2.00	\$757,000
3	Foundation Excavation	CY	20,000	3.50	\$70,000
4	Slope Liner Embankment Fill (in place)	CY	159,000	2.20	\$349,800
5	Reservoir Bottom Grading	LS	1	43,000	\$43,000
6	Topsoil Placement	CY	11,900	1.75	\$20,825
7	Underdrain	LS	1	300,000	\$300,000
Total Bond Increase					\$1,691,525