



Huddleston-Berry
Engineering & Testing, LLC

2789 Riverside Parkway
Grand Junction, Colorado 81501
Phone: 970-255-8005
Info@huddlestonberry.com

March 19, 2022
Project#01349-0001

Bowie Resources, LLC
43659 Bowie Road
Paonia, Colorado 81428

Attention: Mr. Basil Bear

Subject: Summary of Instrumentation Monitoring
1st Quarter 2022
Bowie Coal Waste Disposal Area No. 3
Paonia, Colorado

Reference: *Summary of Instrumentation Monitoring, 4th Quarter 2021, Bowie Coal Waste Disposal Area No. 3, Paonia, Colorado* by Huddleston-Berry Engineering & Testing, LLC for Bowie Resources, LLC, January 25, 2022.

Stability Evaluation, Gob Pile #3, Bowie No. 2 Mine by Huddleston-Berry Engineering & Testing, LLC for Bowie Resources, LLC, July 15, 2014.

Dear Mr. Bear,

At the request of the Colorado Division of Reclamation, Mining and Safety (DRMS), Huddleston-Berry Engineering & Testing, LLC (HBET) prepared this letter regarding quarterly monitoring of vibrating wire piezometers at Coal Waste Disposal Area No. 3 (CWDA No. 3) at the Bowie mine near Paonia, Colorado. The intent of the monitoring was to detect significant changes in the pore water pressures within the coal waste which may impact the stability of the waste pile.

Vibrating Wire Piezometers

Five vibrating wire piezometers were installed in CWDA No. 3 in October 2014. The piezometers were installed at three locations within the footprint of the gob pile as shown on the attached figure. Monitoring of the functioning piezometers was completed by Buckhorn Engineering (Buckhorn) on March 25th, 2022. The attached monitoring report prepared by Buckhorn includes the piezometer monitoring data and the data is summarized in the following table.

VWP ID	Initial Pore Pressure 10/31/14 (psi)	12/27/21 Pore Pressure (psi)	03/25/22 Pore Pressure (psi)	Difference Since Installation (psi)	Difference Since Last Reading (psi)
VWP-A Deep	10.4	3.2	3.1	-7.3	-0.1
VWP-A Shallow	4.7	2.5	2.5	-2.2	0.0
VWP-B Deep	0.2	0.0	0.0	-0.2	0.0
VWP-B Shallow	13.9	8.0	8.0	-5.9	0.0
VWP-D	7.1	3.6	3.4	-3.7	-0.2

Discussion of Vibrating Wire Piezometers

VWP-A Deep

VWP-A Deep was installed on October 6, 2014 near the northern edge of CWDA No. 3. VWP-A Deep was installed in the foundation soil approximately eight feet below the bottom of the gob. The pore pressures recorded at VWP-A Deep generally decreased since installation until September 2015. After that, the pore pressures have fluctuated within a narrow range based upon the activity on the gob pile. In general, HBET does not believe that the pore pressure changes in VWP-A Deep are an indication of instability in CWDA No. 3.

VWP-A Shallow

VWP-A Shallow was installed on October 6, 2014 near the northern edge of CWDA No. 3. VWP-A Shallow was installed approximately ten feet above the base of the gob. After installation, the pore pressures dropped until November 2014. Between November 2014 and September 2015, increases in the pore pressures were recorded at VWP-A Shallow. However, between September 2015 and December 2016, the pore pressures decreased. Since then, the data have fluctuated within a narrow range. In general, HBET does not believe that the pore pressure changes in VWP-A Shallow are an indication of instability in CWDA No. 3.

VWP-B Deep

VWP-B Deep was installed on October 6, 2014 in the west-central portion of CWDA No. 3. VWP-B Deep was installed in the foundation soil approximately ten feet below the bottom of the gob. Since installation, the pore pressures recorded at VWP-B Deep have fluctuated within a narrow range. These pore pressure changes are likely related to activity on the gob pile. In general, HBET does not believe that the pore pressure changes in VWP-B Deep are an indication of instability in CWDA No. 3.

VWP-B Shallow

VWP-B Shallow was installed on October 6, 2014 in the west-central portion of CWDA No. 3. VWP-B Shallow was installed approximately ten feet above the base of the gob. Since installation, the pore pressures recorded at VWP-B Shallow have fluctuated with periods of slight increase and slight decrease; likely associated with activity on the gob pile. In general, HBET does not believe that the pore pressure changes in VWP-B Shallow are an indication of instability in CWDA No. 3.

VWP-D

VWP-D was installed on October 7, 2014 in the east-central portion of CWDA No. 3. VWP-D was installed approximately ten feet above the base of the gob. Since installation, the pore pressures recorded at VWP-D have fluctuated. The pore pressures increase slightly during the 3rd Quarter of 2017. However, this likely reflects the activity at CWDA No. 3 during the monitoring period and the pore pressures have decreased since September 2017. In general, HBET does not believe that the pore pressure changes in VWP-D are an indication of instability in CWDA No. 3.

General

Based upon the results of the most recent VWP monitoring data, HBET does not believe that there is any reduction in the stability of CWDA No. 3.

We are pleased to be of service to your project. Please contact us if you have any questions or comments regarding the contents of this report.

Respectfully Submitted:

Huddlestone-Berry Engineering and Testing, LLC



Michael A. Berry, P.E.
Vice President of Engineering

ATTACHMENTS



March 29, 2022

Mr. Mike Berry, PE
Huddleston-Berry Engineering and Testing, LLC
2789 Riverside Parkway
Grand Junction, CO 81501

**SUBJECT: Summary Report, 1st Quarter 2022, Vibrating Wire Piezometers
January – March 2022, Bowie Mine #2
Coal Waste Disposal Area (CWDA) #3**

Greetings Mr. Berry,

Buckhorn Engineering, Inc. (BEI) conducted quarterly monitoring of installed vibrating wire piezometers (VWP) at Coal Waste Disposal Area #3 (CWDA #3), Bowie Resources, LLC Bowie Mine #2. This report is for the period from January through March 2022 (1st Quarter). VWP data was recorded on March 25, 2022. Per the Colorado Division of Reclamation, Mining & Safety (CDRMS) and your instructions, vibrating wire piezometer readings for all active piezometers are currently taken quarterly.

We present a graph of measured pore pressures on the attached Figure 1 and numerically in Table 1 below. Table 1 is a summary of the initial, last year, last quarter and current readings. In addition, we present the difference between the current pore pressures and those at the time of installation, the previous quarter, and previous year.

Table 1. Summary of Pore Pressure Readings

VWP ID #	Pore Pressure (psi)				Pressure Difference (psi)		
	Installation 10/31/2014	Last Year 3/24/2021	Last Quarter 12/27/2021	Current 3/25/2022	Since Installation	Since Last Year	Since Last Quarter
VWP-A Deep	10.4	3.4	3.2	3.1	-7.3	-0.3	-0.1
VWP-A Shallow	4.7	2.8	2.5	2.5	-2.2	-0.3	0.0
VWP-B Deep	0.2	-0.2	0.0	0.0	-0.2	0.2	0.0
VWP-B Shallow	13.9	7.7	8.0	8.0	-5.9	0.3	0.0
VWP-D	7.1	4.0	3.6	3.4	-3.7	-0.6	-0.2

As seen on Figure 1 and Table 1, all five VWP's decreased in pore pressure when compared with pressures at installation in 2014. Three of the five VWP's had no change in pressure since last quarter and the other two had a small (0.1-0.2 psi) decrease. When compared with the same quarter last year, two VWP's had slight increases (0.2-0.3 psi) in pressure, while two had decreases of 0.3-0.6 psi. Although there is a general trend of decreasing pore pressure over time, three of the piezometers (VWP-A Deep, VWP-B-Deep and VWP-B Shallow) have some erratic behavior in 2019 and some minor fluctuations in the summer readings.


If you have any questions regarding this letter or the instrumentation monitoring at CWDA #3, please contact me at (970) 497-8821 or Lbrandt@buckhornengineering.com.

Respectfully Submitted,

Buckhorn Engineering, Inc.



Laurie J. Brandt, CPG
Certified Professional Geologist



Daniel C. Quigley, PE
Senior Civil Engineer/Geologist



Attachment: Figure 1 – Vibrating Wire Piezometer Data Graph

Figure 1 - Bowie Mine #2 - CWDA #3
Vibrating Wire Piezometer Data

