

Technical Revision to the Mining Plan Narrative

In paragraph four of the Mining Plan Exhibit 6.4.4 a revision to how mining is done.

High walls will be left in place until the area is deemed mined out. Once the area is mined out high walls will be sloped and reclaimed to 3H:1V. This will take place after the area is mined out of all usable material. High wall length will vary from 0 to 2000 linear feet and max heights ranging 12 feet to 18 feet.