





POUDRE PONDS BANK STABILIZATION PROJECT  
CITY OF GREELEY  
90% DESIGN DRAWINGS - NOT FOR CONSTRUCTION  
GREELEY, COLORADO




CLIENT CONTACT:  
CITY OF GREELEY  
RYAN DUVE, PE  
WATER AND SEWER DEPARTMENT  
1001 11TH AVENUE  
GREELEY, CO 80631  
RYAN.DUVE@GREELEYGOV.COM  
970.350.9813

PROJECT CONTACT:  
CHRIS ROMEYN, PE  
OTAK, INC.  
371 CENTENNIAL PARKWAY SUITE 210  
LOUISVILLE, CO, 80027  
CHRIS.ROMEYN@OTAK.COM  
720.758.7751

O:\PROJECT\20100\201119B\04 CAD\ACAD\Draw\Exhibits\Cover.dwg | 24x36 Plan | kye.maduzia | Aug 29, 2023 - 3:13pm

Print Date: Aug 29, 2023  
File Name: Cover.dwg



Sheet Revisions

Date:	Comments	Init.



No Revisions:  
Revised:  
Void:

POUDRE PONDS BANK STABILIZATION PROJECT

COVER

Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:	

Project No./Code

20119B

Sheet Number G1

G:\PROJECT\20100\20119B\04 CAD\ACAD\Draw\Exhibits\Cover.dwg | TOC | kye.maduzia | Aug 29, 2023 - 3:13pm

Sheet List Table	
Sheet Number	Sheet Title
G1	COVER
G2	INDEX AND LEGEND
G3	GENERAL NOTES
G4	SURVEY CONTROL
G5	ACCESS AND STAGING
G6	DEMOLITION PLAN
C1	PROPOSED GRADING PLAN OVERVIEW
C2	PROPOSED GRADING PLAN 1
C3	PROPOSED GRADING PLAN 2
C4	PROPOSED GRADING PLAN 3
C5	SECTIONS
C6	MIDDLE WALL PROFILE
C7	BOTTOM WALL PROFILE
C8	STABILIZATION PLAN 1
C9	STABILIZATION PLAN 2
D1	TYPICAL BANK DETAIL
D2	FABRIC DETAIL
D3	FENCE DETAIL
LS1	PLANTING PLAN 1
LS2	PLANTING PLAN 2
LS3	PLANTING PLAN 3
LS4	PLANTING NOTES
LS5	PLANTING DETAILS
LS6	PLANTING SCEDULES
ESC1	EROSION CONTROL PLAN OVERVIEW
ESC2	INITIAL EROSION CONTROL PLAN 1
ESC3	INITIAL EROSION CONTROL PLAN 2
ESC4	INITIAL EROSION CONTROL PLAN 3
ESC5	INTERIM EROSION CONTROL PLAN 1
ESC6	INTERIM EROSION CONTROL PLAN 2
ESC7	INTERIM EROSION CONTROL PLAN 3
ESC8	FINAL EROSION CONTROL PLAN 1
ESC9	FINAL EROSION CONTROL PLAN 2
ESC10	FINAL EROSION CONTROL PLAN 3
ESC11	DEWATERING AND DIVERSION PLAN

FDP  
FDP XS  
BMPs

ABBREVIATIONS  
FLOODPLAIN DEVELOPMENT PERMIT  
FLOODPLAIN DEVELOPMENT PERMIT CROSS SECTION  
BEST MANAGEMENT PRACTICES

LEGEND	
EXISTING CONTOURS 1FT & 5FT	
PROPOSED 1FT & 5FT	
EXISTING TREE WITH CALIPER	
CONCRETE TRAIL	
PARCELS	
SOIL RIPRAP	
PLANTING BENCH	
ROCK WALL	
EXISTING RIPRAP SPILLWAY	
EXISTING SLURRY WALL	
STAGING AREA	
SITE ACCESS	
EXISTING ECO BLOCKS	
EXISTING RIPRAP BANK	
EXISTING BUCK AND RAIL FENCE	
PROPOSED FENCE	
LIMITS OF DISTURBANCE	
SURVEYED EDGE OF WATER	
STACKED BOULDER WALL	
EROSION CONTROL FABRIC	

Print Date: Aug 29, 2023
File Name: Cover.dwg

Sheet Revisions		
Date:	Comments	Init.




No Revisions:
Revised:
Void:

POUDRE PONDS BANK STABILIZATION PROJECT			
INDEX AND LEGEND			
Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:	Subset Sheets:		

Project No./Code
20119B
Sheet Number G2











NOTE:  
SELECTED CONTRACTOR  
MUST COMPLETE ONSITE  
SAFETY TRAINING WITH  
J2 CONTRACTING TO  
ACCESS AND STAGE  
MATERIAL WITHIN THE  
ACTIVE MINE SITE

Print Date: Aug 29, 2023		<div></div> <div></div> <div></div> <div></div>	Sheet Revisions					POUDRE PONDS BANK STABILIZATION PROJECT				Project No./Code	
File Name: Access Staging.dwg			Date:	Comments	Init.			ACCESS AND STAGING				20119B	
								No Revisions:					
								Revised:		Designer:	CR	Structure	
								Void:		Detailer:	KM	Numbers	
							Sheet Subset:		Subset Sheets:		Sheet Number G5		




o:\PROJECT\20100\201119B\04 CAD\ACAD\Drawings\Exhibits\ExistingConditions.dwg | 24x36 Plot | kye.maduzia | Aug 29, 2023 - 3:17pm



Print Date: Aug 29, 2023		<div><div></div><div></div><div></div><div></div></div>	Sheet Revisions					POUDRE PONDS BANK STABILIZATION PROJECT				Project No./Code	
File Name: ExistingConditions.dwg			Date:	Comments	Init.			DEMOLITION PLAN				20119B	
							No Revisions:	Designer: CR		Structure			
							Revised:	Detailer: KM		Numbers			
							Void:	Sheet Subset:		Subset Sheets:		Sheet Number G6	








C:\PROJECT\20100\20119B\04 CAD\ACAD\Draw\Exhibits\Proposed Grading Plan.dwg | Plan1 | kye.maduzia | Aug 29, 2023 - 3:16pm



0' 5' 10' 20'  
1 INCH = 20 FEET (11 X 17)  
1 INCH = 10 FEET (22 X 34)




FDP XS 50877		
NOTRHING	EASTING	ELEVATION
1407298.637'	3214143.988'	4660.65''
1407296.416'	3214143.079'	4662.78'
1407292.529'	3214141.488'	4663.25'
1407290.771'	3214140.768'	4665.41'
1407287.902'	3214139.594'	4666.12'
1407274.945'	3214134.290'	4670.55'
1407272.261'	3214133.192'	4671.72'
1407270.873'	3214132.623'	4671.75'

90% DESIGN - August 29, 2023

Print Date: Aug 29, 2023
File Name: Proposed Grading Plan.dwg

Sheet Revisions		
Date:	Comments	Init.



No Revisions:
Revised:
Void:

POUDRE PONDS BANK STABILIZATION PROJECT			
PROPOSED GRADING PLAN 1			
Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:	


Project No./Code	
20119B	
Sheet Number	C2



C:\PROJECT\20100\20119B\04 CAD\ACAD\Draw\Exhibits\Proposed Grading Plan.dwg | Plan2 | kye.maduzia | Aug 29, 2023 - 3:16pm



0' 5' 10' 20'  
1 INCH = 20 FEET (11 X 17)  
1 INCH = 10 FEET (22 X 34)




FDP SECTION, SEE SHEET C5  
FINISHED GRADE MUST MATCH INDICATED ELEVATIONS  
SEE TABLE

FDP XS 50688		
NOTHING	EASTING	ELEVATION
1407264.006'	3214360.193'	4660.52'
1407261.818'	3214360.423'	4662.77'
1407257.541'	3214360.873'	4663.28'
1407255.751'	3214361.062'	4665.39'
1407253.265'	3214361.323'	4665.77'
1407236.159'	3214363.124'	4672.72'
1407231.285'	3214363.637'	4672.75'

Print Date: Aug 29, 2023
File Name: Proposed Grading Plan.dwg

Sheet Revisions		
Date:	Comments	Init.



No Revisions:
Revised:
Void:


POUDRE PONDS BANK STABILIZATION PROJECT			
PROPOSED GRADING PLAN 2			
Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:	

Project No./Code	
20119B	
Sheet Number	C3

C:\PROJECT\20100\20119B\04 CAD\ACAD\Draw Exhibits\Proposed Grading Plan.dwg | Plan3 | kye.maduzia | Aug 29, 2023 - 3:16pm



0' 5' 10' 20'  
1 INCH = 20 FEET (11 X 17)  
1 INCH = 10 FEET (22 X 34)



FDP XS 50488		
NOTHING	EASTING	ELEVATION
1407323.260'	3214530.248'	4657.90'
1407319.058'	3214531.857'	4662.77'
1407315.042'	3214533.393'	4663.27'
1407313.361'	3214534.037'	4665.37'
1407311.026'	3214534.930'	4665.77'
1407303.461'	3214537.825'	4668.38'
1407295.429'	3214540.899'	4671.90'

Print Date: Aug 29, 2023
File Name: Proposed Grading Plan.dwg

Sheet Revisions		
Date:	Comments	Init.






No Revisions:
Revised:
Void:

POUDRE PONDS BANK STABILIZATION PROJECT			
PROPOSED GRADING PLAN 3			
Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:	

Project No./Code	
20119B	
Sheet Number	C4




O:\PROJECT\20100\20119B\04 CAD\ACAD\Draw\Exhibits\Proposed Grading Plan.dwg | SECTION1 | kye.maduzia | Aug 29, 2023 - 3:18pm



— PROPOSED CONDITION (PC)  
--- EXISTING CONDITION (EC)  
PROPOSED CUT  
PROPOSED FILL

2X VERTICAL EXAGGERATION

Print Date: Aug 29, 2023  
File Name: Proposed Grading Plan.dwg




Sheet Revisions		
Date:	Comments	Init.



No Revisions:		POUDRE PONDS BANK STABILIZATION PROJECT			Project No./Code	
Revised:		SECTIONS			20119B	
Void:		Designer:	CR	Structure		
		Detailer:	KM	Numbers		
		Sheet Subset:	Subset Sheets:		Sheet Number	C5

O:\PROJECT\20100\20119B\04 CAD\ACAD\Drawings\Exhibits\Proposed Grading Plan.dwg | Mid Wall Prof | kye.maduzia | Aug 29, 2023 - 3:18pm



Print Date: Aug 29, 2023

File Name: Proposed Grading Plan.dwg

#### Sheet Revisions

Date:	Comments	Init.



No Revisions:

Revised:

Void:

POUDRE PONDS BANK STABILIZATION PROJECT

#### MIDDLE WALL PROFILE

Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:	


Project No./Code

20119B

Sheet Number **C6**




O:\PROJECT\20100\20119B\04 CAD\ACAD\Drawings\Exhibits\Proposed Grading Plan.dwg | Bot Wall Prof | lye.maduzia | Aug 29, 2023 - 3:18pm



Print Date: Aug 29, 2023
File Name: Proposed Grading Plan.dwg

Sheet Revisions		
Date:	Comments	Init.




No Revisions:
Revised:
Void:

POUDRE PONDS BANK STABILIZATION PROJECT			
BOTTOM WALL PROFILE			
Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:	Subset Sheets:		

Project No./Code
20119B
Sheet Number
C7


O:\PROJECT\20100\20119B\04 CAD\ACAD\DWG\Exhibits\Stabilization Plan.dwg | StabPlan1 | kye.modulo | Aug 29, 2023 - 3:19pm



NOTE:  
ONLY THE TOP TWO  
COURSES OF  
BOULDERS ARE SHOWN  
FOR CLARITY

Print Date: Aug 29, 2023
File Name: Stabilization Plan.dwg

Sheet Revisions		
Date:	Comments	Init.




No Revisions:
Revised:
Void:

POUDRE PONDS BANK STABILIZATION PROJECT			
STABILIZATION PLAN 1			
Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:	

Project No./Code
20119B
Sheet Number
C8





Print Date: Aug 29, 2023
File Name: Stabilization Plan.dwg

<div> <div></div> <div></div> <div></div> <div></div> <div></div> </div>	Sheet Revisions		
	Date:	Comments	Init.




	POUDRE PONDS BANK STABILIZATION PROJECT			Project No./Code
No Revisions:	STABILIZATION PLAN 2			20119B
Revised:	Designer: CR	Structure		
	Detailer: KM	Numbers		
Void:	Sheet Subset:		Subset Sheets:	Sheet Number <b>C9</b>

90% DESIGN - August 29, 2023




Q:\PROJECT\20100\20119B\04 CAD\ACAD\Drawings\Exhibits\Details\TypicalChannelDetail.dwg | 22\34 PLAN | kye.moduria | Aug 29, 2023 - 3:20pm



Print Date: Aug 29, 2023
File Name: TypicalChannelDetail.dwg

Sheet Revisions		
Date:	Comments	Init.




No Revisions:
Revised:
Void:

POUDRE PONDS BANK STABILIZATION PROJECT			
TYPICAL BANK DETAIL			
Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:	


Project No./Code
20119B
Sheet Number
D1

O:\PROJECT\20100\201119B\04 CAD\ACAD\Draw\Exhibits\Details\FabricDetail.dwg | 22X34 PLAN | kye.maduzia | Aug 29, 2023 - 3:20pm



- FABRIC PLACEMENT AREAS:**  
RIVER LEFT TIE-IN SLOPE FROM APPROX. STA. 11+50 TO STA. 15+50
- NOTES:**
1. WHERE FEASIBLE, FABRIC WILL BE ROLLED OUT AND INSTALLED PARALLEL WITH THE STREAM.
  2. UPSTREAM PIECES WILL OVERLAP DOWNSTREAM PIECES AND UPSLOPE PIECES WILL OVERLAP DOWNSLOPE PIECES.
  3. FOLD OVERLAPPING SEAMS AT LEAST TWICE AND THEN STAKE.
  4. AFTER INITIAL STAKING, STAKE FABRIC AS NECESSARY SO THAT IT IS COMPLETELY FLUSH WITH THE GROUND SURFACE.
  5. SEED, RAKE & INSTALL MULCH AT SPECIFIED RATE PRIOR TO LAYING FABRIC.
  6. SEED, RAKE & MULCH ALL KEY TRENCHES PRIOR TO CLOSING FABRIC.
  7. ALL DISTURBED SLOPES 3:1 OR STEEPER SHALL HAVE EROSION CONTROL FABRIC NEDIA KOIRMAT 400 OR APPROVED EQUIVALENT.
  8. SEE THE EROSION CONTROL PLAN FOR THE LOCATION OF EROSION CONTROL BLANKET.

Print Date: Aug 29, 2023  
File Name: FabricDetail.dwg



Sheet Revisions

Date:	Comments	Init.



No Revisions:

Revised:

Void:

POUDRE PONDS BANK STABILIZATION PROJECT

FABRIC DETAIL


Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:	

Project No./Code


20119B

Sheet Number D2

O:\PROJECT\20100\20119B\04 CAD\ACAD\DWG\Exhibits\Details\Details.dwg | Fence | lye.maduzia | Aug. 29, 2023 - 3:21 pm



- NOTES:
1. FENCE SHALL HAVE A 5-FOOT SETBACK FROM TRAIL/SIDEWALK TO ALLOW FOR MOWING MAINTENANCE CLEARANCE WIDTH, UNLESS OTHERWISE SPECIFIED.
  2. FENCE IS TO BE CONSTRUCTED OF ROUGH SAWN DIMENSIONAL CEDAR LUMBER.
  3. POST SHALL BE 26 INCHES BELOW GROUND, SET IN CONCRETE.
  4. POST HOLE SHALL BE 12" DIAMETER WITH THE POST CENTERED IN THE HOLE. CONCRETE SHALL SLOPE AWAY FROM POST.
  5. RAILS SHALL BE ATTACHED TO THE FACE OF THE POSTS ON THE EXTERIOR SIDE.
  6. RAILS SHALL BE INSTALLED WITH DARK COLORED 4-1/2" STRUCTURAL WOOD SCREWS WITH A SPIDERDRIVE™. SCREWS SHALL BE HEADLOK BY FASTENMASTER OR APPROVED EQUIVALENT. PRE-DRILL SCREWHOLES IF WOODEN RAILS SPLIT AS SCREWS ARE DRIVEN.
  7. ALL LUMBER SHALL BE TREATED WITH TRANSPARENT WESTERN RED CEDAR ULTRA PREMIUM PENETRATING OIL FINISH (PENOFIN) OR APPROVED EQUIVALENT.




NATURAL AREA AND TRAILS FENCE

DETAIL NO. F-1

DATE: APRIL, 2019SCALE: N.T.S.

Print Date: Aug 29, 2023  
File Name: Details.dwg




Sheet Revisions		
Date:	Comments	Init.



No Revisions:		POUDRE PONDS BANK STABILIZATION PROJECT		Project No./Code
Revised:		FENCE DETAIL		20119B
Void:	Designer:	CR	Structure	Sheet Number
	Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:		Sheet Number D3




O:\PROJECT\20100\20119B\04 CAD\ACAD\DWG\Exhibits\Planting Plan.dwg | PlantingPlan1 | kve.modulzia | Aug 29, 2023 - 3:22pm



LEGEND	
EXISTING CONTOURS 1FT & 5FT	
PROPOSED 1FT & 5FT	
CONCRETE TRAIL	
NATIVE RIPARIAN SEEDING	
PLANTING BENCH	
STACKED BOULDER WALL	
TEMPORARY DISTURBANCE AREA	
EROSION CONTROL BLANKET	
CRUSHER FINES	
SITE ACCESS	
LIMITS OF DISTURBANCE	LDA

Print Date: Aug 29, 2023
File Name: Planting Plan.dwg

Sheet Revisions		
Date:	Comments	Init.



No Revisions:
Revised:
Void:

POUDRE PONDS BANK STABILIZATION PROJECT			
PLANTING PLAN 1			
Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:	

Project No./Code	
20119B	
Sheet Number	LS1






O:\PROJECT\20100\20119B\04 CAD\ACAD\Draw\Exhibits\Planting Plan.dwg | PlantingPlan3 | kye.moduliza | Aug 29, 2023 - 3:22pm



LEGEND	
EXISTING CONTOURS 1FT & 5FT	
PROPOSED 1FT & 5FT	
CONCRETE TRAIL	
NATIVE RIPARIAN SEEDING	
PLANTING BENCH	
STACKED BOULDER WALL	
TEMPORARY DISTURBANCE AREA	
EROSION CONTROL BLANKET	
CRUSHER FINES	
SITE ACCESS	
LIMITS OF DISTURBANCE	

Print Date: Aug 29, 2023
File Name: Planting Plan.dwg

Sheet Revisions			
Date:	Comments	Init.	



No Revisions:
Revised:
Void:

POUDRE PONDS BANK STABILIZATION PROJECT			
PLANTING PLAN 3			
Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:	

Project No./Code	
20119B	
Sheet Number	LS3



O:\PROJECT\20100\20119B\04 CAD\ACAD\Draw\Exhibits\Planting Plan.dwg | Aug 29, 2023 - 3:22pm | lye.modazio | Notes |



Poudre Ponds Bank Stabilization Project  
Revegetation Plan  
July 7, 2023

General Notes:

- 1. This Revegetation Plan was prepared by Andy Herb, AlpineEco.
- 2. Any trees to be removed for the project will be removed during the non-nesting season for migratory birds (between September 1 and March 31). If this is not possible, active nest surveys will be required.
- 3. Unnecessary impacts will be avoided by fencing the limits of construction. There will be no vehicle access outside the limits of construction.
- 4. To avoid the continued spread of noxious weeds, all discrete populations of Colorado List A or B noxious weeds found in or within 100 feet of the restoration area will be sprayed with the appropriate herbicide(s) prior to construction. Russian Olive (*Elaeagnus angustifolia*) and Saltcedar (*Tamarisk* spp.) must be removed using the “cut-stump” method (see Specifications). Weed populations must be identified by a qualified ecologist during the growing season.
- 5. All best management practices (BMPs) shall be selected, installed, implemented, and maintained according to appropriate engineering, hydrologic, and pollution control practices. All erosion control materials will be biodegradable and not use plastic netting.
- 6. No chemicals shall be used, stored, or stockpiled within 50 horizontal feet of the river or other aquatic habitats.
- 7. All waste materials generated by the construction (garbage, excess soil or rock, etc.) will be stockpiled and disposed of in an approved upland location.
- 8. The project must meet the revegetation performance standards outlined in the specifications before the contractor is released from maintenance responsibilities.

Earthwork Notes:

- 9. If topsoil will be imported, a qualified ecologist will inspect the donor site for undesirable species, noxious weeds, and other indicators of poor soil quality prior to harvest. If problems are observed, the ecologist will make recommendations to City staff.
- 10. All areas to be revegetated will be decompacted to a depth of 12 inches, being sure to leave the finish grade loose. **See photos.**
- 11. All areas to revegetated will also receive 1,000 pounds per acre of Biosol Forte 7-2-1.
- 12. Areas of temporary disturbance for equipment access will be restored to original contours, amended, seeded, and either mulched (if less than 3H:1V slope) or blanketed according to the following specifications.

Planting and Seeding Notes:

- 13. A qualified ecologist will direct and supervise all plant harvest and installation. The exact installation locations for live plant material will be based on the final grading, as determined by a qualified ecologist.
- 14. Live cuttings will be collected on-site or from elsewhere in Weld County (or nearby counties) within 500 vertical feet of near the site. A qualified ecologist must approve collection site(s).

DENVER AND BUENA VISTA, CO  
TEL: 303-586-5014 WEB: ALPINE-ECO.COM



- 15. Live cuttings to be installed on the Lower and Upper Planting Benches (**Table 1**) will be harvested when dormant (before leaves emerge or after they are dropped) from live plants 0.5 to 1.0 inch in diameter. The stem will be stripped of all branches before cutting and then trimmed to the desired length. The lower (rooting) end of the stem will be cut at a 45-degree angle and the upper end will be cut at a 90-degree angle. The lower end of the cuttings will be placed into cold water (<50 degrees F) within one minute of cutting and then transferred to a storage vessel within 1 hour where they will remain completely submerged for at least 72 hours, but not more than 14 days, prior to planting. The water will be kept cold during the entire soaking period. During planting, the cuttings will be kept wet until placed into the ground and will not be allowed out of water for more than 10 minutes.
- 16. Cuttings will be installed to a depth of two-thirds their length (20 inches for the Lower Planting Bench and 40 inches for the Upper Planting Bench), being sure to have the rooting end (45-degree angle cut) at the bottom. After installing, the hole will be backfilled or tamped to ensure no air pockets.
- 17. All seeded areas will be hand-broadcast with the *Riparian Seed Mix* (**Table 2**). Seeding will only be performed between October 1 and when the ground freezes, and when the ground thaws and May 1, unless approved by a qualified ecologist.
- 18. The Lower Planting Bench will be seeded after planting, whereas the Upper Planting Bench will be planted after seeding and blanket installation (planting through the blanket).
- 19. After seeding, all areas to be revegetated that are not blanketed will be hydromulched per the manufacturer’s specifications to achieve approximately 80 percent ground cover. Hydromulch will include a cellulose-based tackifier.
- 20. No equipment will be allowed in the restoration area after decompaction. Biosol, blanket, seed, and mulch must be applied either by hand or by working from the edge of the restoration area.

Literature Cited

Granite Seed and Erosion Control (Granite Seed). 2023. *Revegetation & Conservation Seed*. <http://www.graniteseed.com/>

Prairie Moon Nursery. 2023. *Seeds*. <https://www.prairiemoon.com/seeds/>.

US Army Corps of Engineers (USACE). 2020. *National Wetland Plant List*, version 3.5. [http://wetland\\_plants.usace.army.mil/](http://wetland_plants.usace.army.mil/).

US Department of Agriculture (USDA). 2023. *The PLANTS Database*. <http://plants.usda.gov>. National Plant Data Team, Greensboro, NC 27401-4901 USA.

Western Native Seed. 2023. *Guides*. <http://www.westernnativeseed.com/>

DENVER AND BUENA VISTA, CO  
TEL: 303-586-5014 WEB: ALPINE-ECO.COM


Print Date: Aug 29, 2023
File Name: Planting Plan.dwg

Sheet Revisions		
Date:	Comments	Init.



POUDRE PONDS BANK STABILIZATION PROJECT			
PLANTING NOTES			
No Revisions:			
Revised:			
Void:			

Project No./Code	
20119B	
Sheet Number	LS4



DENVER AND BUENA VISTA, CO  
TEL: 303-586-5014 WEB: ALPINE-ECO.COM



Table 1: Live Plants Needed for Restoration

Common Name <sup>1</sup>	Scientific Name <sup>1</sup>	Plant Size	Total Plants Needed
Lower Planting Bench (one cutting per linear foot; 622 feet)			
Peachleaf willow	<i>Salix amygdaloides</i>	30-inch cutting	62
Narrowleaf willow	<i>Salix exigua</i>	30-inch cutting	560
		Total	622
Upper Planting Bench (one cutting per linear foot; 625 feet)			
Peachleaf willow	<i>Salix amygdaloides</i>	60-inch cutting	63
Narrowleaf willow	<i>Salix exigua</i>	60-inch cutting	562
		Total	625

<sup>1</sup>Plant nomenclature from the *National Wetland Plant List* (USACE 2020)

Summary of Revegetation Sequence

1. Survey and treat noxious weeds
2. Install BMPs and fence work area
3. Complete earthwork
4. Decompect revegetation areas
5. Apply Biosol
6. Install live plants on Lower Planting Bench, then seed and mulch
7. Seed Upper Planting Bench, then install blanket. Install live plants after blanketing.
8. Restore staging area(s) and access road(s) to original contours, decompact, amend the soil, seed, and mulch or blanket.

DENVER AND BUENA VISTA, CO  
TEL: 303-586-5014 WEB: ALPINE-ECO.COM

O:\PROJECT\20100\20119B\04 CAD\ACAD\Drawings\Exhibits\Planting Plan.dwg | Planting Details | kye.maduzia | Aug 29, 2023 - 3:22pm

Print Date: Aug 29, 2023
File Name: Planting Plan.dwg

Sheet Revisions		
Date:	Comments	Init.



No Revisions:
Revised:
Void:

POUDRE PONDS BANK STABILIZATION PROJECT			
PLANTING DETAILS			
Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:	Subset Sheets:		

Project No./Code
20119B
Sheet Number
LS5



O:\PROJECT\20100\20119B\04 CAD\ACAD\Draw\Exhibits\Planting Plan.dwg | Schedules | kye.maduzia | Aug. 29, 2023 - 3:22pm



Table 2: Riparian Seed Mix

Type	Common Name <sup>1</sup>	Scientific Name <sup>1</sup>	Variety	Seeds per Pound	Seeds per Square Foot	Percent of Mix (by weight)	Pounds of Pure Live Seed/Acre
Graminoids	Indian Ricegrass	<i>Achnatherum hymenoides</i>	White River, Paloma, Rimrock, Nezpar	141,000	6.5	4.9	2.00
	Sideoats Grama	<i>Bouteloua curtipendula</i>	Butte or Pierre	191,000	6.6	3.7	1.50
	Buffalograss	<i>Bouteloua dactyloides</i>	Plains	56,000	6.4	12.3	5.00
	Blue Grama	<i>Bouteloua gracilis</i>	Birds Eye, Alma, Lovington, or Hachita	825,000	9.5	1.2	0.50
	Canada Wild Rye	<i>Elymus canadensis</i>	Mandan	114,000	5.2	4.9	2.00
	Squirreltail	<i>Elymus elymoides</i>	Pueblo or Wapiti	192,000	6.6	3.7	1.50
	Fowl Manna Grass	<i>Glyceria striata</i>	-	1,600,000	7.3	0.5	0.20
	Needle and Thread	<i>Hesperostipa comata</i>	-	115,000	6.6	6.1	2.50
	Baltic Rush	<i>Juncus balticus</i>	-	8,000,000	9.2	0.1	0.05
	Prairie Junegrass	<i>Koeleria macrantha</i>	Sims Mesa	2,300,000	5.3	0.2	0.10
	Alkali Muhly	<i>Muhlenbergia asperifolia</i>	-	2,400,000	5.5	0.2	0.10
	Green Needlegrass	<i>Nassella viridula</i>	Cucharas or Lodorm	181,000	4.2	2.5	1.00
	Western-Wheat Grass	<i>Pascopyrum smithii</i>	Arriba	110,000	8.8	8.6	3.50
	Little Bluestem	<i>Schizachyrium scoparium</i>	Pastura, Cimarron, or Camper	260,000	6.0	2.5	1.00
	Indiangrass	<i>Sorghastrum nutans</i>	Cheyenne, Llano, or NE54	180,000	3.3	2.0	0.80
	Freshwater Cord Grass	<i>Spartina pectinata</i>	-	197,000	6.8	3.7	1.50
	Sand Dropseed	<i>Sporobolus cryptandrus</i>	-	5,300,000	6.1	0.1	0.05
Forbs	Common Yarrow	<i>Achillea millefolium var. occidentalis</i>	Eagle, Great Northern, or Yakima	2,700,000	6.2	0.2	0.10
	Showy Milkweed	<i>Asclepias speciosa</i>	-	58,000	2.7	4.9	2.00
	Rocky Mountain Bee Plant	<i>Cleome serrulata</i>	-	66,000	3.8	6.1	2.50
	Golden Tickseed	<i>Coreopsis tinctoria</i>	-	1,400,000	3.2	0.2	0.10
	Purple Prairie Clover	<i>Dalea purpurea</i>	Kaneb	210,000	3.4	1.7	0.70
	Blanketflower	<i>Gaillardia aristata</i>	Meriweather	132,000	3.6	2.9	1.20
	Common Sunflower	<i>Helianthus annuus</i>	-	115,000	3.4	3.2	1.30
	Maximilian Sunflower	<i>Helianthus maximiliani</i>	-	208,000	3.3	1.7	0.70

DENVER AND BUENA VISTA, CO  
TEL: 303-586-5014 WEB: ALPINE-ECO.COM



Type	Common Name <sup>1</sup>	Scientific Name <sup>1</sup>	Variety	Seeds per Pound	Seeds per Square Foot	Percent of Mix (by weight)	Pounds of Pure Live Seed/Acre
	Hairy False Goldenaster	<i>Heterotheca villosa</i>	-	336,000	3.9	1.2	0.50
	Dotted Blazingstar	<i>Liatris punctata</i>	-	168,000	3.5	2.2	0.90
	Lewis Flax	<i>Linum lewisii</i>	Maple Grove	295,000	3.4	1.2	0.50
	Upright Blue Beardtongue	<i>Penstemon virgatus</i>	-	500,000	3.4	0.7	0.30
	Upright Prairie Coneflower	<i>Ratibida columnifera</i>	-	729,500	3.3	0.5	0.20
	Canada Goldenrod	<i>Solidago altissima</i>	-	700,000	3.2	0.5	0.20
	Simpler's-Joy	<i>Verbena hastata</i>	-	1,600,000	3.7	0.2	0.10
	Fourwing Saltbush	<i>Atriplex canescens</i>	-	44,000	1.5	3.7	1.50
Shrubs	Woods' Rose	<i>Rosa woodsii</i>	-	49,000	1.1	2.5	1.00
	Skunkbush Sumac	<i>Rhus trilobata</i>	-	15,500	1.1	7.4	3.00
	Western Snowberry	<i>Symphoricarpos occidentalis</i>	Trapper	74,000	1.2	1.7	0.70
				<b>Total</b>	<b>168.8</b>	<b>100.0</b>	<b>40.80</b>

<sup>1</sup>Nomenclature follows *PLANTS Database* (USDA 2023); seeding rate based on hand-broadcasting; any substitutions must be approved by the project ecologist; seeds per pound from USDA 2023, Granite Seed 2023, Prairie Moon Nursery 2023, Western Native Seed 2023

DENVER AND BUENA VISTA, CO  
TEL: 303-586-5014 WEB: ALPINE-ECO.COM

Print Date: Aug 29, 2023	<div><div></div><div></div><div></div><div></div><div></div></div>	Sheet Revisions		
File Name: Planting Plan.dwg		Date:	Comments	Init.



No Revisions:  Revised:  Void:	POUDRE PONDS BANK STABILIZATION PROJECT				Project No./Code
	PLANTING SCEDULES				20119B
	Designer:	CR	Structure		
	Detailer:	KM	Numbers		
	Sheet Subset:	Subset Sheets:		Sheet Number	LS6



O:\PROJECT\20100120119B\04 CAD\ACAD\Draw\Exhibits\Erosion Control Plan.dwg | ESC Overview | lye.maduzia | Aug 29, 2023 - 3:24pm



GENERAL NOTES:

1. CONTRACTOR SHALL INSTALL ALL PERIMETER SEDIMENT AND EROSION CONTROL DEVICES IN ACCORDANCE WITH THE MILE HIGH FLOOD DISTRICT (MHFD), VOLUME 3 CONSTRUCTION BEST MANAGEMENT PRACTICES. THESE BEST MANAGEMENT PRACTICES INCLUDE, BUT ARE NOT LIMITED TO, SILT FENCE, INLET PROTECTION, VTC PAD, WHEEL WASHOUT, AND SEDIMENT BASINS. BEST MANAGEMENT PRACTICES SHALL BE INSTALLED BEFORE COMMENCING ANY LAND CLEARING OR GRADING ACTIVITIES. THE CONTRACTOR SHALL LIMIT TOPSOIL STRIPPING OPERATIONS TO WITHIN THE AREAS IN WHICH THEY WILL BE IMMEDIATELY WORKING. THE CONSTRUCTION OF UNDERGROUND UTILITIES SHALL BE INCLUDED AS A LAND DISTURBING ACTIVITY. ALL EXCAVATED MATERIAL SHALL BE PLACED WHERE SEDIMENT WILL ERODE BACK INTO THE TRENCH. ALL TRENCHES SHALL BE BACKFILLED BY THE END OF THE DAYS WORK; BACKFILL SHALL BE PERMANENTLY STABILIZED BEFORE CONSTRUCTION IS CONSIDERED COMPLETE.
2. ALL DISTURBED AREAS AND SOIL STOCKPILES SHALL BE ADEQUATELY STABILIZED AS DEFINED IN MHFD, VOLUME 3, CONSTRUCTION BEST MANAGEMENT PRACTICES. ALL DISTURBED SOILS AND SOIL STOCKPILES SHALL BE WATERED AND MAINTAINED IN A ROUGHENED CONDITION AT ALL TIMES DURING CONSTRUCTION ACTIVITIES TO PREVENT WIND-CAUSED EROSION. ALL LAND DISTURBING ACTIVITIES WILL BE IMMEDIATELY DISCONTINUED WHEN FUGITIVE DUST IMPACTS ADJACENT PROPERTIES, AS DETERMINED BY CITY INSPECTOR. PERMANENT OR TEMPORARY NATIVE SEED (SEE EROSION CONTROL STRUCTURES - DETAIL 12-2 FOR SEEDING SPECIFICATIONS) SOIL STABILIZATION SHALL BE REQUIRED WITHIN 14 DAYS AFTER FINAL GRADE IS REACHED. IF DISTURBED AREAS OR STOCKPILES ARE NOT BROUGHT TO FINAL GRADE WITHIN 30 DAYS FOLLOWING THE INITIAL DISTURBANCE, OR RE-DISTURBANCE, TEMPORARY STABILIZATION MEASURES SHALL BE REQUIRED. NO SOIL STOCKPILE SHALL EXCEED TEN (10) FEET IN HEIGHT. ALL SOIL STOCKPILE SIDE SLOPES SHALL NOT EXCEED A SLOPE OF 4V:1H.
3. ALL STORM SEWER INLETS SHALL BE PROTECTED FROM THE ENTRY OF SEDIMENT-LADEN WATER. HAY BALES ARE NOT RECOGNIZED BY THE CITY OF GREELEY AS

AN ACCEPTABLE FORM OF EROSION CONTROL.

4. INSPECTION OF ALL EROSION AND SEDIMENT CONTROL BMP'S SHALL BE REQUIRED AT THE END OF EACH DAY'S WORK, WITH NECESSARY MAINTENANCE AND REPAIRS PROVIDED IMMEDIATELY. THE CITY OF GREELEY INSPECTOR SHALL, AT THEIR DISCRETION, REQUIRE ANY EROSION CONTROL DEVICES TO BE REPAIRED, REPLACED, RELOCATED, MODIFIED, OR REMOVED. SUCH REQUESTS SHALL BE COMPLETED WITHIN 5 WORKING DAYS FOLLOWING THE RECEIPT OF THE WRITTEN REQUEST FROM THE INSPECTOR. ALL PUBLIC RIGHT OF WAY POLLUTED WITH DIRT, MUD, OR DEBRIS SHALL BE SWEEPED CLEAN AT THE END OF EACH DAYS WORK OR AFTER STORM EVENTS, AS NECESSARY. ALL TEMPORARY AND PERIMETER EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED AS SOON AS THEIR FUNCTION HAS BEEN FULFILLED. SEDIMENT TRAPS/BASINS SHALL BE CLEANED AND REMOVED, OR STABILIZED, WHEN ALL UPSTREAM AREAS ARE PERMANENTLY STABILIZED. THE SITE CONTRACTOR IS RESPONSIBLE FOR PROPERLY DISPOSING OFF ALL SILT FROM THE SITE, IF IT IS NOT REUSABLE ON SITE.
5. THE LANDOWNER SHALL BE HELD RESPONSIBLE FOR THE LONG-TERM STABILITY OF CUT AND FILL SLOPES AND THE SUCCESSFUL ESTABLISHMENT OF PERMANENT VEGETATIVE COVER ON EXPOSED SOIL AS DEFINED IN THE MHFD, VOLUME 3, CONSTRUCTION BEST MANAGEMENT PRACTICES.
6. ALL CONSTRUCTION SUPPLIES OR MATERIALS USED OR STORED ON SITE MUST BE DISPOSED OF PROPERLY AND MUST MEET ALL APPLICABLE MATERIAL SAFETY DATA SHEET CRITERIA.
7. THE STATE STORMWATER DISCHARGE PERMIT HOLDER MAY BE LIABLE FOR ANY VIOLATIONS RESULTING FROM THE ACTIONS TAKEN BY SITE CONTRACTORS, SUBCONTRACTORS, MAINTENANCE CREWS, ETC.

Print Date: Aug 29, 2023

File Name: Erosion Control Plan.dwg



Sheet Revisions

Date:	Comments	Init.



No Revisions:

Revised:

Void:

POUDRE PONDS BANK STABILIZATION PROJECT

EROSION CONTROL PLAN OVERVIEW

Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:	

Project No./Code

20119B

Sheet Number

ESC1




C:\PROJECT\20100\20119B\04 CAD\ACAD\Draw Exhibits\Erosion Control Plan.dwg | ESC INT 1 | kye.maduzia | Aug 29, 2023 - 3:24pm



Print Date: Aug 29, 2023
File Name: Erosion Control Plan.dwg

Sheet Revisions		
Date:	Comments	Init.



No Revisions:
Revised:
Void:

POUDRE PONDS BANK STABILIZATION PROJECT			
INITIAL EROSION CONTROL PLAN 1			
Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:	

Project No./Code
20119B
Sheet Number
ESC2



O:\PROJECT\20100\20119B\04 CAD\ACAD\Draw\Exhibits\Erosion Control Plan.dwg | ESC INT 2 | kye.maduzia | Aug 29, 2023 - 3:24pm




**LEGEND:**

- (SF) SILT FENCE
- (EROSION CONTROL FABRIC)
- (SSA) STABILIZED STAGING AREA
- (PT) PORTABLE TOILET
- (SM) SEEDING AND MULCHING
- (VTC) VEHICLE TRACKING CONTROL
- (LOD) LIMITS OF DISTURBANCE
- (ACCESS ROAD)
- (CONSTRUCTION FENCE)
- (DW) DEWATERING
- (TEMPORARY DIVERSION)

Print Date: Aug 29, 2023
File Name: Erosion Control Plan.dwg

Sheet Revisions		
Date:	Comments	Init.



No Revisions:
Revised:
Void:

POUDRE PONDS BANK STABILIZATION PROJECT			
INITIAL EROSION CONTROL PLAN 2			
Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:	

Project No./Code
20119B
Sheet Number
ESC3



O:\PROJECT\20100\20119B\04 CAD\ACAD\Draw\Exhibits\Erosion Control Plan.dwg | ESC INT 3 | kye.maduzia | Aug 29, 2023 - 3:24pm



0' 20' 40' 80'

1 INCH = 80 FEET (11 X 17)  
1 INCH = 40 FEET (22 X 34)




LEGEND:

- (SF) SILT FENCE
- EROSION CONTROL FABRIC
- (SSA) STABILIZED STAGING AREA
- (PT) PORTABLE TOILET
- (SM) SEEDING AND MULCHING
- (VTC) VEHICLE TRACKING CONTROL
- (LOD) LIMITS OF DISTURBANCE
- ACCESS ROAD
- CONSTRUCTION FENCE
- (DW) DEWATERING
- TEMPORARY DIVERSION

90% DESIGN - August 29, 2023

Print Date: Aug 29, 2023
File Name: Erosion Control Plan.dwg

Sheet Revisions		
Date:	Comments	Init.



No Revisions:
Revised:
Void:

POUDRE PONDS BANK STABILIZATION PROJECT			
INITIAL EROSION CONTROL PLAN 3			
Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:	

Project No./Code
20119B
Sheet Number
ESC4





- LEGEND:**
- (SF) SILT FENCE
  - (EROSION CONTROL FABRIC)
  - (SSA) STABILIZED STAGING AREA
  - (PT) PORTABLE TOILET
  - (SM) SEEDING AND MULCHING
  - (VTC) VEHICLE TRACKING CONTROL
  - (LOD) LIMITS OF DISTURBANCE
  - (ACCESS ROAD)
  - (CONSTRUCTION FENCE)
  - (DW) DEWATERING
  - (TEMPORARY DIVERSION)

C:\PROJECT\201100\201119B.dwg	Print Date: Aug 29, 2023		Sheet Revisions					POUDRE PONDS BANK STABILIZATION PROJECT				Project No./Code		
	File Name: Erosion Control Plan.dwg							INTERIM EROSION CONTROL PLAN 1				20119B		
	<div><div></div><div></div><div></div><div></div><div></div></div>	Date:	Comments	Init.				No Revisions:	Designer: CR		Structure			
									Revised:	Detailer: KM		Numbers		
									Void:	Sheet Subset:		Subset Sheets:		Sheet Number ESC5

C:\PROJECT\20100\20119B\04 CAD\ACAD\Draw\Exhibits\Erosion Control Plan.dwg | ESC INT 1 | kye.molizua | Aug 29, 2023 - 3:25pm







C:\PROJECT\20100\20119B\04 CAD\ACAD\DWG\Exhibits\Erosion Control Plan.dwg | ESC INT 3 | kye.maduzia | Aug 29, 2023 - 3:25pm



0' 20' 40' 80'


1 INCH = 80 FEET (11 X 17)  
1 INCH = 40 FEET (22 X 34)



LEGEND:	
	(SF) SILT FENCE
	EROSION CONTROL FABRIC
	(SSA) STABILIZED STAGING AREA
	(PT) PORTABLE TOILET
	(SM) SEEDING AND MULCHING
	(VTC) VEHICLE TRACKING CONTROL
	(LOD) LIMITS OF DISTURBANCE
	ACCESS ROAD
	CONSTRUCTION FENCE
	(DW) DEWATERING
	TEMPORARY DIVERSION

Print Date: Aug 29, 2023
File Name: Erosion Control Plan.dwg

Sheet Revisions		
Date:	Comments	Init.



No Revisions:
Revised:
Void:

POUDRE PONDS BANK STABILIZATION PROJECT			
INTERIM EROSION CONTROL PLAN 3			
Designer:	CR	Structure	
Detailer:	KM	Numbers	
Sheet Subset:		Subset Sheets:	

Project No./Code
20119B
Sheet Number
ESC7











O:\PROJECT\20100\20119B\04 CAD\ACAD\Drawings\Exhibits\Erosion Control Plan.dwg | ESC FIN 3 | kye.maduzia | Aug 29, 2023 - 3:25pm



0' 20' 40' 80'

1 INCH = 80 FEET (11 X 17)  
1 INCH = 40 FEET (22 X 34)



LEGEND:

- (SF) SILT FENCE
- EROSION CONTROL FABRIC
- (SSA) STABILIZED STAGING AREA
- (PT) PORTABLE TOILET
- (SM) SEEDING AND MULCHING
- (VTC) VEHICLE TRACKING CONTROL
- (LOD) LIMITS OF DISTURBANCE
- ACCESS ROAD
- CONSTRUCTION FENCE
- (DW) DEWATERING
- TEMPORARY DIVERSION

Print Date: Aug 29, 2023

File Name: Erosion Control Plan.dwg



Sheet Revisions

Date:	Comments	Init.



No Revisions:

Revised:

Void:

POUDRE PONDS BANK STABILIZATION PROJECT

FINAL EROSION CONTROL PLAN 3

Designer:	CR	Structure Numbers	
Detailer:	KM		
Sheet Subset:		Subset Sheets:	

Project No./Code

20119B

Sheet Number ESC10



