

Permit M-1980-244

Cresson Project Amendment 14

Exhibit L

Reclamation Costs

TABLE OF CONTENTS

1 RECLAMATION COSTS	1
1.1 Introduction and Approach	1
2 PROJECT FINANCIAL WARRANTY REQUIREMENTS.....	2
3 RECLAMATION EARTHOVING COSTS.....	3
3.1 Scrapers and Trucks	3
3.2 Loaders.....	3
3.3 Bulldozers (Dozers)	3
3.4 Support Equipment.....	3
3.5 Other Equipment	4
4 CALCULATION OF PRODUCTION RATES FOR EQUIPMENT.....	4
5 CALCULATION OF REVEGETATION COSTS	4
6 CALCULATION OF DEMOLITION COSTS	4
7 CALCULATION OF DETOXIFICATION COSTS	5
8 SUMMARY	5
9 REFERENCES	5

1 RECLAMATION COSTS

The following sections present a summary of financial liabilities associated with Amendment 14 and all previous existing liabilities. A detailed analysis of reclamation costs is provided herein.

1.1 Introduction and Approach

The financial warranty calculations addressed below include the reclamation for the entire Cresson Project, including the activities of this Amendment 14. Updated and current reclamation costs have been provided, including facility changes to support the planned activities associated with this Amendment 14.

Included in the cost calculation are the following facilities and related cost items.

- Portal access
- Portal support facilities
- Development mining areas
- Main Cresson Mine area
- East Cresson Mine area
- North Cresson Mine area
- South Cresson Mine area
- Dump 1 (formerly SGOSA)
- East Cresson Overburden Storage Area (ECOSA)
- Valley Leach Facility (VLF) Rinsing and Neutralization for both VLF1 and VLF2
- VLF Physical Reclamation for both VLF1 and VLF2
- Arequa Gulch Adsorption, Desorption and Recovery (AGAD, also referred to as ADR1) and Adsorption, Desorption and Recovery 2 (ADR2, formerly SGADR) facilities
- High Grade (HG) Mill facilities
- External Solution storage Pond (ESP), Sediment Ponds, and Storm Water Control Basins
- Monitoring wells and piezometers
- Haul roads
- Growth medium storage areas
- Powerlines
- Support buildings and footprints
- Surface mine highwall fencing
- Clean-up and miscellaneous areas
- Revegetation repairs and maintenance
- Ancillary areas
- Viewshed conservation areas

- Mobilization and de-mobilization of equipment
- Indirect costs (e.g., public liability, contractor's performance bond, overhead and profit, regulator management fee, and contingency)

The reclamation liability for the life of mine build out has been calculated using the Standard Reclamation Cost Estimator (SRCE). Output from the SRCE is attached to this narrative. Cripple Creek & Victor Gold Mining Company (CC&V) will provide the Division with an annual financial warranty update at the end of October each year. This update will provide an estimated financial warranty for the following years planned disturbance. The financial warranty updated will include updated unit costs, labor costs, and material costs. Additionally, CC&V will use the Closure and Reclamation technical template (CRTT) to prorate the full build in SRCE to reflect the following years year's liability. This is consistent with the incremental bonding approach previously used by CC&V and accepted by the Division of Reclamation, Mining and Safety (DRMS), and is consistent with the Mined Land Reclamation Act and Rules and Regulations. The financial warranty estimate has been developed to support this approach.

The general approach for cost estimating involved calculating the areas and volumes for particular facilities using either direct measurements from software programs (e.g., AutoCAD and Minesight), constructing cross-sections before and after reclamation, measuring from aerial photos using a polar planimeter, or simple computations involving lengths, widths, and heights. Using the volumes and areas determined as above, earthmoving and reclamation equipment were selected based on productivities developed for the specific project involved using such resources as the *Caterpillar Performance Handbook*, time study information, and professional engineering judgment, where appropriate.

For most facilities the basic outline of reclamation involves the following sequential steps: (1) grading, slope reduction, re-contouring with dozers or scrapers; (2) replacing growth medium to a depth of approximately six inches; (3) preparing a seed-bed by scarifying or ripping; (4) revegetation consisting of fertilizing, seeding, and mulching; and (5) planting trees and shrubs on north- and east-facing slopes.

2 PROJECT FINANCIAL WARRANTY REQUIREMENTS

To ensure that the Cresson Project is reclaimed, CC&V will post an appropriate financial warranty, the amount of which has been computed in accordance with the practices used in previously submitted financial warranty computations. Costs developed are in year 2024 dollars. The financial warranty calculations include those items requiring reclamation at the Cresson Project and the appropriate DRMS administration fees. Thereafter, the financial warranty will be reviewed on a periodic basis and adjusted accordingly for the cost to reclaim lands to be affected in the

coming period plus the cost to reclaim those lands affected in previous years and not yet fully reclaimed.

Relevant costs have been included in the computations for reclamation and closure activities for the entire Cresson Project including the activities associated with Amendment 14. The costs have been developed assuming that an independent (i.e., 3rd-Party) contractor will perform the reclamation activities. The procedures followed and the assumptions used to develop the financial warranty are discussed in the following sections.

3 RECLAMATION EARTHMOVING COSTS

The estimated reclamation costs have been developed on the basis of standard production rates for equipment normally used for reclamation work. The costs assume the work is completed by an independent contractor using the following pieces of major equipment.

3.1 Scrapers and Trucks

Scrapers and trucks were assumed to transport the growth medium and to perform certain grading and re-contouring work. For this cost estimate, Caterpillar (Cat) 623 (single engine) scrapers and trucks (Cat 740 and 777C) were used in determining the productivity rates of hauling suitable growth medium from storage areas and in certain instances these machines were used for hauling neutralized ore (VLFs) or overburden (OSAs) to achieve final contours.

3.2 Loaders

Cat 988B and 992D loaders were assumed to be used to load the Cat 740 and 777 haul trucks. A smaller loader (e.g., 972 model) was assumed for loading other materials needed for reclamation.

3.3 Bulldozers (Dozers)

Dozers were assumed to be used for most heavy grading, re-contouring, and slope reduction for the larger facilities such as the surface mine backfills, the VLFs, and the OSAs. For this work, Cat D10 and D11 dozers were assumed in the cost estimate.

3.4 Support Equipment

Earthmoving activities on a large scale will require support equipment such as dozers for spreading growth medium, water trucks for controlling dust on the haul roads, and graders to maintain the haul road surface. In most cases, the respective equipment selected for these tasks

consisted of a D9 dozer for spreading growth media, 5,000-gal water truck to water haul roads for dust control, and a CAT Model 14 grader for maintaining haul roads.

3.5 Other Equipment

Revegetation equipment selected included either a CAT D8 dozer or a CAT D4 dozer mounted with a cyclone style seeder, chain, or harrow depending on the severity of the slope to be traversed. A combination hydro-seeder/hydro-mulcher was selected for distributing wood fiber hydro-mulch and for some of the seeding effort. A conventional agricultural helicopter was selected for the steeper slope seeding and fertilizing where normal agricultural equipment cannot be expected to operate. Other minor pieces of equipment used for specific tasks as outlined on the individual facility cost sheets also were included in the cost estimate.

4 CALCULATION OF PRODUCTION RATES FOR EQUIPMENT

Using the volumes and areas computed for the various facilities to accomplish reclamation, production rates (also known as "productivities") for the selected equipment were developed in the SRCE, taking into account such factors as characteristics of materials handled (i.e., loose, hard, wet, dense, etc.), haul distance, grade resistance, operator efficiency, equipment utilization rate, capacity of loader buckets and truck beds, etc. It should be noted that for the equipment selected for the financial warranty estimate, machine productivities predicted by the *Caterpillar Performance Handbook* do not significantly vary between editions, and changes in cost are governed mostly by price escalation and haul distances.

5 CALCULATION OF REVEGETATION COSTS

Various seed mixtures used at CC&V have been evaluated and improved upon as appropriate during the course of completing concurrent reclamation projects. As a result, CC&V continues to obtain species best suited for reclaiming of the Cresson Project. It is CC&V's experience that certain species will be replaced with improved native or adapted species capable of supporting the wildlife habitat and livestock grazing post-mining land uses. Revegetation costs are based on actual costs for seed and the Division's application costs as approved in Technical Revision (TR) 115 (TR-115).

CALCULATION OF DEMOLITION COSTS

The demolition cost for most structures were adjusted to exceed or match the latest version of *R.S. Means Heavy Construction Cost Data for 2018*, using the dimensions of the structure and applying an appropriate cost per unit of volume. SRCE has revised assumptions about facility demolition, a premium was applied to the SRCE unit cost to meet or exceed the RSMeans Rate.

This cost estimate does not account for the salvage value, or the scrap metal value of materials generated during a large-scale project.

6 CALCULATION OF DETOXIFICATION COSTS

The detoxification procedure for the VLFs is consistent with prior submittals and includes using two pore volumes of water to rinse with a series of resting and rinsing periods followed by an application of one pore volume of H₂O₂ treated water. The rinsing is followed by a period of water sampling to determine whether neutralization of the facilities have been achieved to acceptable standards. The rinse objective is to achieve an average of less than 0.2 milligrams per liter (mg/L) of weak acid dissolute cyanide (CN_{WAD}) in the rinse water from the facilities. Current CC&V operating costs have been used to establish water-handling costs in this estimate.

7 SUMMARY

Financial warranty requirements for reclamation of the Cresson Project through the end of 2024 have been estimated to be approximately \$205,084,543 USD. The overall costs will be incrementally adjusted year as disturbance is increased.

8 REFERENCES

Caterpillar Performance Handbook. Caterpillar. Peoria, Illinois. June 2018.

Heavy Construction Costs with RSMeans Data 2018. RSMeans Co. 2018.

AM-14 Financial Warranty

Activity	Unit	U. Cost \$	Liability Percentage	Totals AM-14 FW
Direct Costs				
1.0) Roads, Railroads, Airstrips				\$2,879,261
Reclamation Area				\$2,879,261
Road Maintenance		\$2,879,261	100%	\$2,879,260.80
2.0) Drill Sites, Drill Pads, Exploration Trenches				
Reclamation Area				
3.0) Drill Hole Abandonment	EA			\$102,960
Well Abandonment (unit ea.)		71.00	\$1,450.14	100%
4.0) Pits, Borrow Areas & Trenches -	CY			
	Acre			
4.1) Portals/Adits Underground Mines				\$100,514
Chicago Tunnel		1	\$100,514	100%
5.0) Non-Process Ponds & Reservoirs	CY			\$567,843
Reclamation Area	Acres			
EMP ponds (Backfill)		79,719.00	\$2.63	100%
Crusher fuel island fresh water pond (Backfill)		1,257.00	\$2.80	100%
Arequa external ponds (Backfill)		85,438.00	\$2.63	100%
EMP ponds (topsoil)		4,572.00	\$2.56	100%
Crusher fuel island fresh water pond (topsoil)		186.00	\$6.30	100%
Arequa external ponds (topsoil)		4,637.00	\$2.53	100%
EMP ponds (Seed)		5.70	\$1,394.56	100%
Crusher fuel island fresh water pond(Seed)		0.20	\$2,193.51	100%
Arequa external ponds (Seed)		5.70	\$1,394.56	100%
EMP ponds (Remove Liner)		1.00	\$42,381.00	100%
Crusher fuel island fresh water pond (Remove Liner)		1.00	\$710.00	100%
Arequa external ponds(Remove Liner)		1.00	\$45,460.00	100%
6.1) Water Treatment/Management Heap Leach Pads				\$74,653,118
Treatment Volume				
VLF1 Rinse		1.00	\$61,394,174	85.20%
VLF2 Rinse		1.00	\$48,670,814	44.83%
Drilling to perforate liner		1.00	\$526,296	100%
7.0) Heap Leach Pad Reclamation	CY			\$31,688,107
Reclamation Area	Acre			
VLFs Tree planting		115.00	\$1,146.97	64.55%
Heaps-Earthwork/Recontouring (unit cy)		14,796,076.00	\$0.29	64.55%
Heaps-Topsoil		1,005,100.00	\$2.69	64.55%
Heaps- Generic Hauling		24,883,444.00	\$1.61	64.55%
Heaps-Revegetation/Stabilization (unit acres)		1,248.49	\$1,569.08	64.55%
8.0) Waste Rock Dump, Stockpile, Landfill Reclamation	CY			\$13,348,248
Reclamation Area	Acres			
Ironclad Mine Area Rgrade		51,824.00	\$0.23	100%
SGOSA Rgrade		1,967,151.00	\$0.47	100%
North Cresson Rgrade		3,402,023.00	\$0.51	
ECOSA Rgrade		5,891,686.00	\$0.67	75.51%
Main Cresson Rgrade		2,767,168.00	\$1.39	100%
Chicago Tunnel area Rgrade		3,228.00	\$0.22	100%
Ironclad Mine Area Topsoil		21,062.00	\$2.11	100%
SGOSA Topsoil		138,924.00	\$2.02	100%
North Cresson Topsoil		136,239.00	\$2.42	
ECOSA Topsoil		705,801.00	\$2.38	75.51%
Main Cresson Topsoil		257,368.00	\$2.38	100%
Chicago Tunnel area Topsoil		3,227.00	\$1.25	100%
Ironclad Mine Area Revegetation		26.62	\$1,615.93	100%
SGOSA Revegetation		173.92	\$1,625.83	100%
North Cresson Revegetation		170.19	\$1,632.25	
ECOSA Revegetation		877.86	\$1,632.93	75.51%
Main Cresson Revegetation		320.91	\$1,642.95	100%
Chicago Tunnel Area Revegetation		4.20	\$1,597.38	100%
Waste rock dump Trees		1,418.60	\$1,146.97	85.98%
WHEX Clay Borrow - Rgrade (EMP-18)		1,870.00	\$0.69	100.00%
WHEX Clay Borrow Topsoil		10,382.00	\$2.14	100.00%
WHEX Clay Borrow Revegetation		12.87	\$1,676.85	100.00%

AM-14 Financial Warranty

9.0) Tailing Storage Facility Reclamation				
Reclamation Area				
10.0) Drainage/Diversion Channels				\$12,931,769
Reclamation Area				
Construct Stormwater	1	\$17,181,963.85	75.26%	\$12,931,769
11.0) Facilities Demolition				\$14,591,012
Foundations & Building Areas Earthworks/Recountouring	66,897.00	\$4.08	100%	\$273,030
Foundations & Building Areas Revegetation/Stabilization	12.40	\$5,562	100%	\$68,968
Foundations & Building Demolition (cubic feet)	18,556,242.00	\$0.29	100%	\$5,352,624
Yards, etc-Revegetation/Stabilization (acres)- Includes Ancillary Area Enhancement	1,549.80	\$1,572.21	100%	\$2,436,608
Other Demo -Mill Conveyor (feet) and Septic System (each)	1.00	\$138,459.04	100%	\$138,459
Tank Demolition (number of)	58.00	\$7,603.64	100%	\$441,011
Fence Removal (feet)	12,285.00	\$3.84	100%	\$47,176
Fence Installation (feet)	39,306.00	\$49.44	100%	\$1,943,289
Pipe Removal (feet)	44,904.00	\$11.40	100%	\$511,906
Powerline and Substation Removal (miles)	9.13	\$39,731.00	100%	\$362,744
Waste Disposal - Liquid (Gallons)	440,000.00	\$6.42	100%	\$2,824,899
Tire Disposal	50.00	\$1,005.07	100%	\$50,254
Yard Tree planting	122.10	\$1,146.97	100%	\$140,045
12.0) Facilities/Equipment Disposition and/or Salvage				
13.0) Inventory Disposition				
14.0) Post Closure Monitoring				\$2,035,325
Closure Monitoring	1	\$2,704,270	75.26%	\$2,035,325
Total Direct Costs				\$152,898,157.13
Indirect Costs				
15.0) Socio-Economic Costs				
16.0) Consultant Services				\$2,603,510
Active Reclamation Construction Management	1.00	\$3,459,188.00	75.26%	\$2,603,510
17.0) Contractor's Overhead & Profit (if not included in direct costs)				\$47,403,778
total effective rate of DRMS indirect costs 28.5% (Overhead and profit, administrative, insurance, performance bond, Engineering, Contingency)		\$62,983,651.0	75.26%	\$47,403,778
18.0) Owners Management (post closure)				\$1,558,927
Environmental Personnel, Administrative Management and Consumables	1.00	\$1,558,927	100.00%	\$1,558,927
19.0) Mobilization and Demobilization (if not included in direct costs)				\$620,171
Mob-Demob	1.0	\$620,190.52	100.00%	\$620,171
Subtotal-Incremental				\$205,084,543.09
20.0) Contingency at 5% (calculated in item 17 O&P)				
Total-C&R-Incremental				\$205,084,543.09

This worksheet should be used for calculations
and/or explanations related to the facility/closure category
required to back-up unit rates or calculations.

SEE SCRE MODEL CALCULATION

FOR FASB PERCENTAGE COMPLETE (from Engineering)

	Design	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032
VLF 1	432,519,716	368,519,716	368,519,716	368,519,716	368,519,716	368,519,716	368,519,716	368,519,716	368,519,716	368,519,716	368,519,716	368,519,716
% Complete		85%	85%	85%	85%	85%	85%	85%	85%	85%	85%	85%
VLF 2	453,000,000	148,430,153	175,850,023	203,061,529	228,425,380	251,531,197	273,527,033	300,527,032	324,510,769	346,613,635	356,601,253	368,243,779
% Complete		33%	39%	45%	50%	56%	60%	66%	72%	77%	79%	81%
Both VLF1&2	885,519,716	58%	61%	65%	67%	70%	73%	76%	78%	81%	82%	83%

This worksheet should be used for calculations
and/or explanations related to the facility/closure category
required to back-up unit rates or calculations.

SEE SCRE MODEL CALCULATION

FOR FASB CALCULATION (from Engineering)

	Design	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032
ECOSA	267,838,478	185,013,958	197,809,880	202,250,373	206,020,434	217,825,952	232,745,062	246,926,272	257,315,025	263,926,484	267,838,478	267,838,478
% Complete		69%	74%	76%	77%	81%	87%	92%	96%	99%	100%	100%
SGOSA	199,969,736	199,969,736	199,969,736	199,969,736	199,969,736	199,969,736	199,969,736	199,969,736	199,969,736	199,969,736	199,969,736	199,969,736
% Complete		100%	100%	100%	100%	100%	100%	100%	100%	100%	100%	100%
Schist Island Backfill				10,818,308	23,448,146	26,816,042	26,816,042	26,816,042	26,816,042	26,816,042	26,816,042	26,816,042
% Complete	.											
Main Cresson Backfill				1,300,674	1,300,674	6,607,929	12,587,287	15,106,077	15,494,627	18,744,121	39,871,472	47,054,173
% Complete												
Total Waste Dumps	467,808,214	82%	85%	86%	87%	89%	92%	96%	98%	99%	100%	100%

**Closure Cost Estimate
Property Information**

STANDARDIZED RECLAMATION COST ESTIMATOR

**Version 2.0
Build - Beta 01**

COST DATA FILE INFORMATION

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Data Date: March 27, 2024
Cost Data Basis: User Data Data Cost Units: Imperial
Author/Source: 2018, 2019, 2020, 2022 Nevada Division of Environmental Protection (NDEP) & NV BLM

PROJECT INFORMATION

Property/Mine Name: CC&V Property Code: _____
Project Name: AM-14 Financial Warranty Update
Date of Submittal: April 2024 Average Elevation 9900 ft.
Units of Measure: Metric (m, km, ha, etc.) Imperial (ft, mi, acres, etc.)
Currency Symbol: Dollar (US)
Project Type: Mine Operations Plan
Land Type: Private Land
Cost Basis Category: AM-14 CC&V - US ▾
Cost Basis Description: Adjusted for escalation, Labor: 1.03, Equipment: 1.03, Tires: 1.03, Reclamation Materials: 1.03, Misc. Costs: 1.03

Copyright© 2004-2019
SRCE Software. All Rights Reserved

**Closure Cost Estimate
Acct Codes**

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Cost type:	ARO
Budget Year:	2022
First Year of Operation:	2009
Closure Year 1:	2030
Closure Period:	12 years
Post Closure Period:	14 years
ID Code Filter:	
FacilityType Filter:	
Phase Filter:	
Location Filter:	
Property Filter:	
Discount Rate:	0.0%
Discount Period:	MOP
Year of NPV:	
Engineering, Design and Construction Plan (%):	0.0%
Contingency (%):	0.0%
Contractor OH and Profit (CP)(%):	28.5%
Contract Administration (%):	0.0%
Show how many years in schedule (10 to 150):	100
Show how many operating years in schedule:	10

Facility/Activity Type	Acct Code	Total Cost \$	Scheduled ARO Cost \$	
			ARO Cost	ARO Cost
1 Roads, Railroads, Airstrips	1	2,879,261	2,879,261	2,879,261
2 Drill sites, Drill Pads, Exploration Trenches	2	0	0	0
3 Drill Hole Abandonment	3	102,960	102,960	102,960
4 Open Pits, Borrow Areas, & Trenches	4	0	0	0
5 Portals / Adits Underground Mines	4.1	100,514	100,514	100,514
6 Non-Process Ponds & Reservoirs	5	567,843	567,843	567,843
7 Water Treatment-Leach Pad Drain Down	6.1	110,615,231	110,615,231	110,615,231
8 Water Treatment- Pit Lakes	6.2	0	0	0
9 Water Treatment-Waste Dump Seepage	6.3	0	0	0
10 Water Treatment-Tails Storage Under-drain	6.4	0	0	0
11 Heap Leach Pads Reclamation	7	48,965,510	48,965,510	48,965,510
12 Dumps , Stockpiles, Landfills	8	17,638,089	17,638,089	17,638,089
13 Tail Storage Facility (TSF)	9	0	0	0
14 Drainage / Diversion Channels	10	17,181,964	17,181,964	17,181,964
15 Facilities Demolition	11	14,623,286	14,601,321	14,601,321
16 Facility/Equipment Disposition and/or Salvaging	12	0	0	0
17 Inventory Disposition	13	0	0	0
18 Monitoring	14	2,704,270	2,704,270	2,704,270
19 Socio-Economic Activities	15	0	0	0
20 Consultants Services	16	3,459,188	3,459,188	3,459,188
21 Contractor's O'head, & Profit (if not included in direct costs)	17	0	0	0
22 Owner's Management (Post Closure)	18	1,558,927	1,558,927	1,558,927
23 Mobilization and Demobilization	19	620,191	620,191	620,191
TOTALS		221,017,233	220,995,268	220,995,268

Engineering, Design and Construction Plan	0	0	0
Contingency	0	0	0
Contractor OH and Profit	62,989,911	62,983,651	62,983,651
Contract Administration	0	0	0
TOTAL COST	284,007,144	283,978,919	283,978,919

Closure Cost Estimate
Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsx

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx

Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Waste Rock Dumps - ARO Cost Summary

	Labor \$	Equipment \$	Materials \$	Totals \$
Grading Costs	2,236,504	8,208,026	N/A	10,444,530
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	322,265	2,641,507	N/A	2,973,655
Ripping/Scarfing Cost	65,465	305,160	N/A	391,625
Subtotal Earthworks	2,655,256	11,154,803		13,810,059
Revegetation Cost	220,884	83,715	0	113,590
TOTALS	2,885,140	11,238,518	0	14,123,659

Waste Rock Dumps - User Input

	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Ground Slope at Toe % Grade	Ungraded Slope H:1V	Final Top Slope H:1V	Lift (dump) Height ft	Mid-Bench Length	Average Long Dimension (ripping distance) ft	Final (Regraded) Footprint acres	Regrade Volume (if calculated elsewhere) cy	Physical - MANDATORY			Cover 1			Cover 2			Growth Media		
																	Cover Slopes in	Cover Thickness Flat Areas in	Haul Distance to Placement Location (2) ft	Slope to Placement % grade	Cover Slopes in	Cover Thickness Flat Areas in	Haul Distance to Placement Location (2) ft	Slope to Placement % grade	Slope Growth Media Thickness in	Flat Area Growth Media Thickness in	Haul Distance to Placement Location ft	Slope to Placement % grade
1	Ironclad Mine Area - Pile Leveling - Mass Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	10.0	1.0	5	0			5,933												
2	Ironclad Mine Area - Pile Leveling - Fine Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	10.0	1.0	5	0			659												
3	Ironclad Mine Area - 40 ft Lift - Mass Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	5.0	1.0	40	0			21,753											
4	Ironclad Mine Area - 40 ft Lift - Fine Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	5.0	1.0	40	0			2,417											
5	Ironclad Mine Area - Topsoil	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	10.0	1.0	5	100	300	26.30	0												
6	Ironclad Mine Area - Topsoil - Dozer Spreading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	10.0	1.0	5	100			21,062												
7	SGOSA Mine Area - Pile Leveling - Mass Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	10.0	1.0	5	0			2,088												
8	SGOSA Mine Area - Pile Leveling - Fine Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	10.0	1.0	5	0			232												
9	SGOSA Mine Area - 100 ft lift - Mass Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	100	0			89,714											
10	SGOSA Mine Area - 100 ft lift - Fine Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	100	0			9,343											
11	SGOSA Mine Area - 150 ft lift - Mass Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	200	0			11,154											
12	SGOSA Mine Area - 150 ft lift - Fine Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	200	0			27,634											
13	SGOSA Mine Area - 200 ft lift - Mass Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	250	0			156,497											
14	SGOSA Mine Area - 200 ft lift - Fine Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	250	0			17,387											
15	SGOSA Mine Area - 250 ft lift - Mass Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	300	0			113,624											
16	SGOSA Mine Area - 250 ft lift - Fine Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	300	0			12,625											
17	SGOSA Mine Area - 300 ft lift - Mass Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	350	0			265,933											
18	SGOSA Mine Area - 300 ft lift - Fine Grading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	350	0			29,548											
19	SGOSA Mine Area - Topsoil - Lift 1	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	10.0	1.0	100	1,000	245	5.76													
20	SGOSA Mine Area - Topsoil - Lift 1 - Dozer Spreading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	10.0	1.0	100	100			18,610												-3.7
21	SGOSA Mine Area - Topsoil - Lift 2	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	100	1,762	245	11.23											-0.5	
22	SGOSA Mine Area - Topsoil - Lift 2 - Dozer Spreading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	100			14,415												
23	SGOSA Mine Area - Topsoil - Lift 3	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	100	2,659	245	19.16											8.6	
24	SGOSA Mine Area - Topsoil - Lift 3 - Dozer Spreading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	100			24,337												
25	SGOSA Mine Area - Topsoil - Lift 4	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	100	6,781	245	53.98											8.5	
26	SGOSA Mine Area - Topsoil - Lift 4 - Dozer Spreading	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	100			46,311												
27	SGOSA Mine Area - Topsoil - Lift 5	2009	Dumps, Stockpiles, Landfills					ARO+LOM+FA	0.0	1.4	2.5	1.0	100	5,218	245	57.65											9.3	
28	SGOSA Mine Area - Topsoil - Lift 5 - Dozer Spreading	2009	Dumps, Stockpiles, Landfills																									

Closure Cost Estimate Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xls

Waste Rock Dumps - ARO Cost Summary		Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US																					
		Labor \$	Equipment \$	Materials \$	Totals \$																		
Grading Costs		2,236,504	8,208,026	N/A	10,444,530																		
Cover 1 Placement Cost		0	0	N/A	0																		
Cover 2 Placement Cost		0	0	N/A	0																		
Topsoil Placement Cost		332,286	2,641,597	N/A	2,973,883																		
Ripping/Scarifying Cost		86,466	305,180	N/A	391,646																		
Subtotal Earthworks		2,655,256	11,154,803		13,810,059																		
Revegetation Cost		229,884	83,715	0	313,599																		
TOTALS		2,885,140	11,238,518	0	14,123,658																		
63	ECOSA Mine Area - Topsoil - Lift 6	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150	1,500	300	24.92	0					6.0	6.0	9,080	-8.9
64	ECOSA Mine Area - Topsoil - Lift 6 - Dozer Spreading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150					20,957							
65	East Cresson Mine Area - Pile Leveling - Mass Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	10.0	10.0	1.0	5	0				473							
66	East Cresson Mine Area - 40 lift - Mass Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	10.0	10.0	1.0	5	0				53							
67	East Cresson Mine Area - 40 lift - Fine Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	40	0				12,777							
68	East Cresson Mine Area - 40 lift - Fire Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	40	0				1,420							
69	East Cresson Mine Area - 50 lift - Mass Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	50	0				763,991							
70	East Cresson Mine Area - 50 lift - Fine Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	50	0				84,888							
71	East Cresson Mine Area - 50 lift - Mass Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	4.5	1.0	50	0				672,099							
72	East Cresson Mine Area - 50 lift - Fine Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	4.5	1.0	50	0				74,678							
73	East Cresson Mine Area - 150 lift - Mass Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150	0				231,066							
74	East Cresson Mine Area - 150 lift - Fine Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150	0				25,674							
75	East Cresson Mine Area - 400 lift - Mass Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	400	0				1,582,312							
76	East Cresson Mine Area - 400 lift - Fine Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	400	0				175,812							
77	East Cresson Mine Area - Topsoil - Lift 2	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150	824	675	12.44	0					6.0	6.0	3,294	-0.1
78	East Cresson Mine Area - Topsoil - Lift 2 - Dozer Spreading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150					10,228							
79	East Cresson Mine Area - Topsoil - Lift 3	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150	282	515	10.86	0					6.0	6.0	3,698	-0.1
80	East Cresson Mine Area - Topsoil - Lift 3 - Dozer Spreading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150					8,575							
81	East Cresson Mine Area - Topsoil - Lift 4	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150	6,264	545	57.93	0					6.0	6.0	4,912	-0.1
82	East Cresson Mine Area - Topsoil - Lift 4 - Dozer Spreading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150					50,320							
83	East Cresson Mine Area - Topsoil - Lift 5	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150	7,172	655	106.97	0					6.0	6.0	6,407	-0.1
84	East Cresson Mine Area - Topsoil - Lift 5 - Dozer Spreading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150					90,226							
85	East Cresson Mine Area - Topsoil - Lift 6	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150	1,500	300	110.79	0					6.0	6.0	9,080	-0.1
86	East Cresson Mine Area - Topsoil - Lift 6 - Dozer Spreading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150					90,330							
87	East Cresson Mine Area - Topsoil - WHEX	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150	500	300	199.30	0					6.0	6.0	1,506	-8.6
88	East Cresson Mine Area - Topsoil - WHEX - Dozer Spreading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150					161,059							
89	East Cresson Mine Area - Topsoil - Ironclad	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150	100	300	14.57	0					6.0	6.0	3,128	4.6
90	East Cresson Mine Area - Topsoil - Ironclad - Dozer Spreading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150					12,043							
91	Main Cresson Mine Area - Pile Leveling - Mass Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	10.0	10.0	1.0	5	0				116,523							
92	Main Cresson Mine Area - Pile Leveling - Fine Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	10.0	10.0	1.0	5	0				12,947							
93	Main Cresson Mine Area - 50 ft lift - Mass Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	50	0				103,266							
94	Main Cresson Mine Area - 50 ft lift - Fine Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	50	0				11,474							
95	Main Cresson Mine Area - 150 ft lift - Mass Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150	0				155,109							
96	Main Cresson Mine Area - 150 ft lift - Fine Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	150	0				177,234							
97	Main Cresson Mine Area - 400 ft lift - Mass Grading	2009	Dumps , Stockpiles, Landfills			ARO+LOM+FA	0.0	1.4	2.5	1.0	400	0				272,666				</			

Notes:
1. All Rights Reserved. Copyright © 2010 by Pearson Education, Inc.

1. All Physical parameters must be input even if manual overrides for volume or area are used.
2. Input distance from plant to boundary, if greater than 100m, enter '100'.

2. Input distance from crusher to placement location if material to be crushed and/or screened.
3. If Slope from facility to barrow source is > 20°, downhill travel time curves and downhill speed tables from CAT Handbook (see Productivity Sheet).

Closure Cost Estimate Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Waste Rock Dumps - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Grading Costs	2,236,504	8,208,026	N/A	10,444,530
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	332,286	2,641,597	N/A	2,973,883
Ripping/Scarifying Cost	86,466	305,180	N/A	391,646
Subtotal Earthworks	2,655,256	11,154,803		13,810,059
Revegetation Cost	229,884	83,715	0	313,599
TOTALS	2,885,140	11,238,518	0	14,123,658

Closure Cost Estimate Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Waste Rock Dumps - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Grading Costs	2,236,504	8,208,026	N/A	10,444,530
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	332,286	2,641,597	N/A	2,973,883
Ripping/Scarifying Cost	86,466	305,180	N/A	391,646
Subtotal Earthworks	2,655,256	11,154,803		13,810,059
Revegetation Cost	229,884	83,715	0	313,599
TOTALS	2,885,140	11,238,518	0	14,123,657

Notes:

1. Input distance to crusher if material to be crushed
2. if distance from borrow <820 ft (250 m) must select loader fleet

Closure Cost Estimate
Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Waste Rock Dumps - ARO Cost Summary

	Labor \$	Equipment \$	Materials \$	Totals \$
Grading Costs	2,236,504	8,208,026	N/A	10,444,530
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsail Placement Cost	322,265	2,641,507	N/A	2,973,655
Ripping/Scarifying Cost	65,469	305,160	N/A	370,629
Subtotal Earthworks	2,655,256	11,154,803		13,810,059
Revegetation Cost	220,884	83,715	0	113,599
TOTALS	2,885,140	11,238,518	0	14,123,658

Waste Rock Dumps - User Input (Cont.)

	You must fill in ALL green cells and relevant blue cells in this section for each dump, lift or dump category										Growth Media					Revegetation							
	Grading			Cover 1			Cover 2			Growth Media					Revegetation								
Description (required)	Dozing Material Condition (select)	Material Type (select)	Grading Equipment Fleet (select)	Slot/Side-by-Side (select)	Material Type (select)	Placement Equipment Fleet (select)	Cycle Time Override (user override)	Maximum Fleet Size (user override)	Material Type (select)	Placement Equipment Fleet (select)	Cycle Time Override (user override)	Maximum Fleet Size (user override)	Material Type (select)	Placement Equipment Fleet (select)	Cycle Time Override (user override)	Maximum Fleet Size (user override)	Seed Mix Slopes (select)	Seed Mix Flat Areas (select)	Mulch Slopes (select)	Fertilizer Flat Areas (select)	Slope Scarify/Rip? (select)	Flat Area Scarify/Rip? (select)	Scarify/Ripping Fleet (select)
1 Ironclad Mine Area - Pile Leveling - Mass Grading	0.6	Granite - broken	Large	Yes																			
2 Ironclad Mine Area - Pile Leveling - Fine Grading	0.6	Granite - broken	Small	No																			
3 Ironclad Mine Area - 40 ft Lift - Mass Grading	1	Granite - broken	Large	Yes																			
4 Ironclad Mine Area - 40 ft Lift - Fine Grading	1	Granite - broken	Small	No																			
5 Ironclad Mine Area - Topsail	1.2	Topsail	Small	No																			
6 Ironclad Mine Area - Topsail - Dozer Spreading	1.2	Topsail	Small	No																			
7 SGOSA Mine Area - Pile Leveling - Mass Grading	0.6	Granite - broken	Large	Yes																			
8 SGOSA Mine Area - Pile Leveling - Fine Grading	0.6	Granite - broken	Small	No																			
9 SGOSA Mine Area - 100 ft lift - Mass Grading	1	Granite - broken	Large	Yes																			
10 SGOSA Mine Area - 100 ft lift - Fine Grading	1	Granite - broken	Small	No																			
11 SGOSA Mine Area - 150 ft lift - Mass Grading	1	Granite - broken	Large	Yes																			
12 SGOSA Mine Area - 150 ft lift - Fine Grading	1	Granite - broken	Small	No																			
13 SGOSA Mine Area - 200 ft lift - Mass Grading	1	Granite - broken	Large	Yes																			
14 SGOSA Mine Area - 200 ft lift - Fine Grading	1	Granite - broken	Small	No																			
15 SGOSA Mine Area - 250 ft lift - Mass Grading	1	Granite - broken	Large	Yes																			
16 SGOSA Mine Area - 250 ft lift - Fine Grading	1	Granite - broken	Small	No																			
17 SGOSA Mine Area - 300 ft lift - Mass Grading	1	Granite - broken	Large	Yes																			
18 SGOSA Mine Area - 300 ft lift - Fine Grading	1	Granite - broken	Small	No																			
19 North Cresson Mine Area - Topsail - Lift 1	1.2	Topsail	Small	No																			
20 North Cresson Mine Area - Topsail - Lift 1 - Dozer Spreading	1.2	Topsail	Small	No																			
21 North Cresson Mine Area - Topsail - Lift 2	1.2	Topsail	Small	No																			
22 North Cresson Mine Area - Topsail - Lift 2 - Dozer Spreading	1.2	Topsail	Small	No																			
23 North Cresson Mine Area - Topsail - Lift 3	1.2	Topsail	Small	No																			
24 North Cresson Mine Area - Topsail - Lift 3 - Dozer Spreading	1.2	Topsail	Small	No																			
25 North Cresson Mine Area - Topsail - Lift 4	1.2	Topsail	Small	No																			
26 SGOSA Mine Area - Topsail - Lift 4 - Dozer Spreading	1.2	Topsail	Small	No																			
27 SGOSA Mine Area - Topsail - Lift 5	1.2	Topsail	Small	No																			
28 SGOSA Mine Area - Topsail - Lift 5 - Dozer Spreading	1.2	Topsail	Small	No																			
29 ECOSA Mine Area - Pile Leveling - Mass Grading	0.6	Granite - broken	Large	Yes																			
30 North Cresson Mine Area - Pile Leveling - Fine Grading	0.6	Granite - broken	Small	No																			
31 North Cresson Mine Area - 200 ft lift - Mass Grading	1	Granite - broken	Large	Yes																			
32 North Cresson Mine Area - 200 ft lift - Fine Grading	1	Granite - broken	Small	No																			
33 North Cresson Mine Area - 250 ft lift - Mass Grading	1	Granite - broken	Large	Yes																			
34 North Cresson Mine Area - 250 ft lift - Fine Grading	1	Granite - broken	Small	No																			
35 North Cresson Mine Area - Topsail	1.2	Topsail	Small	No																			
36 North Cresson Mine Area - Topsail - Dozer Spreading	1.2	Topsail	Small	No																			
37 North Cresson Mine Area - Topsail - Lift 1	1.2	Topsail	Small	No																			
38 North Cresson Mine Area - Topsail - Lift 1 - Dozer Spreading	1.2	Topsail	Small	No																			
39 North Cresson Mine Area - Topsail - Lift 2	1.2	Topsail	Small	No																			
40 North Cresson Mine Area - Topsail - Lift 2 - Dozer Spreading	1.2	Topsail	Small	No																			
41 North Cresson Mine Area - Topsail - Lift 3	1.2	Topsail	Small	No																			
42 North Cresson Mine Area - Topsail - Lift 3 - Dozer Spreading	1.2	Topsail	Small	No																			
43 North Cresson Mine Area - Topsail - Lift 4	1.2	Topsail	Small	No																			
44 North Cresson Mine Area - Topsail - Lift 4 - Dozer Spreading	1.2	Topsail																					

Closure Cost Estimate Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Waste Rock Dumps - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Grading Costs	2,236,504	8,208,026	N/A	10,444,530
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	332,286	2,641,597	N/A	2,973,883
Ripping/Scarifying Cost	86,466	305,180	N/A	391,646
Subtotal Earthworks		2,655,256	11,154,803	13,810,059
Revegetation Cost	229,884	83,715	0	313,599
TOTALS	2,885,140	11,238,518	0	14,123,659

Notes:
1. Material Types are used for density correction based on material densities in Caterpillar Performance Handbook material density table

Closure Cost Estimate
Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Waste Rock Dumps - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Grading Costs	2,236,504	8,208,026	N/A	10,444,530
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	322,265	2,641,507	N/A	2,973,655
Ripping/Scarfing Cost	65,469	305,160	N/A	391,645
Subtotal Earthworks	2,655,256	11,154,803		13,810,059
Revegetation Cost	220,884	83,715	0	113,590
TOTALS	2,885,140	11,238,518	0	14,123,659

Waste Rock Dumps - Assumptions & Calculations				
Regrading Push Distance Calculation				
dozing distance: based on 2/3 final cut slope + 2/3 final fill slope (minimum = 50 ft)				
Ripping/Scarfing Calculations				
Minimum 1 hr ripping/scarfing time per dump				
Slopes: Number of passes = Final slope length / Grader width Travel distance = Number of passes x Mid-bench length Total hours = (Travel distance / Grader productivity) + (Number of passes x Grader maneuver time) Minimum 1 hr				
Flat Areas: Flat area width = Final flat area x Average long dimensions Number of passes = Flat area width / Grader width Travel distance = Number of passes x Average long dimensions Total hours = (Travel distance / Grader productivity) + (Number of passes x Grader maneuver time)				
Revegetation: Minimum 1 acre revegetation crew time per acre				

Waste Rock Dumps - Regrading Costs														
Productivity = Dozer Productivity x Grade Correction x Density Correction x Operator (0.75) x Material x Visibility x Job Efficiency (0.83) x (Slot/Side-by-Side) x (Altitude Deration)														
	Description (required)	Regrading Volume cy	Dozing Distance (see above) ft	Regrading Fleet	Uncorrected Dozer Productivity cy/hr	Grade Correction	Dozing Material	Density Correction	Side-by-Side or Slot Dozing	Total Hourly Productivity cy/hr	Total Dozer Hours hrs	Total Labor Cost \$	Total Equipment Cost \$	Total Regrading Cost \$
1	Ironclad Mine Area - Pile Leveling - Mass Grading	5,933	50	D10T2	2750	1.2	0.6	0.82	1.2	1213	5	365	1,774	2,139
2	Ironclad Mine Area - Pile Leveling - Fine Grading	659	50	D7E	1017	1.2	0.6	0.82	1.0	370	2	146	211	357
3	Ironclad Mine Area - 40 ft Lift - Mass Grading	21,753	91	D10T2	1659	1.6	1.0	0.82	1.2	1626	13	948	4,613	5,561
4	Ironclad Mine Area - 40 ft Lift - Fine Grading	2,417	91	D7E	617	1.6	1.0	0.82	1.0	499	5	365	528	893
5	Ironclad Mine Area - Topsoil - Dozer Spreading	0	1							0	0	0	0	0
6	SGOSA Mine Area - Topsoil - Dozer Spreading	21,062	50	D7E	1017	1.2	1.2	1.44	1.0	1300	16	1,163	1,698	2,855
7	SGOSA Mine Area - Pile Leveling - Mass Grading	2,098	50	D10T2	2750	1.2	0.6	0.82	1.2	1213	2	146	710	755
8	SGOSA Mine Area - Pile Leveling - Fine Grading	232	50	D7E	1017	1.2	0.6	0.82	1.0	370	1	73	106	179
9	SGOSA Mine Area - 100 ft lift - Mass Grading	89,714	147	D10T2	1107	1.6	1.0	0.82	1.2	1085	83	6,051	29,449	35,500
10	SGOSA Mine Area - 100 ft lift - Fine Grading	9,968	147	D7E	414	1.6	1.0	0.82	1.0	335	30	2,187	3,167	5,354
11	SGOSA Mine Area - 150 ft lift - Mass Grading	249,154	293	D10T2	618	1.6	1.0	0.82	1.2	606	411	29,982	145,827	175,789
12	SGOSA Mine Area - 150 ft lift - Fine Grading	27,584	293	D7E	233	1.6	1.0	0.82	1.0	188	147	10,716	15,517	26,233
13	SGOSA Mine Area - 200 ft lift - Mass Grading	156,487	367	D10T2	511	1.6	1.0	0.82	1.2	501	312	22,745	110,701	133,446
14	SGOSA Mine Area - 200 ft lift - Fine Grading	17,387	367	D7E	193	1.6	1.0	0.82	1.0	156	111	8,092	11,717	19,809
15	SGOSA Mine Area - 250 ft lift - Mass Grading	113,624	440	D10T2	439	1.6	1.0	0.82	1.2	430	264	19,246	93,670	112,916
16	SGOSA Mine Area - 250 ft lift - Fine Grading	12,625	440	D7E	166	1.6	1.0	0.82	1.0	134	94	6,853	9,923	16,776
17	SGOSA Mine Area - 300 ft lift - Mass Grading	265,933	513	D10T2	385	1.6	1.0	0.82	1.2	377	705	51,395	250,141	301,536
18	SGOSA Mine Area - 300 ft lift - Fine Grading	29,548	513	D7E	146	1.6	1.0	0.82	1.0	118	250	18,225	26,390	44,615
19	SGOSA Mine Area - Topsoil - Lift 1									0	0	0	0	0
20	SGOSA Mine Area - Topsoil - Lift 1 - Dozer Spreading	18,610	670	D7E	117	1.2	1.2	1.44	1.0	150	124	9,040	13,089	22,129
21	SGOSA Mine Area - Topsoil - Lift 2	90,254	147	Select Fleet	Select Fleet	1.6	Select Material	Select Material	1.0	Select Fleet	0	0	0	0
22	SGOSA Mine Area - Topsoil - Lift 2 - Dozer Spreading	14,415	147	D7E	414	1.6	1.2	1.44	1.0	705	20	1,458	2,111	3,569
23	SGOSA Mine Area - Topsoil - Lift 3	136,200	147	Select Fleet	Select Fleet	1.6	Select Material	Select Material	1.0	Select Fleet	0	0	0	0
24	SGOSA Mine Area - Topsoil - Lift 3 - Dozer Spreading	24,337	147	D7E	414	1.6	1.2	1.44	1.0	705	35	2,552	3,695	6,247
25	SGOSA Mine Area - Topsoil - Lift 4	347,338	147	Select Fleet	Select Fleet	1.6	Select Material	Select Material	1.0	Select Fleet	0	0	0	0
26	SGOSA Mine Area - Topsoil - Lift 4 - Dozer Spreading	46,311	147	D7E	414	1.6	1.2	1.44	1.0	705	66	4,811	6,967	11,778
27	SGOSA Mine Area - Topsoil - Lift 5	267,278	147	Select Fleet	Select Fleet	1.6	Select Material	Select Material	1.0	Select Fleet	0	0	0	0
28	SGOSA Mine Area - Topsoil - Lift 5 - Dozer Spreading	47,964	147	D7E	414	1.6	1.2	1.44	1.0	705	68	4,957	7,178	12,135
29	North Cresson Mine Area - Pile Leveling - Mass Grading	27,350	50	D10T2	2750	1.2	0.6	0.82	1.2	1213	23	1,671	8,161	9,838
30	North Cresson Mine Area - Pile Leveling - Fine Grading	3,020	50	D7E	1017	1.2	0.6	0.82	1.0	370	5	563	744	1,422
31	North Cresson Mine Area - 200 ft lift - Mass Grading	1,202,605	367	D10T2	511	1.6	1.0	0.82	1.2	501	2,400	174,660	651,544	1,026,504
32	North Cresson Mine Area - 200 ft lift - Fine Grading	133,623	367	D7E	193	1.6	1.0	0.82	1.0	156	867	62,475	90,485	132,360
33	North Cresson Mine Area - 250 ft lift - Mass Grading	382,493	513	D10T2	385	1.6	1.0	0.82	1.2	377	980	71,442	347,714	419,156
34	North Cresson Mine Area - 250 ft lift - Fine Grading	41,050	513	D7E	146	1.6	1.0	0.82	1.0	118	348	25,369	36,735	62,104
35	North Cresson Mine Area - Topsoil									0	0	0	0	0
36	North Cresson Mine Area - Topsoil - Dozer Spreading	44,722	50	D7E	1017	1.2								

Closure Cost Estimate
Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Waste Rock Dumps - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Grading Costs	2,236.504	8,208.026	N/A	10,444.530
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsail Placement Cost	322.265	2,641.507	N/A	2,973.653
Ripping/Scarifying Cost	65.465	305.160	N/A	370.626
Subtotal Earthworks	2,655.256	11,154.803		13,810.059
Revegetation Cost	220.884	83.715	0	313.590
TOTALS	2,885.140	11,238.518	0	14,123.659

43	North Cresson Mine Area - Topsail - Lift 4	320.074	367	Select Fleet	Select Fleet	1.6	Select Material	Select Material	1.0	Select Fleet	0	0	0	0
----	--	---------	-----	--------------	--------------	-----	-----------------	-----------------	-----	--------------	---	---	---	---

Closure Cost Estimate
Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Waste Rock Dumps - ARO Cost Summary

	Labor \$	Equipment \$	Materials \$	Totals \$
Grading Costs	2,236,504	8,208,026	N/A	10,444,530
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	322,265	2,641,507	N/A	2,973,655
Ripping/Scarfing Cost	65,465	305,160	N/A	391,645
Subtotal Earthworks	2,655,256	11,154,803		13,810,059
Revegetation Cost	220,884	83,715	0	113,590
TOTALS	2,885,140	11,238,518	0	14,123,659

44	North Cresson Mine Area - Topsoil - Lift 4 - Dozer Spreading	12,536	367	D7E	193	1.6	1.2	1.44	1.0	329	38	2,770	4,011	6,781
45	North Cresson Mine Area - Topsoil - Lift 5	16,004	367	Select Fleet	1.6	1.2	1.44	1.0	329	4	0	0	0	0
46	North Cresson Mine Area - Topsoil - Lift 5 - Dozer Spreading	1,436	367	D7E	193	1.6	1.2	1.44	1.0	329	4	292	422	714
47	North Cresson Mine Area - Topsoil - Globe Hill HR	0										0	0	0
48	ECOSA Mine Area - Topsoil - Globe Hill HR - Dozer	32,404	367	D7E	193	1.6	1.2	1.44	1.0	329	98	7,144	10,345	17,489
49	ECOSA Mine Area - 50 ft lift - Mass Grading	181,413	73	D10T2	1998	1.6	1.0	0.82	1.2	1958	93	6,780	32,997	39,777
50	ECOSA Mine Area - 50 ft lift - Fine Grading	131,268	73	D7E	742	1.6	1.0	0.82	1.0	600	219	15,965	23,118	39,083
51	ECOSA Mine Area - 150 ft lift - Mass Grading	1,123,165	220	D10T2	787	1.6	1.0	0.82	1.2	771	1,457	106,215	516,958	623,173
52	ECOSA Mine Area - 150 ft lift - Fine Grading	124,796	220	D7E	296	1.6	1.0	0.82	1.0	239	522	38,054	55,102	93,156
53	ECOSA Mine Area - Topsoil - Lift 1	0										0	0	0
54	ECOSA Mine Area - Topsoil - Lift 1 - Dozer Spreading	59,734	220	D7E	296	1.6	1.2	1.44	1.0	504	119	8,675	12,562	21,237
55	ECOSA Mine Area - Topsoil - Lift 2	0										0	0	0
56	ECOSA Mine Area - Topsoil - Lift 2 - Dozer Spreading	51,030	220	D7E	296	1.6	1.2	1.44	1.0	504	101	7,363	10,662	18,025
57	ECOSA Mine Area - Topsoil - Lift 3	0										0	0	0
58	ECOSA Mine Area - Topsoil - Lift 3 - Dozer Spreading	54,071	220	D7E	296	1.6	1.2	1.44	1.0	504	107	7,800	11,295	19,095
59	ECOSA Mine Area - Topsoil - Lift 4	0										0	0	0
60	ECOSA Mine Area - Topsoil - Lift 4 - Dozer Spreading	43,302	220	D7E	296	1.6	1.2	1.44	1.0	504	86	6,269	9,078	15,347
61	ECOSA Mine Area - Topsoil - Lift 5	0										0	0	0
62	ECOSA Mine Area - Topsoil - Lift 5 - Dozer Spreading	53,926	220	D7E	296	1.6	1.2	1.44	1.0	504	107	7,800	11,295	19,095
63	ECOSA Mine Area - Topsoil - Lift 6	0										0	0	0
64	ECOSA Mine Area - Topsoil - Lift 6 - Dozer Spreading	20,957	220	D7E	296	1.6	1.2	1.44	1.0	504	42	3,062	4,434	7,496
65	East Cresson Mine Area - Pile Leveling - Mass Grading	473	50	D10T2	2750	1.2	0.8	0.82	1.2	1213	1	73	355	426
66	East Cresson Mine Area - Pile Leveling - Fine Grading	53	50	D7E	1017	1.2	0.8	0.82	1.0	370	1	73	106	178
67	East Cresson Mine Area - 40 lift - Mass Grading	12,777	59	D10T2	2391	1.6	1.0	0.82	1.2	2343	5	365	1,244	2,139
68	East Cresson Mine Area - 40 lift - Fine Grading	14,129	59	D7E	2385	1.6	1.0	0.82	1.0	716	2	148	214	317
69	East Cresson Mine Area - 50 lift - Mass Grading	763,091	73	D10T2	1998	1.6	1.0	0.82	1.2	1958	390	28,431	138,376	166,807
70	East Cresson Mine Area - 50 lift - Fine Grading	84,888	73	D7E	742	1.6	1.0	0.82	1.0	600	141	10,279	14,884	25,163
71	East Cresson Mine Area - 50 lift - Mass Grading	672,099	105	D10T2	1470	1.6	1.0	0.82	1.2	1441	466	33,971	165,341	199,312
72	East Cresson Mine Area - 50 lift - Fine Grading	74,678	105	D7E	549	1.6	1.0	0.82	1.0	443	169	12,320	17,840	30,160
73	East Cresson Mine Area - 150 lift - Mass Grading	231,066	220	D10T2	787	1.6	1.0	0.82	1.2	771	300	21,870	106,443	128,313
74	East Cresson Mine Area - 150 lift - Fine Grading	25,574	220	D7E	296	1.6	1.0	0.82	1.0	239	107	7,800	11,295	19,095
75	East Cresson Mine Area - 400 lift - Mass Grading	1,582,312	586	D10T2	344	1.6	1.0	0.82	1.2	337	4,695	342,266	1,665,833	2,008,099
76	East Cresson Mine Area - 400 lift - Fine Grading	175,812	586	D7E	131	1.6	1.0	0.82	1.0	106	1,659	120,941	175,124	296,065
77	East Cresson Mine Area - Topsoil - Lift 2	0										0	0	0
78	East Cresson Mine Area - Topsoil - Lift 2 - Dozer Spreading	10,228	220	D7E	296	1.6	1.2	1.44	1.0	504	20	1,458	2,111	3,569
79	East Cresson Mine Area - Topsoil - Lift 3	0										0	0	0
80	East Cresson Mine Area - Topsoil - Lift 3 - Dozer Spreading	8,575	220	D7E	296	1.6	1.2	1.44	1.0	504	17	1,239	1,795	3,034
81	East Cresson Mine Area - Topsoil - Lift 4	0										0	0	0
82	East Cresson Mine Area - Topsoil - Lift 4 - Dozer Spreading	50,320	220	D7E	296	1.6	1.2	1.44	1.0	504	100	7,290	10,556	17,846
83	East Cresson Mine Area - Topsoil - Lift 5	0										0	0	0
84	East Cresson Mine Area - Topsoil - Lift 5 - Dozer Spreading	90,226	220	D7E	296	1.6	1.2	1.44	1.0	504	179	13,049	18,895	31,944
85	East Cresson Mine Area - Topsoil - Lift 6	0										0	0	0
86	East Cresson Mine Area - Topsoil - Lift 6 - Dozer Spreading	90,330	220	D7E	296	1.6	1.2	1.44	1.0	504	179	13,049	18,895	31,944
87	East Cresson Mine Area - Topsoil - WHEX	0										0	0	0
88	East Cresson Mine Area - Topsoil - WHEX - Dozer Spreading	161,059	220	D7E	296	1.6	1.2	1.44	1.0	504	320	23,328	33,779	57,107
89	East Cresson Mine Area - Topsoil - Ironlad	0										0	0	0
90	East Cresson Mine Area - Topsoil - Ironlad - Dozer Spreading	12,043	220	D7E	296	1.6	1.2	1.44	1.0	504	24	1,750	2,533	4,285
91	Main Cresson Mine Area - Pile Leveling - Mass Grading	116,523	50	D10T2	2750	1.2	0.8	0.82	1.2	1213	96	6,998	34,062	41,060
92	Main Cresson Mine Area - Pile Leveling - Fine Grading	12,947	50	D7E	1017	1.2	0.8	0.82	1.0	370	35	2,552	3,695	6

Closure Cost Estimate Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Waste Rock Dumps - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Grading Costs	2,236,504	8,208,026	N/A	10,444,530
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	332,286	2,641,597	N/A	2,973,883
Ripping/Scarifying Cost	86,466	305,180	N/A	391,646
Subtotal Earthworks	2,655,256	11,154,803		13,810,059
Revegetation Cost	229,884	83,715	0	313,599
TOTALS	2,885,140	11,238,518	0	14,123,658

Closure Cost Estimate Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Notes:
1. If crushed or screened, Cover Volume = volume delivered to crusher - amount loss to crushing/screening)

Closure Cost Estimate
Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Waste Rock Dumps - ARO Cost Summary

	Labor \$	Equipment \$	Materials \$	Totals \$
Grading Costs	2,236,504	8,208,026	N/A	10,444,530
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsail Placement Cost	322,265	2,641,507	N/A	2,973,655
Ripping/Scarfing Cost	65,465	305,160	N/A	391,625
Subtotal Earthworks	2,655,256	11,154,803		13,810,059
Revegetation Cost	220,884	83,715	0	113,599
TOTALS	2,885,140	11,238,518	0	14,123,658

Waste Rock Dumps - Cover 2 Costs

Description (required)	Material Volumes		Haul to Crusher				Haul to Placement				Haul to Crusher		Crush		Compact		Haul to Placement		Total				
	Material Volume to Crusher cy	Final Material Volume cy	Crusher Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity LCM/hr	Fleet Hours hrs	Placement Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity LCM/hr	Fleet Hours hrs	Labor Cost \$	Equipment Cost \$	Total Cost \$	Total Crush/Screen Cost \$	Labor Cost \$	Equipment Cost \$	Total Cost \$	Labor Cost \$	Equipment Cost \$	Total Cost \$	Total Cover Cost \$
1 Ironclad Mine Area - Pile Leveling - Mass Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
2 Ironclad Mine Area - Pile Leveling - Fine Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
3 Ironclad Mine Area - 40 ft Lift - Mass Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
4 Ironclad Mine Area - 40 ft Lift - Fine Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
5 Ironclad Mine Area - Topsail	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
6 Ironclad Mine Area - Topsail - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
7 SGOSA Mine Area - Pile Leveling - Mass Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
8 SGOSA Mine Area - Pile Leveling - Fine Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
9 SGOSA Mine Area - 100 ft Lift - Mass Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
10 SGOSA Mine Area - 100 ft Lift - Fine Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
11 SGOSA Mine Area - 150 ft Lift - Mass Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
12 SGOSA Mine Area - 150 ft Lift - Fine Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
13 SGOSA Mine Area - 200 ft Lift - Mass Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
14 SGOSA Mine Area - 200 ft Lift - Fine Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
15 SGOSA Mine Area - 250 ft Lift - Mass Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
16 SGOSA Mine Area - 250 ft Lift - Fine Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
17 SGOSA Mine Area - 300 ft Lift - Mass Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
18 SGOSA Mine Area - 300 ft Lift - Fine Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
19 SGOSA Mine Area - Topsail - Lift 1	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
20 SGOSA Mine Area - Topsail - Lift 1 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
21 SGOSA Mine Area - Topsail - Lift 2	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
22 SGOSA Mine Area - Topsail - Lift 2 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
23 SGOSA Mine Area - Topsail - Lift 3	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
24 SGOSA Mine Area - Topsail - Lift 3 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
25 SGOSA Mine Area - Topsail - Lift 4	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
26 SGOSA Mine Area - Topsail - Lift 4 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
27 SGOSA Mine Area - Topsail - Lift 5	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
28 SGOSA Mine Area - Topsail - Lift 5 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
29 North Cresson Mine Area - Pile Leveling - Mass Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
30 North Cresson Mine Area - Pile Leveling - Fine Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
31 North Cresson Mine Area - 200 ft Lift - Mass Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
32 North Cresson Mine Area - 200 ft Lift - Fine Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
33 North Cresson Mine Area - 250 ft Lift - Mass Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
34 North Cresson Mine Area - 250 ft Lift - Fine Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
35 North Cresson Mine Area - Topsail	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
36 North Cresson Mine Area - Topsail - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
37 North Cresson Mine Area - Topsail - Lift 1	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
38 North Cresson Mine Area - Topsail - Lift 1 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0
39 North Cresson Mine Area - Topsail - Lift 2	0	0					0					0	0										

Closure Cost Estimate Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Waste Rock Dumps - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Grading Costs	2,236,504	8,208,026	N/A	10,444,530
	0	0	N/A	0
	0	0	N/A	0
	332,286	2,641,597	N/A	2,973,883
	86,466	305,180	N/A	391,646
	Subtotal Earthworks	2,655,256	11,154,803	13,810,059
Revegetation Cost	229,884	83,715	0	313,599
TOTALS	2,885,140	11,238,518	0	14,123,658
65 East Cresson Mine Area - Pile Leveling - Mass Grading	0	0	0	0
66 East Cresson Mine Area - Pile Leveling - Fine Grading	0	0	0	0
67 East Cresson Mine Area - 40 lift - Mass Grading	0	0	0	0
68 East Cresson Mine Area - 40 lift - Fine Grading	0	0	0	0
69 East Cresson Mine Area - 50 lift - Mass Grading	0	0	0	0
70 East Cresson Mine Area - 50 lift - Fine Grading	0	0	0	0
71 East Cresson Mine Area - 50 lift - Mass Grading	0	0	0	0
72 East Cresson Mine Area - 50 lift - Fine Grading	0	0	0	0
73 East Cresson Mine Area - 150 lift - Mass Grading	0	0	0	0
74 East Cresson Mine Area - 150 lift - Fine Grading	0	0	0	0
75 East Cresson Mine Area - 400 lift - Mass Grading	0	0	0	0
76 East Cresson Mine Area - 400 lift - Fine Grading	0	0	0	0
77 East Cresson Mine Area - Topsoil - Lift 2	0	0	0	0
78 East Cresson Mine Area - Topsoil - Lift 2 - Dozer Spreading	0	0	0	0
79 East Cresson Mine Area - Topsoil - Lift 3	0	0	0	0
80 East Cresson Mine Area - Topsoil - Lift 3 - Dozer Spreading	0	0	0	0
81 East Cresson Mine Area - Topsoil - Lift 4	0	0	0	0
82 East Cresson Mine Area - Topsoil - Lift 4 - Dozer Spreading	0	0	0	0
83 East Cresson Mine Area - Topsoil - Lift 5	0	0	0	0
84 East Cresson Mine Area - Topsoil - Lift 5 - Dozer Spreading	0	0	0	0
85 East Cresson Mine Area - Topsoil - Lift 6	0	0	0	0
86 East Cresson Mine Area - Topsoil - Lift 6 - Dozer Spreading	0	0	0	0
87 East Cresson Mine Area - Topsoil - WHEX	0	0	0	0
88 East Cresson Mine Area - Topsoil - WHEX - Dozer Spreading	0	0	0	0
89 East Cresson Mine Area - Topsoil - Ironclad	0	0	0	0
90 East Cresson Mine Area - Topsoil - Ironclad - Dozer Spreading	0	0	0	0
91 Main Cresson Mine Area - Pile Leveling - Mass Grading	0	0	0	0
92 Main Cresson Mine Area - Pile Leveling - Fine Grading	0	0	0	0
93 Main Cresson Mine Area - 50 ft lift - Mass Grading	0	0	0	0
94 Main Cresson Mine Area - 50 ft lift - Fine Grading	0	0	0	0
95 Main Cresson Mine Area - 150 ft lift - Mass Grading	0	0	0	0
96 Main Cresson Mine Area - 150 ft lift - Fine Grading	0	0	0	0
97 Main Cresson Mine Area - 400 ft lift - Mass Grading	0	0	0	0
98 Main Cresson Mine Area - 400 ft lift - Fine Grading	0	0	0	0
99 Main Cresson Mine Area - 450 ft lift - Mass Grading	0	0	0	0
100 Main Cresson Mine Area - 450 ft lift - Fine Grading	0	0	0	0
101 Main Cresson Mine Area - 650 ft lift - Mass Grading	0	0	0	0
102 Main Cresson Mine Area - 650 ft lift - Fine Grading	0	0	0	0
103 Main Cresson Mine Area - Topsoil - 10185	0	0	0	0
104 Main Cresson Mine Area - Topsoil - 10185 - Dozer Spreading	0	0	0	0
105 Main Cresson Mine Area - Topsoil - Ruby Road	0	0	0	0
106 Main Cresson Mine Area - Topsoil - Ruby Road - Dozer Spreading	0	0	0	0
107 Main Cresson Mine Area - Topsoil - AJAX	0	0	0	0
108 Main Cresson Mine Area - Topsoil - AJAX - Dozer Spreading	0	0	0	0
109 Main Cresson Mine Area - Topsoil - Pit Bottom	0	0	0	0
110 Main Cresson Mine Area - Topsoil - Pit Bottom - Dozer Spreading	0	0	0	0
111 Main Cresson Mine Area - Topsoil - South Cresson HR	0	0	0	0
112 Main Cresson Mine Area - Topsoil - South Cresson HR - D	0	0	0	0
113 Main Cresson Mine Area - Topsoil - Cresson HR	0	0	0	0
114 Main Cresson Mine Area - Topsoil - Cresson HR - Dozer Spreading	0	0	0	0
115 Chicago Mine Area	0	0	0	0
116 Chicago Mine Area topsoil - Dozer Spreading	0	0	0	0
117 East Cresson Mine Area - Regrade (EMP-18)	0	0	0	0
118 East Cresson Mine Area - Topsoil - WHEX Clay Borrow	0	0	0	0
119 East Cresson Mine Area - Topsoil - WHEX Clay Borrow - D	0	0	0	0

Notes:
1. If crushed or screened, Cover Volume = volume delivered to crusher - amount loss to crushing/screening)

Closure Cost Estimate
Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Waste Rock Dumps - ARO Cost Summary

	Labor \$	Equipment \$	Materials \$	Totals \$
Grading Costs	2,236,504	8,208,026	N/A	10,444,530
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	322,265	2,641,507	N/A	2,973,653
Ripping/Scarfing Cost	65,469	305,160	N/A	391,626
Subtotal Earthworks	2,655,256	11,154,803		13,810,059
Revegetation Cost	220,884	83,715	0	113,590
TOTALS	2,885,140	11,238,518	0	14,123,659

Waste Rock Dumps - Growth Media Costs

	Description (required)	Final Material Volume cy	Growth Media Placement							
			Placement Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity BCY/hr	Fleet Hours hrs	Labor Cost \$	Equipment Cost \$	Total Cost \$
1	Ironclad Mine Area - Pile Leveling - Mass Grading						0	0	0	0
2	Ironclad Mine Area - Pile Leveling - Fine Grading						0	0	0	0
3	Ironclad Mine Area - 40 ft Lift - Mass Grading						0	0	0	0
4	Ironclad Mine Area - 40 ft Lift - Fine Grading						0	0	0	0
5	Ironclad Mine Area - Topsoil	21,062	777G/992K/D10T2	6.82	2	973	22	5,155	39,350	44,505
6	Ironclad Mine Area - Topsoil - Dozer Spreading						0	0	0	0
7	SGOSA Mine Area - Pile Leveling - Mass Grading						0	0	0	0
8	SGOSA Mine Area - Pile Leveling - Fine Grading						0	0	0	0
9	SGOSA Mine Area - 100 ft lift - Mass Grading						0	0	0	0
10	SGOSA Mine Area - 100 ft lift - Fine Grading						0	0	0	0
11	SGOSA Mine Area - 150 ft lift - Mass Grading						0	0	0	0
12	SGOSA Mine Area - 150 ft lift - Fine Grading						0	0	0	0
13	SGOSA Mine Area - 200 ft lift - Mass Grading						0	0	0	0
14	SGOSA Mine Area - 200 ft lift - Fine Grading						0	0	0	0
15	SGOSA Mine Area - 250 ft lift - Mass Grading						0	0	0	0
16	SGOSA Mine Area - 250 ft lift - Fine Grading						0	0	0	0
17	SGOSA Mine Area - 300 ft lift - Mass Grading						0	0	0	0
18	SGOSA Mine Area - 300 ft lift - Fine Grading						0	0	0	0
19	SGOSA Mine Area - Topsoil - Lift 1	18,610	777G/992K/D10T2	12.39	4	1,072	17	5,469	45,386	50,855
20	SGOSA Mine Area - Topsoil - Lift 1 - Dozer Spreading						0	0	0	0
21	SGOSA Mine Area - Topsoil - Lift 2	9,648	777G/992K/D10T2	8.53	3	1,165	9	2,502	20,063	22,565
22	SGOSA Mine Area - Topsoil - Lift 2 - Dozer Spreading						0	0	0	0
23	SGOSA Mine Area - Topsoil - Lift 3	16,569	777G/992K/D10T2	8.17	3	1,218	14	3,892	31,209	35,101
24	SGOSA Mine Area - Topsoil - Lift 3 - Dozer Spreading						0	0	0	0
25	SGOSA Mine Area - Topsoil - Lift 4	46,133	777G/992K/D10T2	6.58	2	1,008	46	10,778	82,277	93,055
26	SGOSA Mine Area - Topsoil - Lift 4 - Dozer Spreading						0	0	0	0
27	SGOSA Mine Area - Topsoil - Lift 5	47,964	777G/992K/D10T2	5.35	2	1,240	39	9,138	69,757	78,895
28	SGOSA Mine Area - Topsoil - Lift 5 - Dozer Spreading						0	0	0	0
29	North Cresson Mine Area - Pile Leveling - Mass Grading						0	0	0	0
30	North Cresson Mine Area - Pile Leveling - Fine Grading						0	0	0	0
31	North Cresson Mine Area - 200 ft lift - Mass Grading						0	0	0	0
32	North Cresson Mine Area - 200 ft lift - Fine Grading						0	0	0	0
33	North Cresson Mine Area - 250 ft lift - Mass Grading						0	0	0	0
34	North Cresson Mine Area - 250 ft lift - Fine Grading						0	0	0	0
35	North Cresson Mine Area - Topsoil	44,722	777G/992K/D10T2	9.75	3	1,021	44	12,232	98,685	110,317
36	North Cresson Mine Area - Topsoil - Dozer Spreading						0	0	0	0
37	North Cresson Mine Area - Topsoil - Lift 1	3,759	777G/992K/D10T2	12.11	4	1,096	3	965	8,009	8,974
38	North Cresson Mine Area - Topsoil - Lift 1 - Dozer Spreading						0	0	0	0
39	North Cresson Mine Area - Topsoil - Lift 2	13,915	777G/992K/D10T2	12.11	4	1,096	13	4,182	34,707	38,889
40	North Cresson Mine Area - Topsoil - Lift 2 - Dozer Spreading						0	0	0	0
41	North Cresson Mine Area - Topsoil - Lift 3	27,467	777G/992K/D10T2	8.17	3	1,218	23	6,331	51,231	57,666
42	North Cresson Mine Area - Topsoil - Lift 3 - Dozer Spreading						0	0	0	0
43	North Cresson Mine Area - Topsoil - Lift 4	12,536	777G/992K/D10T2	6.58	2	1,008	12	2,812	21,464	24,276
44	North Cresson Mine Area - Topsoil - Lift 4 - Dozer Spreading						0	0	0	0
45	North Cresson Mine Area - Topsoil - Lift 5	1,436	777G/992K/D10T2	5.35	2	1,240	2	469	3,577	4,046
46	North Cresson Mine Area - Topsoil - Lift 5 - Dozer Spreading						0	0	0	0
47	North Cresson Mine Area - Topsoil - Globe Hill HR	32,404	777G/992K/D10T2	10.57	3	941	34	9,452	75,793	85,245
48	North Cresson Mine Area - Topsoil - Globe Hill HR - Dozer						0	0	0	0
49	ECOSA Mine Area - 50 ft lift - Mass Grading						0	0	0	0
50	ECOSA Mine Area - 50 ft lift - Fine Grading						0	0	0	0
51	ECOSA Mine Area - 150 ft lift - Mass Grading						0	0	0	0
52	ECOSA Mine Area - 150 ft lift - Fine Grading						0	0	0	0
53	ECOSA Mine Area - Topsoil - Lift 1	59,734	777G/992K/D10T2	6.55	2	1,013	59	13,824	105,529	119,353
54	ECOSA Mine Area - Topsoil - Lift 1 - Dozer Spreading						0	0	0	0
55	ECOSA Mine Area - Topsoil - Lift 2	51,030	777G/992K/D10T2	8.25	3	1,205	42	11,676	93,626	105,302
56	ECOSA Mine Area - Topsoil - Lift 2 - Dozer Spreading						0	0	0	0
57	ECOSA Mine Area - Topsoil - Lift 3	54,071	777G/992K/D10T2	10.19	3	976	55	15,291	122,606	137,897
58	ECOSA Mine Area - Topsoil - Lift 3 - Dozer Spreading						0	0	0	0
59	ECOSA Mine Area - Topsoil - Lift 4	43,302	777G/992K/D10T2	12.06	4	1,099	40	12,869	106,791	119,660
60	ECOSA Mine Area - Topsoil - Lift 4 - Dozer Spreading						0	0	0	0
61	ECOSA Mine Area - Topsoil - Lift 5	53,926	777G/992K/D10T2	15.65	5	1,058	51	18,637	158,627	177,264
62	ECOSA Mine Area - Topsoil - Lift 5 - Dozer Spreading						0	0	0	0
63	ECOSA Mine Area - Topsoil - Lift 6	20,957	777G/992K/D10T2	18.51	6	1,076	19	7,774	67,467	75,241
64	ECOSA Mine Area - Topsoil - Lift 6 - Dozer Spreading						0	0	0	0

Closure Cost Estimate
Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Waste Rock Dumps - ARO Cost Summary

	Labor \$	Equipment \$	Materials \$	Totals \$
Grading Costs	2,236,504	8,208,026	N/A	10,444,530
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsail Placement Cost	322,265	2,641,597	N/A	2,973,852
Ripping/Scarfing Cost	65,469	305,160	N/A	391,629
Subtotal Earthworks	2,655,256	11,154,803		13,810,059
Revegetation Cost	220,884	83,715	0	113,599
TOTALS	2,885,140	11,238,518	0	14,123,658

65	East Cresson Mine Area - Pile Leveling - Mass Grading				0	0	0	0
66	East Cresson Mine Area - Pile Leveling - Fine Grading				0	0	0	0
67	East Cresson Mine Area - 40 ft lift - Mass Grading				0	0	0	0
68	East Cresson Mine Area - 40 ft lift - Fine Grading				0	0	0	0
69	East Cresson Mine Area - 40 ft lift - Mass Grading				0	0	0	0
70	East Cresson Mine Area - 50 ft lift - Fine Grading				0	0	0	0
71	East Cresson Mine Area - 50 ft lift - Mass Grading				0	0	0	0
72	East Cresson Mine Area - 50 ft lift - Fine Grading				0	0	0	0
73	East Cresson Mine Area - 150 ft lift - Mass Grading				0	0	0	0
74	East Cresson Mine Area - 150 ft lift - Fine Grading				0	0	0	0
75	East Cresson Mine Area - 400 ft lift - Mass Grading				0	0	0	0
76	East Cresson Mine Area - 400 ft lift - Fine Grading				0	0	0	0
77	East Cresson Mine Area - Topsail - Lift 2	10,228	777G/992K/D10T2	6.61	2	1,004	10	2,343
78	East Cresson Mine Area - Topsail - Lift 2 - Dozer Spreading				0	0	0	0
79	East Cresson Mine Area - Topsail - Lift 3	8,575	777G/992K/D10T2	6.87	2	966	9	2,109
80	East Cresson Mine Area - Topsail - Lift 3 - Dozer Spreading				0	0	0	0
81	East Cresson Mine Area - Topsail - Lift 4	50,320	777G/992K/D10T2	7.65	2	867	58	13,589
82	East Cresson Mine Area - Topsail - Lift 4 - Dozer Spreading				0	0	0	0
83	East Cresson Mine Area - Topsail - Lift 5	90,226	777G/992K/D10T2	8.63	3	1,153	78	21,685
84	East Cresson Mine Area - Topsail - Lift 5 - Dozer Spreading				0	0	0	0
85	East Cresson Mine Area - Topsail - Lift 6	90,330	777G/992K/D10T2	10.37	3	959	94	26,133
86	East Cresson Mine Area - Topsail - Lift 6 - Dozer Spreading				0	0	0	0
87	East Cresson Mine Area - Topsail - WHEX	161,059	777G/992K/D10T2	6.8	2	976	165	38,601
88	East Cresson Mine Area - Topsail - WHEX - Dozer Spreading				0	0	0	0
89	East Cresson Mine Area - Topsail - Ironclad - Dozer Spreading	12,043	777G/992K/D10T2	6.91	2	959	13	3,046
90	East Cresson Mine Area - Topsail - Ironclad - Dozer Spreading				0	0	0	0
91	Main Cresson Mine Area - Pile Leveling - Mass Grading				0	0	0	0
92	Main Cresson Mine Area - Pile Leveling - Fine Grading				0	0	0	0
93	Main Cresson Mine Area - 50 ft lift - Mass Grading				0	0	0	0
94	Main Cresson Mine Area - 50 ft lift - Fine Grading				0	0	0	0
95	Main Cresson Mine Area - 150 ft lift - Mass Grading				0	0	0	0
96	Main Cresson Mine Area - 150 ft lift - Fine Grading				0	0	0	0
97	Main Cresson Mine Area - 400 ft lift - Mass Grading				0	0	0	0
98	Main Cresson Mine Area - 400 ft lift - Fine Grading				0	0	0	0
99	Main Cresson Mine Area - 450 ft lift - Mass Grading				0	0	0	0
100	Main Cresson Mine Area - 450 ft lift - Fine Grading				0	0	0	0
101	Main Cresson Mine Area - 650 ft lift - Mass Grading				0	0	0	0
102	Main Cresson Mine Area - 650 ft lift - Fine Grading				0	0	0	0
103	Main Cresson Mine Area - Topsail - 10185	67,115	777G/992K/D10T2	6.15	2	1,079	62	14,527
104	Main Cresson Mine Area - Topsail - 10185 - Dozer Spreading				0	0	0	0
105	Main Cresson Mine Area - Topsail - Ruby Road	59,128	777G/992K/D10T2	7.73	2	858	69	16,167
106	Main Cresson Mine Area - Topsail - Ruby Road - Dozer Spreading				0	0	0	0
107	Main Cresson Mine Area - Topsail - AJAX	26,870	777G/992K/D10T2	6.44	2	1,029	26	6,092
108	Main Cresson Mine Area - Topsail - AJAX - Dozer Spreading				0	0	0	0
109	Main Cresson Mine Area - Topsail - Pit Bottom	55,725	777G/992K/D10T2	14.43	5	1,150	48	17,541
110	Main Cresson Mine Area - Topsail - Pit Bottom - Dozer Spreading				0	0	0	0
111	Main Cresson Mine Area - Topsail - South Cresson HR	24,265	777G/992K/D10T2	9.1	3	1,093	22	6,116
112	Main Cresson Mine Area - Topsail - South Cresson HR - Dozer Spreading				0	0	0	0
113	Main Cresson Mine Area - Topsail - Cresson HR	24,265	777G/992K/D10T2	13.05	4	1,016	24	7,721
114	Main Cresson Mine Area - Topsail - Cresson HR - Dozer Spreading				0	0	0	0
115	Chicago Mine Area - Dozer Spreading	3,227	777G/992K/D10T2	5.04	2	1,316	2	469
116	Chicago Mine Area topsail - Dozer Spreading				0	0	0	0
117	East Cresson Mine Area - Grade (EMP-18)				0	0	0	0
118	East Cresson Mine Area - Topsail - WHEX Clay Borrow	10,382	777G/992K/D10T2	7.07	2	938	11	2,577
119	East Cresson Mine Area - Topsail - WHEX Clay Borrow - D				0	0	0	0
		1,273,003			1,235	332,286	2,641,597	2,973,883

Closure Cost Estimate
Waste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Waste Rock Dumps - ARO Cost Summary

	Labor \$	Equipment \$	Materials \$	Totals \$
Grading Costs	2,236,504	8,208,026	N/A	10,444,530
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	322,265	2,641,507	N/A	2,973,655
Ripping/Scarfing Cost	65,465	305,160	N/A	370,625
Subtotal Earthworks	2,655,256	11,154,803		13,810,059
Revegetation Cost	220,884	83,715	0	113,590
TOTALS	2,885,140	11,238,518	0	14,123,659

Waste Rock Dumps - Scarify/Revegetation Costs

	Description (required)	Slope Area acres	Flat Area acres	Total Surface Area acres	Final Slope Length ft	Average Long Dimension (ripping distance) ft	Ripping/ Scarifying Fleet	Slope Scarifying/ Ripping Hours hrs	Flat Area Scarifying/ Ripping Hours hrs	Scarifying Costs		Revegetation Costs				
										Scarifying/ Ripping Labor Costs \$	Scarifying/ Ripping Equipment Cost \$	Total Scarifying/ Ripping Costs \$	Revegetation Labor Cost \$	Revegetation Equipment Cost \$	Revegetation Material Cost \$	Total Vegetation Cost \$
1 Ironclad Mine Area - Pile Leveling - Mass Grading	0.10	0.00	0.10	50			D9T	0	20	1,458	5,146	6,604	3,803	1,385	31,224	36,412
2 Ironclad Mine Area - Pile Leveling - Fine Grading	0.10	0.00	0.10	50			D9T	0	0	0	0	0	0	0	0	
3 Ironclad Mine Area - 40 ft Lift - Mass Grading	0.10	0.00	0.10	208			D9T	0	0	0	0	0	0	0	0	
4 Ironclad Mine Area - 40 ft Lift - Fine Grading	0.10	0.00	0.10	208			D9T	0	0	0	0	0	0	0	0	
5 Ironclad Mine Area - Topsoil	0.11	26.00	26.11	50	300	D9T	0	20	1,458	5,146	6,604	3,803	1,385	31,224	36,412	
6 Ironclad Mine Area - Topsoil - Dozer Spreading	0.11	0.00	0.11	50			D9T	0	0	0	0	0	0	0	0	
7 SGOSA Mine Area - Pile Leveling - Mass Grading	0.10	0.00	0.10	50			D9T	0	0	0	0	0	0	0	0	
8 SGOSA Mine Area - Pile Leveling - Fine Grading	0.10	0.00	0.10	50			D9T	0	0	0	0	0	0	0	0	
9 SGOSA Mine Area - 40 ft Lift - Mass Grading	0.10	0.00	0.10	21			D9T	0	0	0	0	0	0	0	0	
10 SGOSA Mine Area - 100 ft lift - Mass Grading	0.10	0.00	0.10	271			D9T	0	0	0	0	0	0	0	0	
11 SGOSA Mine Area - 150 ft lift - Mass Grading	0.10	0.00	0.10	542			D9T	0	0	0	0	0	0	0	0	
12 SGOSA Mine Area - 150 ft lift - Fine Grading	0.10	0.00	0.10	542			D9T	0	0	0	0	0	0	0	0	
13 SGOSA Mine Area - 200 ft lift - Mass Grading	0.10	0.00	0.10	677			D9T	0	0	0	0	0	0	0	0	
14 SGOSA Mine Area - 200 ft lift - Fine Grading	0.10	0.00	0.10	677			D9T	0	0	0	0	0	0	0	0	
15 SGOSA Mine Area - 250 ft lift - Mass Grading	0.10	0.00	0.10	812			D9T	0	0	0	0	0	0	0	0	
16 SGOSA Mine Area - 250 ft lift - Fine Grading	0.10	0.00	0.10	812			D9T	0	0	0	0	0	0	0	0	
17 SGOSA Mine Area - 300 ft lift - Mass Grading	0.10	0.00	0.10	948			D9T	0	0	0	0	0	0	0	0	
18 SGOSA Mine Area - 300 ft lift - Fine Grading	0.10	0.00	0.10	948			D9T	0	0	0	0	0	0	0	0	
19 SGOSA Mine Area - Topsoil - Lift 1	23.07	0.00	23.07	1,005	245	D9T	17	0	1,239	4,374	5,613	3,360	1,224	27,588	32,172	
20 SGOSA Mine Area - Topsoil - Lift 1 - Dozer Spreading	0.10	0.00	0.10	1,005			D9T	0	0	0	0	0	0	0	0	
21 SGOSA Mine Area - Topsoil - Lift 2	10.96	1.00	11.96	271	245	D9T	8	1	656	2,316	2,972	1,742	634	14,302	16,678	
22 SGOSA Mine Area - Topsoil - Lift 2 - Dozer Spreading	0.10	0.00	0.10	271			D9T	0	0	0	0	0	0	0	0	
23 SGOSA Mine Area - Topsoil - Lift 3	16.54	4.00	20.54	271	245	D9T	12	3	1,094	3,860	4,954	2,992	1,089	24,562	28,643	
24 SGOSA Mine Area - Topsoil - Lift 3 - Dozer Spreading	0.10	0.00	0.10	271			D9T	0	0	0	0	0	0	0	0	
25 SGOSA Mine Area - Topsoil - Lift 4	42.19	15.00	57.19	271	245	D9T	31	12	3,135	11,065	14,200	8,330	3,034	68,390	79,754	
26 SGOSA Mine Area - Topsoil - Lift 4 - Dozer Spreading	0.10	0.00	0.10	271			D9T	0	0	0	0	0	0	0	0	
27 SGOSA Mine Area - Topsoil - Lift 5	32.46	27.00	59.46	271	245	D9T	24	21	3,281	11,579	14,860	8,661	3,154	71,103	82,918	
28 SGOSA Mine Area - Topsoil - Lift 5 - Dozer Spreading	0.10	0.00	0.10	271			D9T	0	0	0	0	0	0	0	0	
29 North Cresson Mine Area - Pile Leveling - Mass Grading	0.10	0.00	0.10	50			D9T	0	0	0	0	0	0	0	0	
30 North Cresson Mine Area - Pile Leveling - Fine Grading	0.10	0.00	0.10	50			D9T	0	0	0	0	0	0	0	0	
31 North Cresson Mine Area - 200 ft lift - Mass Grading	0.10	0.00	0.10	677			D9T	0	0	0	0	0	0	0	0	
32 North Cresson Mine Area - 200 ft lift - Fine Grading	0.10	0.00	0.10	677			D9T	0	0	0	0	0	0	0	0	
33 North Cresson Mine Area - 250 ft lift - Mass Grading	0.10	0.00	0.10	948			D9T	0	0	0	0	0	0	0	0	
34 North Cresson Mine Area - 250 ft lift - Fine Grading	0.10	0.00	0.10	948			D9T	0	0	0	0	0	0	0	0	
35 North Cresson Mine Area - Topsoil - Lift 1	3.44	52.00	55.44	50	300	D9T	2	40	3,062	10,807	13,869	8,075	2,940	66,297	77,312	
36 North Cresson Mine Area - Topsoil - Lift 1 - Dozer Spreading	0.10	0.00	0.10	50			D9T	0	0	0	0	0	0	0	0	
37 North Cresson Mine Area - Topsoil - Lift 1	4.66	0.00	4.66	677	245	D9T	4	0	292	1,029	1,321	679	247	5,573	6,499	
38 North Cresson Mine Area - Topsoil - Lift 1 - Dozer Spreading	0.10	0.00	0.10	677			D9T	0	0	0	0	0	0	0	0	
39 North Cresson Mine Area - Topsoil - Lift 2	17.25	0.00	17.25	677	245	D9T	13	0	948	3,345	4,293	2,513	915	20,628	24,056	
40 North Cresson Mine Area - Topsoil - Lift 2 - Dozer Spreading	0.10	0.00	0.10	677			D9T	0	0	0	0	0	0	0	0	
41 North Cresson Mine Area - Topsoil - Lift 3	34.05	0.00	34.05	677	245	D9T	25	0	1,823	6,433	8,256	4,960	1,806	40,718	47,484	
42 North Cresson Mine Area - Topsoil - Lift 3 - Dozer Spreading	0.10	0.00	0.10	677			D9T	0	0	0	0	0	0	0	0	
43 North Cresson Mine Area - Topsoil - Lift 4	15.54	0.00	15.54	677	245	D9T	11	0	802	2,831	3,633	2,263	824</td			

sure Cost Estimate aste Rock Dumps

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Waste Rock Dumps - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Grading Costs	2,236,504	8,208,026	N/A	10,444,530
Cover 1 Placement Cost	0	0	N/A	
Cover 2 Placement Cost	0	0	N/A	
Topsoil Placement Cost	332,286	2,641,597	N/A	2,973,883
Ripping/Scarifying Cost	86,466	305,180	N/A	391,646
Subtotal Earthworks	2,655,256	11,154,803		13,810,059
Revegetation Cost	229,884	83,715	0	313,599
TOTALS	2,885,140	11,238,518	0	14,123,658

67	East Cresson Mine Area - 40 lift - Mass Grading	0.10	0.00	0.10	108			0	0	0	0	0	0	0	0	0	0	0	0
68	East Cresson Mine Area - 40 lift - Fine Grading	0.10	0.00	0.10	108			0	0	0	0	0	0	0	0	0	0	0	0
69	East Cresson Mine Area - 50 lift - Mass Grading	0.10	0.00	0.10	135			0	0	0	0	0	0	0	0	0	0	0	0
70	East Cresson Mine Area - 50 lift - Fine Grading	0.10	0.00	0.10	135			0	0	0	0	0	0	0	0	0	0	0	0
71	East Cresson Mine Area - 50 lift - Mass Grading	0.10	0.00	0.10	234			0	0	0	0	0	0	0	0	0	0	0	0
72	East Cresson Mine Area - 50 lift - Fine Grading	0.10	0.00	0.10	234			0	0	0	0	0	0	0	0	0	0	0	0
73	East Cresson Mine Area - 150 lift - Mass Grading	0.10	0.00	0.10	406			0	0	0	0	0	0	0	0	0	0	0	0
74	East Cresson Mine Area - 150 lift - Fine Grading	0.10	0.00	0.10	406			0	0	0	0	0	0	0	0	0	0	0	0
75	East Cresson Mine Area - 400 lift - Mass Grading	0.10	0.00	0.10	1,083			0	0	0	0	0	0	0	0	0	0	0	0
76	East Cresson Mine Area - 400 lift - Fine Grading	0.10	0.00	0.10	1,083			0	0	0	0	0	0	0	0	0	0	0	0
77	East Cresson Mine Area - Topsoil - Lift 2	7.68	5.00	12.68	406	675	D9T	6	4	729	2,573	3,302	1,847	672	15,163	17,682			
78	East Cresson Mine Area - Topsoil - Lift 2 - Dozer Spreading	0.10	0.00	0.10	406			0	0	0	0	0	0	0	0	0	0	0	0
79	East Cresson Mine Area - Topsoil - Lift 3	2.63	8.00	10.63	406	515	D9T	2	6	583	2,059	2,642	1,548	564	12,711	14,823			
80	East Cresson Mine Area - Topsoil - Lift 3 - Dozer Spreading	0.10	0.00	0.10	406			0	0	0	0	0	0	0	0	0	0	0	0
81	East Cresson Mine Area - Topsoil - Lift 4	58.38	4.00	62.38	406	545	D9T	42	3	3,281	11,579	14,860	9,086	3,309	74,596	86,991			
82	East Cresson Mine Area - Topsoil - Lift 4 - Dozer Spreading	0.10	0.00	0.10	406			0	0	0	0	0	0	0	0	0	0	0	0
83	East Cresson Mine Area - Topsoil - Lift 5	66.85	45.00	111.85	406	655	D9T	48	33	5,905	20,843	26,748	16,292	5,933	133,755	155,980			
84	East Cresson Mine Area - Topsoil - Lift 5 - Dozer Spreading	0.10	0.00	0.10	406			0	0	0	0	0	0	0	0	0	0	0	0
85	East Cresson Mine Area - Topsoil - Lift 6	13.98	98.00	111.98	406	300	D9T	10	75	6,197	21,872	28,069	16,310	5,940	133,910	156,160			
86	East Cresson Mine Area - Topsoil - Lift 6 - Dozer Spreading	0.10	0.00	0.10	406			0	0	0	0	0	0	0	0	0	0	0	0
87	East Cresson Mine Area - Topsoil - WHEX	4.66	195.00	199.66	406	300	D9T	3	150	11,154	39,370	50,524	29,082	10,591	238,760	278,433			
88	East Cresson Mine Area - Topsoil - WHEX - Dozer Spreading	0.10	0.00	0.10	406			0	0	0	0	0	0	0	0	0	0	0	0
89	East Cresson Mine Area - Topsoil - Ironclad	0.93	14.00	14.93	406	300	D9T	1	11	875	3,088	3,963	2,174	792	17,854	20,820			
90	East Cresson Mine Area - Topsoil - Ironclad - Dozer Spreading	0.10	0.00	0.10	406			0	0	0	0	0	0	0	0	0	0	0	0
91	Main Cresson Mine Area - Pile Leveling - Mass Grading	0.10	0.00	0.10	50			0	0	0	0	0	0	0	0	0	0	0	0
92	Main Cresson Mine Area - Pile Leveling - Fine Grading	0.10	0.00	0.10	50			0	0	0	0	0	0	0	0	0	0	0	0
93	Main Cresson Mine Area - 50 ft lift - Mass Grading	0.10	0.00	0.10	135			0	0	0	0	0	0	0	0	0	0	0	0
94	Main Cresson Mine Area - 50 ft lift - Fine Grading	0.10	0.00	0.10	135			0	0	0	0	0	0	0	0	0	0	0	0
95	Main Cresson Mine Area - 150 ft lift - Mass Grading	0.10	0.00	0.10	406			0	0	0	0	0	0	0	0	0	0	0	0
96	Main Cresson Mine Area - 150 ft lift - Fine Grading	0.10	0.00	0.10	406			0	0	0	0	0	0	0	0	0	0	0	0
97	Main Cresson Mine Area - 400 ft lift - Mass Grading	0.10	0.00	0.10	1,083			0	0	0	0	0	0	0	0	0	0	0	0
98	Main Cresson Mine Area - 400 ft lift - Fine Grading	0.10	0.00	0.10	1,083			0	0	0	0	0	0	0	0	0	0	0	0
99	Main Cresson Mine Area - 450 ft lift - Mass Grading	0.10	0.00	0.10	1,218			0	0	0	0	0	0	0	0	0	0	0	0
100	Main Cresson Mine Area - 450 ft lift - Fine Grading	0.10	0.00	0.10	1,218			0	0	0	0	0	0	0	0	0	0	0	0
101	Main Cresson Mine Area - 650 ft lift - Mass Grading	0.10	0.00	0.10	1,760			0	0	0	0	0	0	0	0	0	0	0	0
102	Main Cresson Mine Area - 650 ft lift - Fine Grading	0.10	0.00	0.10	1,760			0	0	0	0	0	0	0	0	0	0	0	0
103	Main Cresson Mine Area - Topsoil - 10185	20.20	63.00	83.20	1,760	400	D9T	15	48	4,593	16,211	20,804	12,118	4,414	99,493	116,025			
104	Main Cresson Mine Area - Topsoil - 10185 - Dozer Spreading	0.10	0.00	0.10	1,760			0	0	0	0	0	0	0	0	0	0	0	0
105	Main Cresson Mine Area - Topsoil - Ruby Road	23.30	50.00	73.30	406	300	D9T	17	38	4,010	14,153	18,163	10,677	3,888	87,656	102,221			
106	Main Cresson Mine Area - Topsoil - Ruby Road - Dozer Spreading	0.10	0.00	0.10	406			0	0	0	0	0	0	0	0	0	0	0	0
107	Main Cresson Mine Area - Topsoil - AJAX	2.31	31.00	33.31	67	100	D9T	2	27	2,114	7,462	9,576	4,851	1,767	39,833	46,451			
108	Main Cresson Mine Area - Topsoil - AJAX - Dozer Spreading	0.10	0.00	0.10	67			0	0	0	0	0	0	0	0	0	0	0	0
109	Main Cresson Mine Area - Topsoil - Pit Bottom	0.10	69.00	69.10	1,760	300	D9T	1	53	3,937	13,895	17,832	10,065	3,665	82,633	96,363			
110	Main Cresson Mine Area - Topsoil - Pit Bottom - Dozer Spreading	0.10	0.00	0.10	100			0	0	0	0	0	0	0	0	0	0	0	0
111	Main Cresson Mine Area - Topsoil - South Cresson HR	0.10	30.00	30.10	1,760	300	D9T	1	23	1,750	6,176	7,926	4,385	1,596	35,995	41,976			
112	Main Cresson Mine Area - Topsoil - South Cresson HR - Dozer Spreading	0.10	0.00	0.10	112			0	0	0	0	0	0	0	0	0	0	0	0
113	Main Cresson Mine Area - Topsoil - Cresson HR	0.10	30.00	30.10	1,760	300	D9T	1	23	1,750	6,176	7,926	4,385	1,596	35,995	41,976			
114	Main Cresson Mine Area - Topsoil - Cresson HR - Dozer Spreading	0.10	0.00	0.10	112		</												

Notes:
1. Minimum total ripping hours = 1 (i.e. If total ripping hrs (slope + flat) < 1, then one hour of fleet time is assumed, regardless of acres shown in scarifying table.)
2. A maximum of 50 acres is assumed per availability.

2. Assumes 50 min/hr equipment availability

Closure Cost Estimate
Heap Leach

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Heap Leach Pads - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Drain Installation	0	0	0	0
Grading Costs	792,205	3,396,854	N/A	4,189,050
Cove 1 Placement Cost	0	0	N/A	0
Cove 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	291,145	2,414,874	N/A	2,706,019
Ripping/Scarfing Cost	90,470	130,999	N/A	221,469
Subtotal Earthworks	1,173,820	5,942,727	0	7,116,547
Revegetation Cost	181,485	66,098	1,489,998	1,737,581
TOTALS	1,355,305	6,008,825	1,489,998	8,854,128

Heap Leach Pads - User Input

	Description (required)	ID Code	Construction Year	Facility Description		Properties	Cost Type	Ground Slope at Toe % grade	Ungraded Slope H:1V	Final Slope	Final Top Slope % grade	Lift (heap) Height ft	Mid-Bench Length ft	Average Flat Area Length Dimension (ripping distance) ft	(Regraded) Heap Footprint acres	Physical (1) - MANDATORY			Cover 1			Cover 2			Growth Media						
				Facility/Activity Type	Phases											Haul Distance to Placement Location (2) ft	Slope to Placement Location % grade	Cover Thickness Slopes in	Cover Thickness Flat Areas in	Haul Distance to Placement Location (2) ft	Slope to Placement Location % grade	Cover Thickness Slopes in	Cover Thickness Flat Areas in	Haul Distance to Placement Location (2) ft	Slope from Dump to Cover Borrow % grade	Slope Growth Media Thickness in	Flat Area Growth Media Thickness in	Haul Distance to Placement Location ft	Slope to Placement Location % grade		
1	AGVL-F - Mass Grading		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	1.0	100			6,048,388												6.0	6.0	2,000	-0.6	
2	AGVL-F - Topsill		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	1.0	175	200	350	34.77	0												6.0	6.0	3,087	3.9
3	AGVL-F - Topsill - Dozer Spreading		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	1.0	175			25.997												6.0	6.0	3,196	-0.7	
4	AGVL-F - Topsill - Lift 1		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	150	3104	175	21.57												6.0	6.0	4,268	-3.3	
5	AGVL-F - Topsill - Lift 1 - Dozer Spreading		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	150			32.998												6.0	6.0	6,312	-5.5	
6	AGVL-F - Topsill - Lift 2		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	141	4295	355	35.82												6.0	6.0	7,462	-6.2	
7	AGVL-F - Topsill - Lift 2 - Dozer Spreading		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	141			42.669												6.0	6.0	8,747	-6.8	
8	AGVL-F - Topsill - Lift 3		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	118	5370	355	48.87	0											6.0	6.0	10,490	-6.8	
9	AGVL-F - Topsill - Lift 3 - Dozer Spreading		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	118			62,280												6.0	6.0	1,859	-8.0	
10	AGVL-F - Topsill - Lift 4		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	207	5769	415	54.92	0											6.0	6.0	2,908	-8.9	
11	AGVL-F - Topsill - Lift 4 - Dozer Spreading		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	207			63,390												6.0	6.0	3,710	3.9	
12	AGVL-F - Topsill - Lift 5		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	113	7392	465	73.41	0											6.0	6.0	20,252	-7.1	
13	AGVL-F - Topsill - Lift 5 - Dozer Spreading		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	113			80,185												6.0	6.0	2,000	-0.6	
14	AGVL-F - Topsill - Lift 6		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	133	7598	685	93.43	0											6.0	6.0	2,000	-0.6	
15	AGVL-F - Topsill - Lift 6 - Dozer Spreading		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	133			107,526												6.0	6.0	2,000	-0.6	
16	AGVL-F - Topsill - Lift 7		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	118	1500	700	131.07	0											6.0	6.0	2,000	-0.6	
17	AGVL-F - Topsill - Lift 7 - Dozer Spreading		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	118			62,653												6.0	6.0	2,000	-0.6	
18	AGVL-F - Topsill - Lift 8		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	200	5999	415	49.28	0											6.0	6.0	2,000	-0.6	
19	AGVL-F - Topsill - Lift 8 - Dozer Spreading		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	200			44,511												6.0	6.0	2,000	-0.6	
20	AGVL-F - Topsill - Lift 9		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	106	4569	415	51.64	0											6.0	6.0	2,000	-0.6	
21	AGVL-F - Topsill - Lift 9 - Dozer Spreading		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	106			41,737												6.0	6.0	2,000	-0.6	
22	SGVL-F - Mass Grading		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	100			3,982,293												6.0	6.0	6,269	7.1	
23	SGVL-F - Topsill - Lift 1		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	100	1333	245	18.10												6.0	6.0	2,000	-0.6	
24	SGVL-F - Topsill - Lift 1 - Dozer Spreading		2009	Heap Leach Pads Reclamation		ARO+LOM+FA		0.0	1.4	2.5	0.0	100			21,411												6.0	6.0	4,774	5.4	
25	SGVL-F - Topsill - Lift 2		2009	Heap Leach Pads Reclamation		ARO+LOM																									

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

sure Cost Estimate Heap Leach

Heap Leach Pads - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Drain Installation	0	0	0	0
Grading Costs	792,205	3,396,854	N/A	4,189,059
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	291,145	2,414,874	N/A	2,706,019
Ripping/Scarifying Cost	90,470	130,999	N/A	221,469
Subtotal Earthworks	1,173,820	5,942,727	0	7,116,547
Revegetation Cost	181,485	66,098	1,489,998	1,737,581
TOTALS	1,355,305	6,008,825	1,489,998	8,854,128

Heap Leach - User Input (Cont.)

Notes:

1. Input distance from crusher to placement location if material to be crushed, screened or compacted
2. If distance from borrow <820 ft (250 m) must select loader fleet

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Heap Leach Pads - ARO Cost Summary

	Labor \$	Equipment \$	Materials \$	Totals \$
Drain Installation	0	0	0	0
Grading Costs	792,205	3,396,854	N/A	4,189,059
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	291,145	2,414,874	N/A	2,706,019
Ripping/Scarifying Cost	90,470	130,999	N/A	221,469
Subtotal Earthworks	1,173,820	5,942,727	0	7,116,547
Revegetation Cost	181,485	66,098	1,489,998	1,737,581
TOTALS	1,355,305	6,008,825	1,489,998	8,854,128

Heap Leach Pads - User Input (cont.)

You must fill in ALL green cells and relevant blue cells in this section for each heap, lift or heap category

Notes:

1. Material Types are used for density correction based on material densities in Caterpillar Performance Handbook material density table

Closure Cost Estimate
Heap Leach

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Heap Leach Pads - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Drain Installation	0	0	0	0
Grading Costs	792,205	3,396,854	N/A	4,189,050
Cove 1 Placement Cost	0	0	N/A	0
Cove 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	291,145	2,414,874	N/A	2,706,019
Ripping/Scarfing Cost	90,470	130,999	N/A	221,469
Subtotal Earthworks	1,173,820	5,942,727	0	7,116,547
Revegetation Cost	181,485	66,098	1,489,998	1,737,581
TOTALS	1,355,305	6,008,825	1,489,998	8,854,128

Heap Leach Pads - User Input (cont.)

	Description (required)	Solution Collection Ditch Fill					Piping					
		Collection Ditch Length ft	Collection Ditch Top Width ft	Collection Ditch Depth ft	Volume (if calculated elsewhere) cy	Distance from Borrow ft	Slope to Borrow % grade	Drain Rock Equipment Fleet (select)	Solid Pipe Length ft	Solid Pipe Type (select)	Drainage Pipe Length ft	Drainage Pipe Type (select)
1	AGVLF - Mass Grading											
2	AGVLF - Topsill											
3	AGVLF - Topsill - Dozer Spreading											
4	AGVLF - Topsill - Lift 1											
5	AGVLF - Topsill - Lift 1 - Dozer Spreading											
6	AGVLF - Topsill - Lift 2											
7	AGVLF - Topsill - Lift 2 - Dozer Spreading											
8	AGVLF - Topsill - Lift 3											
9	AGVLF - Topsill - Lift 3 - Dozer Spreading											
10	AGVLF - Topsill - Lift 4											
11	AGVLF - Topsill - Lift 4 - Dozer Spreading											
12	AGVLF - Topsill - Lift 5											
13	AGVLF - Topsill - Lift 5 - Dozer Spreading											
14	AGVLF - Topsill - Lift 6											
15	AGVLF - Topsill - Lift 6 - Dozer Spreading											
16	AGVLF - Topsill - Lift 7											
17	AGVLF - Topsill - Lift 7 - Dozer Spreading											
18	AGVLF - Topsill - Lift 8											
19	AGVLF - Topsill - Lift 8 - Dozer Spreading											
20	AGVLF - Topsill - Lift 9											
21	AGVLF - Topsill - Lift 9 - Dozer Spreading											
22	SGVLF - Mass Grading											
23	SGVLF - Topsill - Lift 1											
24	SGVLF - Topsill - Lift 1 - Dozer Spreading											
25	SGVLF - Topsill - Lift 2											
26	SGVLF - Topsill - Lift 2 - Dozer Spreading											
27	SGVLF - Topsill - Lift 3											
28	SGVLF - Topsill - Lift 3 - Dozer Spreading											
29	SGVLF - Topsill - Lift 4											
30	SGVLF - Topsill - Lift 4 - Dozer Spreading											
31	SGVLF - Topsill - Lift 5											
32	SGVLF - Topsill - Lift 5 - Dozer Spreading											
33	SGVLF - Topsill - Lift 6											
34	SGVLF - Topsill - Lift 6 - Dozer Spreading											
35	SGVLF - Topsill - Lift 7											
36	SGVLF - Topsill - Lift 7 - Dozer Spreading											
37	SGVLF - Topsill - Lift 8											
38	SGVLF - Topsill - Lift 8 - Dozer Spreading											
39	SGVLF - Topsill - Lift 9											
40	SGVLF - Topsill - Lift 9 - Dozer Spreading											
41	SGVLF - Topsill - Lift 10											
42	SGVLF - Topsill - Lift 10 - Dozer Spreading											
43	SGVLF - Topsill - Lift 11											
44	SGVLF - Topsill - Lift 11 - Dozer Spreading											
45	SGVLF - Topsill - Lift 12											
46	SGVLF - Topsill - Lift 12 - Dozer Spreading											
47	SGVLF - Topsill - Lift 13											
48	SGVLF - Topsill - Lift 13 - Dozer Spreading											

Notes:

Closure Cost Estimate
Heap Leach

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Heap Leach Pads - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Drain Installation	0	0	0	0
Grading Costs	792,205	3,396,854	N/A	4,189,059
Cove 1 Placement Cost	0	0	N/A	0
Cove 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	291,145	2,414,874	N/A	2,706,019
Ripping/Scarfing Cost	90,470	130,999	N/A	221,469
Subtotal Earthworks	1,173,820	5,942,727	0	7,116,547
Revegetation Cost	181,485	66,098	1,489,998	1,737,581
TOTALS	1,355,305	6,008,825	1,489,998	8,954,128

Heap Leach - Assumptions & Calculations

Regrading Push Distance Calculation

dozing distance:
 based on 2/3 final cut slope + 2/3 final fill slope (minimum = 50 ft)

Ripping/Scarfing Calculations

Minimum 1 hr ripping/scarfing per area

Slopes:
 Number of passes = Final slope length ÷ Grader width
 Travel distance = Number of passes × Mid-bench length
 Total hours = (Travel distance ÷ Grader productivity) + (Number of passes × Grader maneuver time)

Flat Areas:
 Flat area width = Final flat area ÷ Average long dimensions
 Number of passes = Flat area width ÷ Grader width
 Travel distance = Number of passes × Average long dimensions
 Total hours = (Travel distance ÷ Grader productivity) + (Number of passes × Grader maneuver time)

Revegetation:
 Minimum 1 acre revegetation crew time per area

Solution Collection Ditch Calculations

Use when existing heap material is not suitable drain rock
 Assume to be constructed in existing solution channels
 Assume 2H:1V ditch sideslopes
 Drain rock assumed to be Gravel - Dry at 2,550 lb/cy (1,510 kg/m³) from CAT Handbook 35th Ed.

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Closure Cost Estimate
Heap Leach

Heap Leach Pads - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Drain Installation	0	0	0	0
Grading Costs	792,205	3,396,854	N/A	4,189,050
Cove 1 Placement Cost	0	0	N/A	0
Cove 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	291,145	2,414,874	N/A	2,706,019
Ripping/Scarfing Cost	90,470	130,999	N/A	221,469
Subtotal Earthworks	1,173,820	5,942,727	0	7,116,547
Revegetation Cost	181,485	66,098	1,489,998	1,737,581
TOTALS	1,355,305	6,008,825	1,489,998	8,854,128

Heap Leach Pad - Drainage Channel Fill & Drainage Pipe Installation

	Description (required)	Drain Rock Placement							Drainpipe Installation					
		Drain Rock Volume cy	Drain Rock Fleet	Fleet Productivity LCY/hr	Number of Trucks/ Scrapers	Total Fleet Hours hrs	Drainage Labor Cost \$	Drainage Equipment Cost \$	Total Drainage Cost \$	Piping Crew Hours hrs	Piping Labor Cost \$	Piping Equipment Cost \$	Piping Material Cost \$	Total Pipe Installation Cost \$
1	AGVL.F - Mass Grading	0				0	0	0	0	0	0	0	0	0
2	AGVL.F - Topsoll	0				0	0	0	0	0	0	0	0	0
3	AGVL.F - Topsoll - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
4	AGVL.F - Topsoll - Lift 1	0				0	0	0	0	0	0	0	0	0
5	AGVL.F - Topsoll - Lift 1 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
6	AGVL.F - Topsoll - Lift 2	0				0	0	0	0	0	0	0	0	0
7	AGVL.F - Topsoll - Lift 2 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
8	AGVL.F - Topsoll - Lift 3	0				0	0	0	0	0	0	0	0	0
9	AGVL.F - Topsoll - Lift 3 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
10	AGVL.F - Topsoll - Lift 4	0				0	0	0	0	0	0	0	0	0
11	AGVL.F - Topsoll - Lift 4 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
12	AGVL.F - Topsoll - Lift 5	0				0	0	0	0	0	0	0	0	0
13	AGVL.F - Topsoll - Lift 5 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
14	AGVL.F - Topsoll - Lift 6	0				0	0	0	0	0	0	0	0	0
15	AGVL.F - Topsoll - Lift 6 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
16	AGVL.F - Topsoll - Lift 7	0				0	0	0	0	0	0	0	0	0
17	AGVL.F - Topsoll - Lift 7 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
18	AGVL.F - Topsoll - Lift 8	0				0	0	0	0	0	0	0	0	0
19	AGVL.F - Topsoll - Lift 8 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
20	AGVL.F - Topsoll - Lift 9	0				0	0	0	0	0	0	0	0	0
21	AGVL.F - Topsoll - Lift 9 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
22	SGVL.F - Mass Grading	0				0	0	0	0	0	0	0	0	0
23	SGVL.F - Topsoll - Lift 1	0				0	0	0	0	0	0	0	0	0
24	SGVL.F - Topsoll - Lift 1 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
25	SGVL.F - Topsoll - Lift 2	0				0	0	0	0	0	0	0	0	0
26	SGVL.F - Topsoll - Lift 2 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
27	SGVL.F - Topsoll - Lift 3	0				0	0	0	0	0	0	0	0	0
28	SGVL.F - Topsoll - Lift 3 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
29	SGVL.F - Topsoll - Lift 4	0				0	0	0	0	0	0	0	0	0
30	SGVL.F - Topsoll - Lift 4 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
31	SGVL.F - Topsoll - Lift 5	0				0	0	0	0	0	0	0	0	0
32	SGVL.F - Topsoll - Lift 5 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
33	SGVL.F - Topsoll - Lift 6	0				0	0	0	0	0	0	0	0	0
34	SGVL.F - Topsoll - Lift 6 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
35	SGVL.F - Topsoll - Lift 7	0				0	0	0	0	0	0	0	0	0
36	SGVL.F - Topsoll - Lift 7 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
37	SGVL.F - Topsoll - Lift 8	0				0	0	0	0	0	0	0	0	0
38	SGVL.F - Topsoll - Lift 8 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
39	SGVL.F - Topsoll - Lift 9	0				0	0	0	0	0	0	0	0	0
40	SGVL.F - Topsoll - Lift 9 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
41	SGVL.F - Topsoll - Lift 10	0				0	0	0	0	0	0	0	0	0
42	SGVL.F - Topsoll - Lift 10 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
43	SGVL.F - Topsoll - Lift 11	0				0	0	0	0	0	0	0	0	0
44	SGVL.F - Topsoll - Lift 11 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
45	SGVL.F - Topsoll - Lift 12	0				0	0	0	0	0	0	0	0	0
46	SGVL.F - Topsoll - Lift 12 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0
47	SGVL.F - Topsoll - Lift 13	0				0	0	0	0	0	0	0	0	0
48	SGVL.F - Topsoll - Lift 13 - Dozer Spreading	0				0	0	0	0	0	0	0	0	0

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Closure Cost Estimate
Heap Leach

Heap Leach Pads - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Drain Installation	0	0	0	0
Grading Costs	792,205	3,396,854	N/A	4,189,050
Cove 1 Placement Cost	0	0	N/A	0
Cove 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	291,145	2,414,874	N/A	2,706,019
Ripping/Scarfing Cost	90,470	130,999	N/A	221,469
Subtotal Earthworks	1,173,820	5,942,727	0	7,116,547
Revegetation Cost	181,485	66,098	1,489,998	1,737,581
TOTALS	1,355,305	6,008,825	1,489,998	8,584,128

Heap Leach Pad - Regrading Costs

Productivity = Dozer Productivity x Grade Correction x Density Correction x Operator (0.75) x Material x Visibility x Job Efficiency (0.83) x (Slot/Side-by-Side) x (Altitude Deration)

	Description (required)	Regrading Volume cy	Dozing Distance (see above ft)	Regrading Fleet	Uncorrected Dozer Productivity cy/hr	Grade Correction	Dozing Material	Density Correction	Side-by-Side or Slot Dozing	Total Hourly Productivity	Total Dozer Hours hr	Total Labor Cost \$	Total Equipment Cost \$	Total Regrading Cost \$
1	AGVL-F - Mass Grading	6,049,388	147	D10T2	1.107	1.6	1.0	0.85	1.2	1,125	5,376	391,910	1,907,459	2,299,368
2	AGVL-F - Topsoll	0		Select Fleet						0		0	0	0
3	AGVL-F - Topsoll - Dozer Spreading	25,997	257	D7E	260	1.6	1.2	1.44	1.0	443	59	4,301	6,228	10,523
4	AGVL-F - Topsoll - Lift 1	0		Select Fleet						0		0	0	0
5	AGVL-F - Topsoll - Lift 1 - Dozer Spreading	32,998	219	D7E	297	1.6	1.2	1.44	1.0	506	65	4,739	6,861	11,600
6	AGVL-F - Topsoll - Lift 2	0		Select Fleet						0		0	0	0
7	AGVL-F - Topsoll - Lift 2 - Dozer Spreading	42,869	206	D7E	313	1.6	1.2	1.44	1.0	533	80	5,832	8,445	14,277
8	AGVL-F - Topsoll - Lift 3	0		Select Fleet						0		0	0	0
9	AGVL-F - Topsoll - Lift 3 - Dozer Spreading	62,280	172	D7E	363	1.6	1.2	1.44	1.0	619	101	7,363	10,662	18,025
10	AGVL-F - Topsoll - Lift 4	0		Select Fleet						0		0	0	0
11	AGVL-F - Topsoll - Lift 4 - Dozer Spreading	63,390	302	D7E	227	1.6	1.2	1.44	1.0	387	184	11,956	17,312	29,268
12	AGVL-F - Topsoll - Lift 5	0		Select Fleet						0		0	0	0
13	AGVL-F - Topsoll - Lift 5 - Dozer Spreading	80,185	165	D7E	376	1.6	1.2	1.44	1.0	641	125	9,113	13,195	22,308
14	AGVL-F - Topsoll - Lift 6	0		Select Fleet						0		0	0	0
15	AGVL-F - Topsoll - Lift 6 - Dozer Spreading	107,526	194	D7E	329	1.6	1.2	1.44	1.0	561	192	13,997	20,268	34,265
16	AGVL-F - Topsoll - Lift 7	0		Select Fleet						0		0	0	0
17	AGVL-F - Topsoll - Lift 7 - Dozer Spreading	62,653	172	D7E	363	1.6	1.2	1.44	1.0	619	101	7,363	10,662	18,025
18	AGVL-F - Topsoll - Lift 8	0		Select Fleet						0		0	0	0
19	AGVL-F - Topsoll - Lift 8 - Dozer Spreading	44,511	292	D7E	234	1.6	1.2	1.44	1.0	399	112	8,165	11,823	19,988
20	AGVL-F - Topsoll - Lift 9	0		Select Fleet						0		0	0	0
21	AGVL-F - Topsoll - Lift 9 - Dozer Spreading	41,737	155	D7E	396	1.6	1.2	1.44	1.0	675	62	4,520	6,545	11,065
22	SGVL-F - Mass Grading	3,982,293	146	D10T2	1,113	1.6	1.0	0.82	1.2	1,091	3,650	266,085	1,295,057	1,561,142
23	SGVL-F - Topsoll - Lift 1	67,884	146	Select Fleet	Select Fleet	1.6	Dozing Material	Material Type!	1.0	Select Fleet	0	0	0	0
24	SGVL-F - Topsoll - Lift 1 - Dozer Spreading	21,411	146	D7E	416	1.6	1.2	1.44	1.0	709	30	2,187	3,167	5,354
25	SGVL-F - Topsoll - Lift 2	108,065	146	Select Fleet	Select Fleet	1.6	Dozing Material	Material Type!	1.0	Select Fleet	0	0	0	0
26	SGVL-F - Topsoll - Lift 2 - Dozer Spreading	20,641	146	D7E	416	1.6	1.2	1.44	1.0	709	29	2,114	3,061	5,175
27	SGVL-F - Topsoll - Lift 3	153,694	146	Select Fleet	Select Fleet	1.6	Dozing Material	Material Type!	1.0	Select Fleet	0	0	0	0
28	SGVL-F - Topsoll - Lift 3 - Dozer Spreading	24,747	146	D7E	416	1.6	1.2	1.44	1.0	709	35	2,552	3,695	6,247
29	SGVL-F - Topsoll - Lift 4	177,986	146	Select Fleet	Select Fleet	1.6	Dozing Material	Material Type!	1.0	Select Fleet	0	0	0	0
30	SGVL-F - Topsoll - Lift 4 - Dozer Spreading	33,707	146	D7E	416	1.6	1.2	1.44	1.0	709	48	3,499	5,067	8,566
31	SGVL-F - Topsoll - Lift 5	374,509	146	Select Fleet	Select Fleet	1.6	Dozing Material	Material Type!	1.0	Select Fleet	0	0	0	0
32	SGVL-F - Topsoll - Lift 5 - Dozer Spreading	49,182	146	D7E	416	1.6	1.2	1.44	1.0	709	69	5,030	7,284	12,314
33	SGVL-F - Topsoll - Lift 6	463,324	146	Select Fleet	Select Fleet	1.6	Dozing Material	Material Type!	1.0	Select Fleet	0	0	0	0
34	SGVL-F - Topsoll - Lift 6 - Dozer Spreading	78,755	146	D7E	416	1.6	1.2	1.44	1.0	709	111	8,092	11,717	19,809
35	SGVL-F - Topsoll - Lift 7	514,861	146	Select Fleet	Select Fleet	1.6	Dozing Material	Material Type!	1.0	Select Fleet	0	0	0	0
36	SGVL-F - Topsoll - Lift 7 - Dozer Spreading	62,978	146	D7E	416	1.6	1.2	1.44	1.0	709	89	6,488	9,395	15,883
37	SGVL-F - Topsoll - Lift 8	477,176	146	Select Fleet	Select Fleet	1.6	Dozing Material	Material Type!	1.0	Select Fleet	0	0	0	0
38	SGVL-F - Topsoll - Lift 8 - Dozer Spreading	56,183	146	D7E	416	1.6	1.2	1.44	1.0	709	79	5,759	8,339	14,098
39	SGVL-F - Topsoll - Lift 9	430,120	146	Select Fleet	Select Fleet	1.6	Dozing Material	Material Type!	1.0	Select Fleet	0	0	0	0
40	SGVL-F - Topsoll - Lift 9 - Dozer Spreading	51,252	146	D7E	416	1.6	1.2	1.44	1.0	709	72	5,249	7,600	12,848
41	SGVL-F - Topsoll - Lift 10	366,972	146	Select Fleet	Select Fleet	1.6	Dozing Material	Material Type!	1.0	Select Fleet	0	0	0	0
42	SGVL-F - Topsoll - Lift 10 - Dozer Spreading	46,549	146	D7E	416	1.6	1.2	1.44	1.0	709	66	4,811	6,967	11,778
43	SGVL-F - Topsoll - Lift 11	334,736	146	Select Fleet	Select Fleet	1.6	Dozing Material	Material Type!	1.0	Select Fleet	0	0	0	0
44	SGVL-F - Topsoll - Lift 11 - Dozer Spreading	46,487	146	D7E	416	1.6	1.2	1.44	1.0	709	66	4,811	6,967	11,778
45	SGVL-F - Topsoll - Lift 12	102,463	146	Select Fleet	Select Fleet	1.6	Dozing Material	Material Type!	1.0	Select Fleet	0	0	0	0
46	SGVL-F - Topsoll - Lift 12 - Dozer Spreading	35,364	146	D7E	416	1.6	1.2	1.44	1.0	709	50	3,645	5,278	8,923
47	SGVL-F - Topsoll - Lift 13	76,390	146	Select Fleet	Select Fleet	1.6	Dozing Material	Material Type!	1.0	Select Fleet	0	0	0	0
48	SGVL-F - Topsoll - Lift 13 - Dozer Spreading	25,814	146	D7E	416	1.6	1.2	1.44	1.0	709	3			

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

sure Cost Estimate Heap Leach

Heap Leach Pads - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Drain Installation	0	0	0	0
Grading Costs	792,205	3,396,854	N/A	4,189,059
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	291,145	2,414,874	N/A	2,706,019
Ripping/Scarifying Cost	90,470	130,999	N/A	221,469
Subtotal Earthworks	1,173,820	5,942,727	0	7,116,547
Revegetation Cost	181,485	66,098	1,489,998	1,737,581
TOTALS	1,355,305	6,008,825	1,489,998	8,854,128

Notes:

1. If crushed or screened, Cover Volume = volume delivered to crusher - amount loss to crushing/screening)

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Closure Cost Estimate
Heap Leach

Heap Leach Pads - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Drain Installation	0	0	0	0
Grading Costs	792,205	3,396,854	N/A	4,189,050
Cove 1 Placement Cost	0	0	N/A	0
Cove 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	291,145	2,414,874	N/A	2,706,019
Ripping/Scarfing Cost	90,470	130,999	N/A	221,469
Subtotal Earthworks	1,173,820	5,942,727	0	7,116,547
Revegetation Cost	181,485	66,098	1,489,998	1,737,581
TOTALS	1,355,305	6,008,825	1,489,998	8,954,128

Heap Leach - Cover 2 Costs		Material Volumes		Haul to Crusher				Haul to Placement				Haul to Crusher				Crush			Compact			Haul to Placement			Total		
	Description (required)	Material Volume to Crusher cy	Final Material Volume cy	Crusher Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity LCM/hr	Fleet Hours hrs	Placement Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity LCM/hr	Fleet Hours hrs	Labor Cost \$	Equipment Cost \$	Total Cost \$	Total Crush/Screen Cost \$	Labor Cost \$	Equipment Cost \$	Total Cost \$	Labor Cost \$	Equipment Cost \$	Total Cost \$	Total Cover Cost \$			
1	AGVLF - Mass Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
2	AGVLF - Topsoll	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
3	AGVLF - Topsoll - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
4	AGVLF - Topsoll - Lift 1	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
5	AGVLF - Topsoll - Lift 1 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
6	AGVLF - Topsoll - Lift 2	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
7	AGVLF - Topsoll - Lift 2 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
8	AGVLF - Topsoll - Lift 3	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
9	AGVLF - Topsoll - Lift 3 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
10	AGVLF - Topsoll - Lift 4	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
11	AGVLF - Topsoll - Lift 4 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
12	AGVLF - Topsoll - Lift 5	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
13	AGVLF - Topsoll - Lift 5 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
14	AGVLF - Topsoll - Lift 6	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
15	AGVLF - Topsoll - Lift 6 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
16	AGVLF - Topsoll - Lift 7	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
17	AGVLF - Topsoll - Lift 7 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
18	AGVLF - Topsoll - Lift 8	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
19	AGVLF - Topsoll - Lift 8 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
20	AGVLF - Topsoll - Lift 9	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
21	AGVLF - Topsoll - Lift 9 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
22	SGVLF - Mass Grading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
23	SGVLF - Topsoll - Lift 1	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
24	SGVLF - Topsoll - Lift 1 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
25	SGVLF - Topsoll - Lift 2	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
26	SGVLF - Topsoll - Lift 2 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
27	SGVLF - Topsoll - Lift 3	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
28	SGVLF - Topsoll - Lift 3 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
29	SGVLF - Topsoll - Lift 4	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
30	SGVLF - Topsoll - Lift 4 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
31	SGVLF - Topsoll - Lift 5	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
32	SGVLF - Topsoll - Lift 5 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
33	SGVLF - Topsoll - Lift 6	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
34	SGVLF - Topsoll - Lift 6 - Dozer Spreading	0	0					0					0	0	0	0	0	0	0	0	0	0	0	0	0	0	
35	SGVLF - Topsoll - Lift 7	0	0					0					0	0	0	0	0										

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Closure Cost Estimate
Heap Leach

Heap Leach Pads - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Drain Installation	0	0	0	0
Crushing Costs	792,205	3,396,854	N/A	4,189,050
Cove 1 Placement Cost	0	0	N/A	0
Cove 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	291,145	2,414,874	N/A	2,706,019
Ripping/Scarfing Cost	90,470	130,999	N/A	221,469
Subtotal Earthworks	1,173,820	5,942,727	0	7,116,547
Revegetation Cost	181,485	66,098	1,489,998	1,737,581
TOTALS	1,355,305	6,008,825	1,489,998	8,554,128

Heap Leach - Growth Media Costs										
Growth Media Placement										
	Description (required)	Final Material Volume cy	Placement Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity BCY/hr	Fleet Hours hrs	Labor Cost \$	Equipment Cost \$	Total Cost \$
1 AGVLF - Mass Grading							0	0	0	0
2 AGVLF - Topsoll	28,177	777G/992K/D10T2	5.77	2	1,150	25	5,858	44,716	50,574	
3 AGVLF - Topsoll - Dozer Spreading							0	0	0	0
4 AGVLF - Topsoll - Lift 1	23,224	777G/992K/D10T2	6.87	2	966	24	5,623	42,927	48,550	
5 AGVLF - Topsoll - Lift 1 - Dozer Spreading							0	0	0	0
6 AGVLF - Topsoll - Lift 2	31,041	777G/992K/D10T2	6.55	2	1,013	31	7,263	55,448	62,711	
7 AGVLF - Topsoll - Lift 2 - Dozer Spreading							0	0	0	0
8 AGVLF - Topsoll - Lift 3	41,704	777G/992K/D10T2	8.47	3	1,175	36	10,008	80,251	90,259	
9 AGVLF - Topsoll - Lift 3 - Dozer Spreading							0	0	0	0
10 AGVLF - Topsoll - Lift 4	59,508	777G/992K/D10T2	11.72	4	1,132	53	17,051	141,498	158,549	
11 AGVLF - Topsoll - Lift 4 - Dozer Spreading							0	0	0	0
12 AGVLF - Topsoll - Lift 5	62,234	777G/992K/D10T2	14.74	5	1,125	55	20,099	171,063	191,168	
13 AGVLF - Topsoll - Lift 5 - Dozer Spreading							0	0	0	0
14 AGVLF - Topsoll - Lift 6	79,021	777G/992K/D10T2	16.51	6	1,205	66	27,003	234,360	261,363	
15 AGVLF - Topsoll - Lift 6 - Dozer Spreading							0	0	0	0
16 AGVLF - Topsoll - Lift 7	106,367	777G/992K/D10T2	18.92	7	1,226	87	39,398	347,259	386,657	
17 AGVLF - Topsoll - Lift 7 - Dozer Spreading							0	0	0	0
18 AGVLF - Topsoll - Lift 8	59,879	777G/992K/D10T2	8.81	3	1,130	53	14,735	118,148	132,883	
19 AGVLF - Topsoll - Lift 8 - Dozer Spreading							0	0	0	0
20 AGVLF - Topsoll - Lift 9	43,342	777G/992K/D10T2	7.34	2	903	48	11,246	85,854	97,100	
21 AGVLF - Topsoll - Lift 9 - Dozer Spreading							0	0	0	0
22 SGVLF - Mass Grading							0	0	0	0
23 SGVLF - Topsoll - Lift 1	15,069	777G/992K/D10T2	10.43	3	954	16	4,448	35,667	40,115	
24 SGVLF - Topsoll - Lift 1 - Dozer Spreading							0	0	0	0
25 SGVLF - Topsoll - Lift 2	14,294	777G/992K/D10T2	8.19	3	1,215	12	3,336	26,750	30,086	
26 SGVLF - Topsoll - Lift 2 - Dozer Spreading							0	0	0	0
27 SGVLF - Topsoll - Lift 3	18,408	777G/992K/D10T2	7.36	2	901	21	4,920	37,561	42,481	
28 SGVLF - Topsoll - Lift 3 - Dozer Spreading							0	0	0	0
29 SGVLF - Topsoll - Lift 4	27,362	777G/992K/D10T2	6.53	2	1,016	27	6,326	48,293	54,619	
30 SGVLF - Topsoll - Lift 4 - Dozer Spreading							0	0	0	0
31 SGVLF - Topsoll - Lift 5	42,834	777G/992K/D10T2	6.33	2	1,047	41	9,606	73,334	82,940	
32 SGVLF - Topsoll - Lift 5 - Dozer Spreading							0	0	0	0
33 SGVLF - Topsoll - Lift 6	72,407	777G/992K/D10T2	8.86	3	1,123	64	17,793	142,669	160,462	
34 SGVLF - Topsoll - Lift 6 - Dozer Spreading							0	0	0	0
35 SGVLF - Topsoll - Lift 7	56,636	777G/992K/D10T2	8.96	3	1,111	51	14,179	113,689	127,668	
36 SGVLF - Topsoll - Lift 7 - Dozer Spreading							0	0	0	0
37 SGVLF - Topsoll - Lift 8	49,836	777G/992K/D10T2	11.22	4	1,182	42	13,512	112,130	125,642	
38 SGVLF - Topsoll - Lift 8 - Dozer Spreading							0	0	0	0
39 SGVLF - Topsoll - Lift 9	44,915	777G/992K/D10T2	12.65	4	1,049	43	13,834	114,800	128,634	
40 SGVLF - Topsoll - Lift 9 - Dozer Spreading							0	0	0	0
41 SGVLF - Topsoll - Lift 10	40,205	777G/992K/D10T2	15.38	5	1,079	37	13,521	115,083	128,604	
42 SGVLF - Topsoll - Lift 10 - Dozer Spreading							0	0	0	0
43 SGVLF - Topsoll - Lift 11	40,148	777G/992K/D10T2	16.42	6	1,210	33	13,502	117,180	130,682	
44 SGVLF - Topsoll - Lift 11 - Dozer Spreading							0	0	0	0
45 SGVLF - Topsoll - Lift 12	29,016	777G/992K/D10T2	17.39	6	1,145	26	10,638	92,324	102,962	
46 SGVLF - Topsoll - Lift 12 - Dozer Spreading							0	0	0	0
47 SGVLF - Topsoll - Lift 13	19,473	777G/992K/D10T2	19.38	7	1,197	16	7,246	63,864	71,110	
48 SGVLF - Topsoll - Lift 13 - Dozer Spreading							0	0	0	0
						907	291,145	2,414,874	2,706,019	
										1,005,100

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Cost Estimate Cap Leach

Heap Leach Pads - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Drain Installation	0	0	0	0
Grading Costs	792,205	3,396,854	N/A	4,189,059
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Topsoil Placement Cost	291,145	2,414,874	N/A	2,706,019
Ripping/Scarifying Cost	90,470	130,999	N/A	221,469
Subtotal Earthworks	1,173,820	5,942,727	0	7,116,547
Revegetation Cost	181,485	66,098	1,489,998	1,737,581
TOTALS	1,355,305	6,008,825	1,489,998	8,854,128

Heap Leach - Scarify/Revegetation Costs

	Description (required)	Scarifying Costs										Revegetation Costs				
		Slope Area acres	Flat Area acres	Total Surface Area acres	Final Slope Length ft	Average Long Dimension (ripping distance) ft	Ripping/ Scarifying Fleet	Slope Scarifying/ Ripping Hours hrs	Flat Area Scarifying/ Ripping Hours hrs	Scarifying/ Ripping Labor Costs \$	Scarifying/ Ripping Equipment Cost \$	Total Scarifying/ Ripping Costs \$	Revegetation Labor Cost \$	Revegetation Equipment Cost \$	Revegetation Material Cost \$	Total Revegetation Cost \$
1	AGVLF - Mass Grading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
2	AGVLF - Topsoil	2.18	32.75	34.93	474	#REF!	D7E	2	34	2,624	3,800	6,424	5,088	1,853	41,770	48,711
3	AGVLF - Topsoil - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
4	AGVLF - Topsoil - Lift 1	28.79	0.00	28.79	404	#REF!	D7E	29	0	2,114	3,061	5,175	4,193	1,527	34,428	40,148
5	AGVLF - Topsoil - Lift 1 - Dozer Spreading	0.10	0.00	0.10		#REF!		0	0	0	0	0	0	0	0	0
6	AGVLF - Topsoil - Lift 2	37.47	1.01	38.48	380	#REF!	D7E	37	1	2,770	4,011	6,781	5,605	2,042	46,015	53,662
7	AGVLF - Topsoil - Lift 2 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
8	AGVLF - Topsoil - Lift 3	39.20	12.50	51.70	318	355	D7E	39	13	3,791	5,489	9,280	7,531	2,742	61,826	72,099
9	AGVLF - Topsoil - Lift 3 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
10	AGVLF - Topsoil - Lift 4	73.77	0.00	73.77	557	415	D7E	73	0	5,322	7,706	13,028	10,745	3,913	88,217	102,875
11	AGVLF - Topsoil - Lift 4 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
12	AGVLF - Topsoil - Lift 5	51.59	25.56	77.15	304	465	D7E	50	26	5,540	8,023	13,563	11,237	4,093	92,258	107,588
13	AGVLF - Topsoil - Lift 5 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
14	AGVLF - Topsoil - Lift 6	62.44	35.52	97.96	358	685	D7E	61	36	7,071	10,239	17,310	14,269	5,196	117,144	136,609
15	AGVLF - Topsoil - Lift 6 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
16	AGVLF - Topsoil - Lift 7	10.95	120.91	131.86	318	700	D7E	11	122	9,696	14,039	23,735	19,206	6,995	157,682	183,883
17	AGVLF - Topsoil - Lift 7 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
18	AGVLF - Topsoil - Lift 8	74.23	0.00	74.23	539	415	D7E	73	0	5,322	7,706	13,028	10,812	3,938	88,766	103,516
19	AGVLF - Topsoil - Lift 8 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
20	AGVLF - Topsoil - Lift 9	29.89	23.84	53.73	285	415	D7E	29	25	3,937	5,700	9,637	7,826	2,851	64,252	74,929
21	AGVLF - Topsoil - Lift 9 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
22	SGVLF - Mass Grading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
23	SGVLF - Topsoil - Lift 1	8.23	10.45	18.68	269	245	D7E	8	11	1,385	2,006	3,391	2,721	991	22,338	26,050
24	SGVLF - Topsoil - Lift 1 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
25	SGVLF - Topsoil - Lift 2	13.10	4.62	17.72	269	245	D7E	13	5	1,312	1,900	3,212	2,581	940	21,190	24,711
26	SGVLF - Topsoil - Lift 2 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
27	SGVLF - Topsoil - Lift 3	18.64	4.18	22.82	269	#REF!	D7E	18	4	1,604	2,322	3,926	3,324	1,211	27,290	31,825
28	SGVLF - Topsoil - Lift 3 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
29	SGVLF - Topsoil - Lift 4	21.58	12.34	33.92	269	245	D7E	21	13	2,479	3,589	6,068	4,940	1,800	40,564	47,304
30	SGVLF - Topsoil - Lift 4 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
31	SGVLF - Topsoil - Lift 5	45.41	7.69	53.10	269	245	D7E	44	8	3,791	5,489	9,280	7,734	2,817	63,497	74,048
32	SGVLF - Topsoil - Lift 5 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
33	SGVLF - Topsoil - Lift 6	56.18	33.58	89.76	269	245	D7E	55	36	6,634	9,606	16,240	13,074	4,761	107,339	125,174
34	SGVLF - Topsoil - Lift 6 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
35	SGVLF - Topsoil - Lift 7	62.43	7.78	70.21	269	245	D7E	61	8	5,030	7,284	12,314	10,226	3,725	83,959	97,910
36	SGVLF - Topsoil - Lift 7 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
37	SGVLF - Topsoil - Lift 8	57.86	3.92	61.78	269	245	D7E	56	4	4,374	6,334	10,708	8,999	3,277	73,879	86,155
38	SGVLF - Topsoil - Lift 8 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
39	SGVLF - Topsoil - Lift 9	52.16	3.52	55.68	269	245	D7E	51	4	4,010	5,806	9,816	8,110	2,954	66,584	77,648
40	SGVLF - Topsoil - Lift 9 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
41	SGVLF - Topsoil - Lift 10	44.50	5.34	49.84	269	245	D7E	43	6	3,572	5,172	8,744	7,260	2,644	59,601	69,505
42	SGVLF - Topsoil - Lift 10 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
43	SGVLF - Topsoil - Lift 11	40.59	9.18	49.77	269	245	D7E	39	10	3,572	5,172	8,744	7,249	2,640	59,517	69,406
44	SGVLF - Topsoil - Lift 11 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
45	SGVLF - Topsoil - Lift 12	12.42	23.55	35.97	269	245	D7E	12	25	2,697	3,906	6,603	5,239	1,908	43,014	50,161
46	SGVLF - Topsoil - Lift 12 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0	0	0	0	0	0
47	SGVLF - Topsoil - Lift 13	9.26	14.88	24.14	269	245	D7E	9	16	1,823	2,639	4,462	3,516	1,280	28,868	33,664
48	SGVLF - Topsoil - Lift 13 - Dozer Spreading	0.10	0.00	0.10		Rip Dist		0	0	0	0					

Notes: 1) Minimum total ripping hours = 1 (i.e. If total ripping hrs (slope + flat) < 1, then one hour of fleet time is assumed, regardless of acres shown in scarifying table.)
2) Assumes 50 min/hr equipment availability

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Closure Cost Estimate
 Process Ponds

Process Ponds - ARO Cost Summary					
	Labor \$	Equipment \$	Materials \$	Markup \$	Totals \$
Liner Cutting & Folding Costs	59,742	28,809	N/A	N/A	88,551
Backfill 1 Costs	103,976	334,367	N/A	N/A	438,343
Backfill 2 Costs	0	0	N/A	N/A	0
Growth Media Placement Costs	5,838	18,774	N/A	N/A	24,612
Subtotal Earthworks	169,556	381,950	0	0	551,506
Revegetation Costs	1,806	657	13,874	N/A	16,337
Evaporation/Evapotranspiration Cell Lining	0	0	0	0	0
Evaporation/Evapotranspiration Cell Piping	0	0	0	0	0
Subtotal Evaporation/Evapotranspiration Cells	0	0	0	0	0
TOTALS	171,362	382,607	13,874	0	567,843

Process Ponds - Assumptions & Calculations					
Revegetation Calculations					
Minimum 1 acre revegetation crew time per area					
Evaporation/Evapotranspiration					
Distribution header pipe assumed to be length of pond Area of additional geosynthetic layers assumed to be Minimum 1 acre revegetation crew time per area Minimum 1 acre revegetation crew time per area					

Process Ponds - Liner Removal Costs					
Description (required)	Crew Hours hrs	Total Labor Cost \$	Total Equipment Cost \$	Total Cover Cost \$	
1 EMP ponds	179	28,593	13,788	42,381	
2 Crusher fuel island fresh water pond	3	478	231	710	
3 Arequa external ponds	192	30,670	14,790	45,460	
	374	59,742	28,809	88,551	

Process Ponds - Backfill 1 Costs																							
Description (required)	Material Volumes			Haul to Crusher				Backfill Placement				Haul to Crusher				Crush		Compact		Haul to Placement		Total	
	Material Volume to Crusher cy	Final Material Volume (1,2) cy	Crusher Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity LCM/hr	Fleet Hours hrs	Placement Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity LCM/hr	Fleet Hours hrs	Labor Cost \$	Equipment Cost \$	Total Cost \$	Total Crush/Screen Cost \$	Labor Cost \$	Equipment Cost \$	Total Cost \$	Labor Cost \$	Equipment Cost \$	Total Cost \$	Total Cover Cost \$
1 EMP ponds	0	79,719						0	740C/988K/D8T	8.87	3	446	179	0	0	0	0	0	0	49,764	160,031	209,795	209,795
2 Crusher fuel island fresh water pond	0	1,257						0	740C/988K/D8T	8.87	3	446	3	0	0	0	0	0	0	834	2,682	3,516	3,516
3 Arequa external ponds	0	85,438						0	740C/988K/D8T	8.87	3	446	192	0	0	0	0	0	0	53,378	171,654	225,032	225,032
		166,414						0					374	0	0	0	0	0	0	103,976	334,367	438,343	438,343

Notes:
 1. If crushed or screened, Cover Volume = volume delivered to crusher - amount loss to crushing/screening)
 2. If pond backfilled by dozing berm into pond, backfill volume will be 50% of the backfill volume to account for cut-to-fit construction

Process Ponds - Backfill 2 Costs																							
Description (required)	Material Volumes			Haul to Crusher				Backfill Placement				Haul to Crusher				Crush		Compact		Haul to Placement		Total	
	Material Volume to Crusher cy	Final Material Volume (1,2) cy	Crusher Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity LCM/hr	Fleet Hours hrs	Placement Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity LCM/hr	Fleet Hours hrs	Labor Cost \$	Equipment Cost \$	Total Cost \$	Total Crush/Screen Cost \$	Labor Cost \$	Equipment Cost \$	Total Cost \$	Labor Cost \$	Equipment Cost \$	Total Cost \$	Total Cover Cost \$
1 EMP ponds	0	0						0					0	0	0	0	0	0	0	0	0	0	
2 Crusher fuel island fresh water pond	0	0						0					0	0	0	0	0	0	0	0	0	0	
3 Arequa external ponds	0	0						0					0	0	0	0	0	0	0	0	0	0	
		0						0					0	0	0	0	0	0	0	0	0	0	

Notes:
 1. If crushed or screened, Cover Volume = volume delivered to crusher - amount loss to crushing/screening)
 2. If pond backfilled by dozing berm into pond, backfill volume will be 50% of the backfill volume to account for cut-to-fit construction

Process Ponds - Growth Media Costs									
Growth Media Placement									
Description (required)	Final Material Volume cy	Placement Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity BCY/hr	hrs	Labor Cost \$	Equipment Cost \$	Total Cost \$
1 EMP ponds	4,572	740C/988K/D8T	8.87	3	446	10	2,780	8,940	11,720
2 Crusher fuel island fresh water pond	186	740C/988K/D8T	8.87	3	446	0	278	894	1,772
3 Arequa external ponds	4,572	740C/988K/D8T	8.87	3	446	10	2,780	8,940	11,720
	9,395					20	5,838	16,774	24,612

Process Ponds - Vegetation Costs									
Description (required)	Surface Area acres	Revegetation Labor Cost \$	Revegetation Equipment Cost \$	Revegetation Material Cost \$					

Closure Cost Estimate
Yards, Etc.

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Yards, Etc. - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Regrading Cost	0	0	N/A	0
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Growth Media Placement Cost	0	0	N/A	0
Ripping/Scarfing Cost	112,465	162,879	N/A	275,364
Subtotal Earthworks	112,465	162,879		275,364
Revegetation Cost	225,738	82,209	1,853,297	2,161,244
TOTALS	338,223	245,088	1,853,297	2,436,608

Yards, Etc. - User Input																				
Facility Description								Physical			Cover 1			Cover 2			Growth Media			
	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Area acres	Average Flat Area Long Dimension (ripping distance) ft	Regrade Volume (calculated elsewhere) cy	Cover Thickness in	Haul Distance to Placement Location (2) ft	Slope to Placement Location % grade	Cover Thickness in	Haul Distance to Placement Location (2) ft	Slope to Placement Location % grade	Growth Media Thickness in	Haul Distance to Placement ft	Slope to Placement Location % grade
1	Ancillary areas	2009	Facilities Demolition					ARO+LOM+FA	1431.00	4,000								6	2,000	-5.0
2	Growth Media piles	2009	Facilities Demolition					ARO+LOM+FA	118.80	200										

- Notes:
 1. All Physical parameters must be input even if manual overrides for volume or area are used.
 2. Input distance from crusher to placement location if material to be crushed, screened or compacted
 3. If Slope from facility to borrow source is >20, downhill travel time may be underestimated due to limitation of uphill travel time curves and downhill speed tables from CAT Handbook (see Productivity Sheet)

Yards, Etc. - User Input (Cont.)																			
Facility Description		Cover 1 - Crushing & Screening																	
	Description (required)	Crush Material (select)	Screen Material (select)	Loss to Crushing/ Screening %	Haul Distance to Crusher (1) ft	Slope from Cover Borrow % grade	Haul to Crusher Fleet (2) (select)	Compact After Placement? (select)	Cycle Time Override (user override)	Maximum Fleet Size (user override)	Crush Material (select)	Screen Material (select)	Loss to Crushing/ Screening %	Haul Distance to Crusher (1) ft	Slope from Cover Borrow % grade	Haul to Crusher Fleet (2) (select)	Compact After Placement? (select)	Cycle Time Override (user override)	Maximum Fleet Size (user override)
1	Ancillary areas																		
2	Growth Media piles																		

- Notes:
 1. Input distance to crusher if material to be crushed
 2. if distance from borrow >820 ft (250 m) must select loader fleet

Yards, Etc. - User Input (Cont.)																					
Grading		Cover 1			Cover 2			Growth Media			Revegetation										
	Description (required)	Dozing Material Condition (select)	Dozing Material Type (select)	Grading Equipment Fleet (select)	Material Type (select)	Placement Equipment Fleet (select)	Cycle Time Override (user override)	Maximum Fleet Size (user override)	Material Type (select)	Placement Equipment Fleet (select)	Cycle Time Override (user override)	Maximum Fleet Size (user override)	Material Type (select)	Placement Equipment Fleet (select)	Cycle Time Override (user override)	Maximum Fleet Size (user override)	Seed Mix (select)	Mulch (select)	Fertilizer (select)	Scarf/Rip? (select)	Ripping Fleet (select)
1	Ancillary areas	1	Granite - broken	Large													User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer
2	Growth Media piles																User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer

Notes:
 1. Material Types are used for density correction based on material densities in Caterpillar Performance Handbook material density table

Closure Cost Estimate
Yards, Etc.

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Yards, Etc. - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Regrading Cost	0	0	N/A	0
Cover 1 Placement Cost	0	0	N/A	0
Cover 2 Placement Cost	0	0	N/A	0
Growth Media Placement Cost	0	0	N/A	0
Ripping/Scarfing Cost	112,465	162,879	N/A	275,364
Subtotal Earthworks	112,465	162,879		275,364
Revegetation Cost	225,738	82,209	1,853,297	2,161,244
TOTALS	338,223	245,088	1,853,297	2,436,608

Yards, Etc. - Assumptions & Calculations	
Grading Calculations	
Average push distance assumed to be 2/3 of the 600 feet maximum from Caterpillar Handbook or 400 feet Material assumed to be loose stockpile (1.2 productivity factor) Slope assumed to be 0 to 5% (1.0 productivity factor)	
Cover Volume Calculation	
Yard area x cover thickness	
Ripping/Scarfing Calculations	
Flat area width = Final flat area + Average long dimensions Number of passes = Flat area width x Grader width Travel distance = Number of passes x Average long dimensions Total hours = (Travel distance + Grader productivity) + (Number of passes x Grader maneuver time) Minimum 1 hr ripping/scarfing per area	
Revegetation	
Minimum 1 acre revegetation crew time per area	

Yards, Etc. - Regrading Costs													
Productivity = Dozer Productivity x Grade Correction x Density Correction x Operator (0.75) x Material x Visibility x Job Efficiency (0.83) x (Slot/Side-by-Side)													
	Description (required)	Regrading Volume cy	Dozing Distance (see above) ft	Regrading Fleet	Uncorrected Dozer Productivity cy/hr	Grade Correction	Dozing Material	Density Correction	Total Hourly Productivity cy/hr	Total Dozer Hours hrs	Total Labor Cost \$	Total Equipment Cost \$	Total Regrading Cost \$
1	Ancillary areas			D10T2					0	0	0	0	0
2	Growth Media piles			Select Fleet					0	0	0	0	0
		0							0	0	0	0	0

Yards, Etc. - Cover 1 Costs																					
	Description (required)	Material Volume to Crusher cy	Final Material Volume cy	Crusher Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity LCM/hr	Fleet Hours hrs	Placement Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity LCM/hr	Fleet Hours hrs	Labor Cost \$	Equipment Cost \$	Total Cost \$	Total Crush/Screen Cost \$	Labor Cost \$	Equipment Cost \$	Total Cost \$	Total Cover Cost \$
1	Ancillary areas	0	0					0					0	0	0	0	0	0	0	0	
2	Growth Media piles	0	0					0					0	0	0	0	0	0	0	0	
		0	0					0					0	0	0	0	0	0	0	0	

Notes:
 1. If crushed or screened, Cover Volume = volume delivered to crusher - amount loss to crushing/screening)

Yards, Etc. - Cover 2 Costs																					
	Description (required)	Material Volume to Crusher cy	Final Material Volume cy	Crusher Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity LCM/hr	Fleet Hours hrs	Placement Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity LCM/hr	Fleet Hours hrs	Labor Cost \$	Equipment Cost \$	Total Cost \$	Total Crush/Screen Cost \$	Labor Cost \$	Equipment Cost \$	Total Cost \$	Total Cover Cost \$
1	Ancillary areas	0	0					0					0	0	0	0	0	0	0	0	
2	Growth Media piles	0	0					0					0	0	0	0	0	0	0	0	
		0	0					0					0	0	0	0	0	0	0	0	

Notes:
 1. If crushed or screened, Cover Volume = volume delivered to crusher - amount loss to crushing/screening)

Yards, Etc. - Growth Media Costs											
Growth Media Placement											
	Description (required)	Final Material Volume cy	Placement Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity BCY/hr	Fleet Hours hrs	Labor Cost \$	Equipment Cost \$	Total Cost \$	Total Crush/Screen Cost \$
1	Ancillary areas	1,154,340	Select Material	Select Material	Select Material	Select Material	0	0	0	0	0
2	Growth Media piles	0					0	0	0	0	0
		1,154,340					0	0	0	0	0

Yards, Etc. - Scarify/Revegetation Costs											
Scarifying Costs											
	Description (required)	Total Surface Area acres	Average Long Dimension (Ripping distance) ft	Ripping/Scarifying Fleet	Scarifying/Ripping Hours hrs	Scarifying Ripping Labor Costs \$	Scarifying Ripping Equipment Cost \$	Total Scarifying/Ripping Costs \$	Revegetation Labor Cost \$	Revegetation Equipment Cost \$	Total Vegetation Cost \$
1	Ancillary areas	1431.00	4,000	D7E	1,414	103,081	149,262	252,343	208,434	75,907	1,711,232
2	Growth Media piles	118.80	200	D7E	129	9,404	13,617	23,021	17,304	6,302	142,055
		1,549.80			1,543	112,485	162,879	275,364	225,738	82,209	1,853,297
											2,161,244

Notes: 1) Minimum total ripping hours = 1 (i.e. If total ripping hrs (slope + flat) < 1, then one hour of fleet time is assumed, regardless of acres shown in scarifying table.)
 2) Assumes 50 min/hr equipment availability

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: Site_E_2.0_FW_AM14.xlsm
 Model Version: Version 2.0
 Cost Data User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Closure Cost Estimate Haul Material

Generic Material Hauling - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Hauling/Crush/Screen/Compact	3,607,030	36,372,450	N/A	39,979,480
Cover Placement Cost	0	0	N/A	0
Total Placement Cost	0	0	N/A	0
Ripping/Scalping Cost	0	0	N/A	0
Subtotal Earthworks	3,607,030	36,372,450		39,979,480
Revegetation Cost	0	0	0	0
TOTALS	3,607,030	36,372,450	0	39,979,480

Generic Material Hauling - User Input

	Description (required)	Facility Description					Physical			Haul to Crusher			Crushing & Screening			Haul to Placement			Cover Thickness			Growth Media			
		ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Final Surface Area acres	Average Ripping Distance ft	Material Volume Required cu yd	Haul Distance to Crusher (1) mi	Slope to Crusher % grade	Crush Material	Screen Material	Loss to Crushing/Screening %	Haul Distance to Placement Location (2) mi	Slope to Placement Area % grade	Cover Thickness ft	Haul Distance to Placement Location mi	Slope to Placement % grade	Growth Media Thickness ft	Haul Distance to Placement Location mi	Slope to Placement % grade	
1 AGVL-F-9400	2009	Heap Leach Pads Reclamation						ARO+LOM+FA	340,405			4.374	8.2												
2 AGVL-F-9500	2009	Heap Leach Pads Reclamation						ARO+LOM+FA	437,763			3.782	5.8												
3 AGVL-F-9600	2009	Heap Leach Pads Reclamation						ARO+LOM+FA	669,112			2,074	3.9												
4 AGVL-F-9700	2009	Heap Leach Pads Reclamation						ARO+LOM+FA	924,035			1,500	-4.5												
5 AGVL-F-9800	2009	Heap Leach Pads Reclamation						ARO+LOM+FA	845,553			3,194	-7.5												
6 AGVL-F-9900	2009	Heap Leach Pads Reclamation						ARO+LOM+FA	291,740			4,981	-8.8												
7 AGVL-F-10000	2009	Heap Leach Pads Reclamation						ARO+LOM+FA	84,533			6,981	-8.6												
8 AGVL-F-9920	2009	Heap Leach Pads Reclamation						ARO+LOM+FA	6,599,307			4,606	5.2												
9 AGVL-F-10020	2009	Heap Leach Pads Reclamation						ARO+LOM+FA	4,040,912			4,269	2.3												
10 AGVL-F-10100	2009	Heap Leach Pads Reclamation						ARO+LOM+FA	3,131,171			1,170	-4.3												
11 AGVL-F-10190	2009	Heap Leach Pads Reclamation						ARO+LOM+FA	3,562,003			3,754	-6.6												
12 AGVL-F-10288	2009	Heap Leach Pads Reclamation						ARO+LOM+FA	3,477,782			6,052	-7.6												
13 Remove ROM	2009	Heap Leach Pads Reclamation						ARO+LOM+FA	1.68		12,587						1,126	2.0							
14 Remove DCF and Liner	2009	Heap Leach Pads Reclamation						ARO+LOM+FA	1.68		12,587						1,126	2.0							
15 Cresson underground portal backfill	2009	Portals / Adits Underground Mines						ARO+LOM+FA	0.00		0						9,300	10.0							

Notes:
 1. Input distance to crusher if material to be crushed
 2. Assumed to be 0% if material will be crushed and source is within 250 m of crusher
 3. If slope is >20, downhill travel time may be underestimated due to limitation of uphill travel time curves and downhill speed tables from CAT Handbook (see Productivity Sheet)

Generic Material Hauling - User Input (cont.)

	Description (required)	Hauling Material					Cover			Growth Media			Revegetation									
		Haul Material Type (select)	Crusher Fleet (select)	Cycle Time Override (user override)	Maximum Fleet Size (user override)	Placement Fleet	Cycle Time Override (user override)	Maximum Fleet Size (user override)	Compact After Placement? (select)	Material Type (select)	Placement Fleet (select)	Cycle Time Override (user override)	Maximum Fleet Size (user override)	Material Type (select)	Placement Fleet (select)	Cycle Time Override (user override)	Maximum Fleet Size (user override)	Seed Mix (select)	Mulch Type (select)	Fertilizer Type (select)	Scarf/Rip? (select)	Scarfing/Ripping Fleet (select)
1 AGVL-F-9400	Granite - broken	XLarge Truck				No																
2 AGVL-F-9500	Granite - broken	XLarge Truck				No																
3 AGVL-F-9600	Granite - broken	XLarge Truck				No																
4 AGVL-F-9700	Granite - broken	XLarge Truck				No																
5 AGVL-F-9800	Granite - broken	XLarge Truck				No																
6 AGVL-F-9900	Granite - broken	XLarge Truck				No																
7 AGVL-F-10000	Granite - broken	XLarge Truck				No																
8 AGVL-F-9920	Granite - broken	XLarge Truck				No																
9 AGVL-F-10020	Granite - broken	XLarge Truck				No																
10 AGVL-F-10100	Granite - broken	XLarge Truck				No																
11 AGVL-F-10190	Granite - broken	XLarge Truck				No																
12 AGVL-F-10288	Granite - broken	XLarge Truck				No																
13 Remove ROM		XLarge Truck				No																
14 Remove DCF and Liner		XLarge Truck				No																
15 Cresson underground portal backfill		Med Truck				No																

Notes: Final Material Volume includes allowance for additional material hauled to crushing/screening plant based on Loss to Crushing/Screening input above.

Generic Material Hauling - Load, Haul, Place and Grade

	Description (required)	Material Volumes			Haul to Crusher			Haul to Placement			Haul to Crusher			Crush			Compact			Haul to Placement			Total		
Material Volume to Crusher cy	Final Material Volume cy	Crusher Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity LCY/hr	Fleet Hours hrs	Placement Fleet	Cycle Time	Haul Fleet Size	Fleet Productivity	Fleet Hours	Labor Cost \$	Equipment Cost \$	Total Cost \$	Labor Cost \$	Equipment Cost \$	Total Cost \$	Labor Cost \$	Equipment Cost \$	Total Cost \$	Total Cover Cost \$				

<tbl_r cells="10" ix="1" maxcspan="3"

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SMC_E_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Closure Cost Estimate
Haul Material

Generic Material Hauling - ARO Cost Summary				
	Labor	Equipment	Materials	Totals
	\$	\$	\$	\$
Hauling/Crush/Screen/Compact	3,607.030	36,372.450	N/A	39,979.480
Cover Placement Cost	0	0	N/A	0
Topsoil Placement Cost	0	0	N/A	0
Ripping/Scalping Cost	0	0	N/A	0
Subtotal Earthworks	3,607.030	36,372.450		39,979.480
Revegetation Cost	0	0	0	0
TOTALS	3,607.030	36,372.450		39,979.480

14 Remove DCF and Liner	1.70	0	0	0	0	0	0	0	0
15 Cresson underground portal backfill	0.10	0	0	0	0	0	0	0	0

4.70

Closure Cost Estimate
Foundations & Buildings

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Buildings & Foundation Demolition - ARO Cost Summary				
	Labor	Equipment	Materials	Totals
Building Demolition Cost	2,786,359	2,227,722	N/A	5,014,081
Wall Demolition Cost	91,765	87,111	N/A	178,876
Slab Demolition	36,583	121,263	N/A	157,846
Subtotal Demolition	2,914,707	2,436,096	0	5,350,803
Cover Placement Cost	76,116	196,914	N/A	273,030
Growth Media Placement Cost		0	N/A	0
Ripping/Scarfing Cost	5,329	7,737	N/A	13,066
Subtotal Earthworks	81,446	204,651	0	286,096
Revegetation Cost	10,560	3,346	13,545	27,051
TOTALS	3,006,712	2,644,593	13,545	5,664,850

Buildings & Foundation - User Input

Description (required)	ID Code	Facility Description			Properties	Cost Type	Physical - MANDATORY					Building Area Footprint (including surrounding facilities) acres	Foundation Cover (1)		Growth Media (1) (entire footprint)		
		Construction Year	Facility/Activity Type	Phases			Length ft	Width ft	Eave Height ft	Slab Thickness in	Foundation Wall Thickness in	Foundation Wall Height ft	Haul Distance to Placement Location ft	Slope to Placement Location % grade	Growth Media Thickness in	Haul Distance to Placement Location ft	Slope to Placement Location % grade
1 Primary crushers		2009	Facilities Demolition		ARO+LOM+FA		78	48	112	12	6	1	78	0.00	60	8,300	5.0
2 Crane above pocket		2009	Facilities Demolition		ARO+LOM+FA		85	33	50	12	6	1	85	0.06	60	10,300	3.0
3 Secondary crusher MCC		2009	Facilities Demolition		ARO+LOM+FA		53	21	15	12	6	1	53	0.03	60	10,300	3.0
4 Secondary crushers		2009	Facilities Demolition		ARO+LOM+FA		120	67	107	12	6	1	120	0.18	60	10,300	3.0
5 Screen Bldg		2009	Facilities Demolition		ARO+LOM+FA		72	32	86	12	6	1	72	0.05	60	10,300	3.0
6 Screen MCCs		2009	Facilities Demolition		ARO+LOM+FA		40	18	15	12	6	1	40	0.02	60	5,100	3.0
7 Crusher Maint		2009	Facilities Demolition		ARO+LOM+FA		40	40	17	12	6	1	40	0.04	60	5,100	3.0
8 Sec pump		2009	Facilities Demolition		ARO+LOM+FA		65	40	10	12	6	1	65	0.06	60	5,100	3.0
9 MCC for phase II pumps		2009	Facilities Demolition		ARO+LOM+FA		21	11	12	12	6	1	21	0.01	60	5,100	3.0
10 Laboratory		2009	Facilities Demolition		ARO+LOM+FA		150	69	52	12	6	1	150	0.24	60	5,100	3.0
11 Project mcr trailer		2009	Facilities Demolition		ARO+LOM+FA		57	12	10	6			57	0.02	60	20,000	6.0
12 Project trailer		2009	Facilities Demolition		ARO+LOM+FA		40	53	10	6			53	0.05	60	11,400	1.0
13 Fire trailer		2009	Facilities Demolition		ARO+LOM+FA		20	10	10	6			20	0.00	60	10,300	3.0
14 Process maint trailer		2009	Facilities Demolition		ARO+LOM+FA		60	25	10	6			60	0.03	60	10,300	3.0
15 Crusher Maint addition		2009	Facilities Demolition		ARO+LOM+FA		25	40	17	12	6	1	40	0.02	60	10,300	3.0
16 Crusher Maint lean to		2009	Facilities Demolition		ARO+LOM+FA		10	40	13	12	6	1	40	0.01	60	10,300	3.0
17 AGADR 995		2009	Facilities Demolition		ARO+LOM+FA		165	100	52	12	8	3	165	0.38	60	10,300	3.0
18 Pipe access gallery		2009	Facilities Demolition		ARO+LOM+FA		60	10	10	12	8	3	60	0.01	60	10,300	3.0
19 carbon strip & regen		2009	Facilities Demolition		ARO+LOM+FA		107	25	45	12	8	3	107	0.06	60	10,300	3.0
20 Process maint trailer		2009	Facilities Demolition		ARO+LOM+FA		60	25	12	6			60	0.03	60	10,300	3.0
21 AGADR north		2009	Facilities Demolition		ARO+LOM+FA		165	43	44	12	8	3	165	0.16	60	10,300	3.0
22 AGADR south		2009	Facilities Demolition		ARO+LOM+FA		108	70	57	12	8	3	108	0.17	60	10,300	3.0
23 Etrain		2009	Facilities Demolition		ARO+LOM+FA		142	42	53	12	8	3	142	0.14	60	10,300	3.0
24 MCC fume scrubber		2009	Facilities Demolition		ARO+LOM+FA		37	16	16	12	8	3	37	0.01	60	10,300	3.0
25 enrichment pump station		2009	Facilities Demolition		ARO+LOM+FA		60	30	38	12	8	3	60	0.04	60	5,100	3.0
26 Ph V Preg pump MCC		2009	Facilities Demolition		ARO+LOM+FA		22	22	17	12	8	3	22	0.01	60	5,100	3.0
27 Ph V Preg enrich MCC		2009	Facilities Demolition		ARO+LOM+FA		42	22	17	12	8	3	42	0.02	60	5,100	3.0
28 Ph V Preg enrich LVSC		2009	Facilities Demolition		ARO+LOM+FA		20	10	12	12	8	3	20	0.00	60	5,100	3.0
29 Victor maint light vehicle shop		2009	Facilities Demolition		ARO+LOM+FA		80	56	12	12	6	1	80	0.10	60	5,100	3.0
30 truck wash		2009	Facilities Demolition		ARO+LOM+FA		75	45	41	12	6	1	75	0.08	60	8,300	5.0
31 truck shop		2009	Facilities Demolition		ARO+LOM+FA		305	95	65	12	6	1	305	0.67	60	5,100	3.0
32 Mill maint warehouse		2009	Facilities Demolition		ARO+LOM+FA		57	200	47	12	6	1	200	0.26	60	5,100	3.0
33 pump house		2009	Facilities Demolition		ARO+LOM+FA		16	15	13	12	6	3	16	0.11	60	3,300	5.0
34 conveyor shed		2009	Facilities Demolition		ARO+LOM+FA		85	13	21	12	6	1	85	0.03	60	3,300	5.0
35 process corridor		2009	Facilities Demolition		ARO+LOM+FA		15	175	24	12	6	3	175	0.06	60	3,300	5.0
36 Buckley main bldg		2009	Facilities Demolition		ARO+LOM+FA		60	40	12	12	6	1	60	0.06	60	3,300	5.0
37 AGVLE & AGADR		2009	Facilities Demolition		ARO+LOM+FA		142	42	53	12	8	3	142	0.14	60	3,300	5.0
38 MCC & fume scrubber		2009	Facilities Demolition		ARO+LOM+FA		37	16	16	12	8	3	37	0.01	60	5,100	3.0
39 VL F2 enrichment pump station		2021	Facilities Demolition		ARO+LOM+FA		60	54	20	12	8	3	60	0.04	60	10,300	3.0
40 VL F2 enrichment pump station		2012	Facilities Demolition		ARO+LOM+FA		15	59	8	12	8	3	60	0.04	60	10,300	3.0
41 Ph V Preg pump MCC		2009	Facilities Demolition	</td													

Closure Cost Estimate
Foundations & Buildings

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Buildings & Foundation Demolition - ARO Cost Summary				
	Labor	Equipment	Materials	Totals
Building Demolition Cost	2,786,359	2,227,722	N/A	5,014,081
Wall Demolition Cost	91,765	87,111	N/A	178,876
Slab Demolition	36,583	121,263	N/A	157,846
Subtotal Demolition	2,914,707	2,436,096	0	5,360,803
Cover Placement Cost	76,116	196,914	N/A	273,030
Growth Media Placement Cost	5,329	7,737	N/A	13,066
Ripping/Scarfing Cost				
Subtotal Earthworks	81,445	204,651	0	286,086
Revegetation Cost	10,560	3,846	13,545	27,951
TOTALS	3,006,712	2,644,593	13,545	5,664,850

Closure Cost Estimate
Foundations & Buildings

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Buildings & Foundation Demolition - ARO Cost Summary				
	Labor	Equipment	Materials	Totals
Building Demolition Cost	2,786,359	2,227,722	N/A	5,014,081
Wall Demolition Cost	91,765	87,111	N/A	178,876
Slab Demolition	36,583	121,263	N/A	157,846
Subtotal Demolition	2,914,707	2,436,096	0	5,350,803
Cover Placement Cost	76,116	196,914	N/A	273,030
Growth Media Placement Cost		0	N/A	0
Ripping/Scarfing Cost	5,329	7,737	N/A	13,066
Subtotal Earthworks	81,446	204,651	0	286,096
Revegetation Cost	10,560	3,346	13,545	27,051
TOTALS	3,006,712	2,644,593	13,545	5,864,850

Buildings & Foundation - User Input (cont.)																	
	Construction Materials		Slab Demolition		Foundation Cover			Growth Media			Revegetation						
	Description (required)	Building Type (select)	Foundation Wall Type (select)	Slab Demo Method (select)	Slab Breaking Equipment Fleet (select)	Cover Material Type (select)	Cover Placement Equipment Fleet (select)	Cycle Time Override (user override)	Maximum Fleet Size (user override)	Growth Media Material Type (select)	Growth Media Placement Equipment Fleet (select)	Cycle Time Override (user override)	Maximum Fleet Size (user override)	Seed Mix (select)	Mulch (select)	Fertilizer (select)	Scarf/ Rip? (select)
1 Primary crushers	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
2 Crane above pocket	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
3 Secondary crusher MCC	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
4 Secondary crushers	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
5 Screen Bldg	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
6 Screen MCCs	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
7 Crusher Maint	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
8 Security	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
9 MCC for phase II pumps	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
10 Lab	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
11 Insulated mgt trailer	Sm. wood			Break & bury	Med Excavator	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
12 Project trailer	Sm. wood			Break & bury	Med Excavator	Alluvium	Small Truck			User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
13 Fire trailer	Sm. wood			Break & bury	Med Excavator	Alluvium	Small Truck			User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
14 Process maint trailer	Sm. wood			Break & bury	Med Excavator	Alluvium	Small Truck			User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
15 Crusher Maint addition	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
16 Crusher Maint lean to	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
17 AGADR 1995	Lg. steel	Conc 8 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
18 Pipe access gallery	Lg. steel	Conc 8 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
19 carbon strip & regen	Lg. steel	Conc 8 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
20 Process maint trailer	Sm. wood			Break & bury	Med Excavator	Alluvium	Small Truck			User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
21 AGADR north	Lg. steel	Conc 8 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
22 AGADR south	Lg. steel	Conc 8 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
23 Etrain	Lg. steel	Conc 8 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
24 MCC fume scrubber	Lg. steel	Conc 8 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
25 enrichment pump station	Lg. steel	Conc 8 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
26 Ph V Preg pump MCC	Lg. steel	Conc 8 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
27 Ph V Preg enrich MCC	Lg. steel	Conc 8 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
28 Ph V Preg enrich LVSC	Lg. steel	Conc 8 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
29 Victor maint light vehicle shop	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
30 truck wash	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
31 truck shop	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
32 Mill maint warehouse	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
33 sump pump	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
34 conveyor shed	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
35 incercator corridor	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
36 Buckley main bldg	Lg. steel	Conc 6 in (150 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
37 AGVL & AGDR	Lg. steel	Conc 6 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
38 MCC & fume scrubber	Lg. steel	Conc 6 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
39 VLFe enrichment pump station	Lg. steel	Conc 8 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
40 VLFe enrichment pump station	Lg. steel	Conc 8 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
41 Ph V Preg pump MCC	Lg. steel	Conc 8 in (200 mm) thick	Break & bury	Med Excavator	Alluvium	Small Truck				User Mix 1	Hydro Mulch	Chemical	Yes	Small Dozer			
42 Ph V Preg enrich MCC	Lg. steel	Conc 8 in (200 mm) thick	Break & bury	Med Excavator	Alluvium												

Closure Cost Estimate
Foundations & Buildings

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Buildings & Foundation Demolition - ARO Cost Summary				
	Labor	Equipment	Materials	Totals
Building Demolition Cost	2,786,359	2,227,722	N/A	5,014,081
Wall Demolition Cost	91,765	87,111	N/A	178,876
Slab Demolition	36,583	121,263	N/A	157,846
Subtotal Demolition	2,914,707	2,436,096	0	5,360,803
Cover Placement Cost	76,116	196,914	N/A	273,030
Growth Media Placement Cost			0	N/A
Ripping/Scarfing Cost	5,329	7,737	N/A	13,066
Subtotal Earthworks	81,445	204,651	0	286,086
Revegetation Cost	10,560	3,346	13,545	27,051
TOTALS	3,006,712	2,644,593	13,545	5,664,850

Foundations & Buildings - Assumptions & Calculations

Building Volume Calculations

Using Means Heavy Construction Cost Data (2004) calculates cubic feet from building dimensions
 Estimates slab thickness and wall thickness if not known
 Assumes that all concrete slabs are reinforced
 Productivity for crew from Means Heavy Construction Cost Data (2004) adjusted for supervision
 (addressed in Misc. Costs) and Davis-Bacon Wage Rates
 Demolition costs do not include hauling or disposing of debris - Use Waste Disposal module

Slab Demolition Calculations

Minimum 1 hr excavator time for slab demolition

Cover Volume Calculation

Foundation area x cover thickness
 If "Buy in Place" is selected as slab demolition method, cover thickness is adjusted such that
 total cover (cover + growth media) equals value entered in "Minimum thickness of cover over unbroken slab" cell above

Ripping/Scarfing Calculations

Flat area width = Final flat area - Average long dimensions
 Number of passes = Flat area width / Grader width
 Travel distance = Number of passes x Average long dimensions
 Total hours = (Travel distance / Grader productivity) + (Number of passes x Grader maneuver time)

Revegetation

Minimum 1 acre revegetation crew time per area

Closure Cost Estimate
Foundations & Buildings

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsx

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx

Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Buildings & Foundation Demolition - ARO Cost Summary

	Labor	Equipment	Materials	Totals
Building Demolition Cost	2,786,359	2,227,722	N/A	5,014,081
Wall Demolition Cost	91,765	87,111	N/A	178,876
Slab Demolition	36,583	121,263	N/A	157,846
Subtotal Demolition	2,914,707	2,436,096	0	5,350,803
Cover Placement Cost	76,116	196,914	N/A	273,030
Growth Media Placement Cost	0	0	N/A	0
Ripping/Scarfing Cost	5,329	7,737	N/A	13,066
Subtotal Earthworks	81,446	204,651	0	286,696
Revegetation Cost	10,560	3,346	13,545	27,051
TOTALS	3,006,712	2,644,593	13,545	5,664,850

Building & Foundation Demolition Costs

Uses RS Means Heavy Construction Cost Data for building and wall demolition cost calculations. Uses CAT Handbook for slab breaking production.																						
	Description (required)	Building Footprint (slab area) sqft	Building Volume cu ft	Building Demolition Fleet	Building Demolition Hours	Wall Length ft	Wall Area sq ft	Wall Demolition Hours hrs	Slab Demolition Fleet	Slab Demolition Hours hrs	Total Labor Cost \$	Total Equipment Cost \$	Total Building Demolition Cost \$	Total Labor Cost \$	Total Equipment Cost \$	Total Wall Demolition Cost \$	Total Labor Cost \$	Total Equipment Cost \$	Total Slab Breaking Cost \$	Total Labor Cost \$	Total Equipment Cost \$	Total Demolition Costs \$
																	Building Demolition			Wall Demolition		
1 Primary crushers	3,744	419,328	930M/20 Ton Crane/Dump	156	252	13	139	349F	2	62,899	50,319	113,216	592	564	1,156	294	974	1,268	63,785	51,857	115,642	
2 Crane above pocket	2,805	140,250	930M/20 Ton Crane/Dump	52	236	12	104	349F	2	21,038	16,830	37,868	555	529	1,084	294	974	1,268	21,887	18,333	40,220	
3 Secondary crusher MCC	1,113	16,695	930M/20 Ton Crane/Dump	6	148	7	41	349F	1	2,504	2,003	4,507	348	332	680	147	487	634	2,999	2,822	5,821	
4 Secondary crushers	8,040	860,280	930M/20 Ton Crane/Dump	320	374	19	298	349F	5	129,042	103,234	232,276	879	838	1,717	734	2,435	3,169	130,655	106,507	237,162	
5 Screen Bldg	2,304	198,144	930M/20 Ton Crane/Dump	74	208	10	85	349F	1	29,722	23,777	53,499	469	466	955	147	487	634	30,358	24,730	55,088	
6 Screen MCCs	720	10,800	930M/20 Ton Crane/Dump	4	116	6	27	349F	1	1,620	1,296	2,916	273	260	533	147	487	634	2,040	2,043	4,083	
7 Crusher Maint	1,600	27,200	930M/20 Ton Crane/Dump	10	160	8	59	349F	1	4,080	3,264	7,344	376	358	734	147	487	634	4,603	4,109	8,712	
8 Security	2,600	26,000	930M/20 Ton Crane/Dump	10	210	11	96	349F	2	3,900	3,000	6,900	494	470	964	294	974	1,268	4,688	4,564	9,252	
9 MCC for phase II pumps	234	2,712	930M/20 Ton Crane/Dump	1	64	3	9	349F	1	1,160	930	1,745	150	143	293	147	487	634	1,713	963	1,676	
10 Lathe main	10,150	530,200	930M/20 Ton Crane/Dump	200	438	22	303	349F	6	80,720	64,824	145,244	1,023	981	2,010	681	2,022	634	82,465	68,000	151,027	
11 Impact mag trailer	684	6,940	930M/Dump Truck (10-12')	4	138	0	13	349F	1	1,231	899	2,120	0	0	0	147	487	634	1,378	1,376	2,754	
12 Project trailer	2,120	21,200	930M/Dump Truck (10-12')	11	186	0	0	349F	1	3,816	2,758	6,572	0	0	0	147	487	634	3,963	3,243	7,208	
13 Fire trailer	200	2,000	930M/Dump Truck (10-12')	1	60	0	0	349F	1	360	260	620	0	0	0	147	487	634	507	747	1,254	
14 Process maint trailer	1,500	15,000	930M/Dump Truck (10-12')	8	170	0	0	349F	1	2,700	1,950	4,650	0	0	0	147	487	634	2,847	2,437	5,284	
15 Crusher Maint addition	1,000	17,000	930M/20 Ton Crane/Dump	6	130	7	37	349F	1	2,550	2,040	4,590	306	291	597	147	487	634	3,003	2,818	5,821	
16 Crusher Maint Jean to	400	5,200	930M/20 Ton Crane/Dump	2	100	5	15	349F	1	780	624	1,404	235	224	459	147	487	634	1,162	1,335	2,497	
17 AGADR 1995	16,500	858,000	930M/20 Ton Crane/Dump	319	530	91	611	349F	10	128,700	102,660	231,660	4,293	4,070	8,363	1,469	4,870	634	6,339	134,462	111,900	246,362
18 Pipe access gallery	600	6,000	930M/20 Ton Crane/Dump	2	140	24	22	349F	1	900	720	1,620	1,134	1,075	2,209	147	487	634	2,181	2,282	4,463	
19 carbon strip & regen	2,675	120,375	930M/20 Ton Crane/Dump	45	264	792	45	349F	2	18,056	14,445	32,501	2,138	2,028	4,166	294	974	1,268	20,488	17,447	37,935	
20 Process maint trailer	1,500	18,000	930M/Dump Truck (10-12')	10	170	0	0	349F	1	3,240	2,340	5,580	0	0	0	147	487	634	3,387	2,827	6,214	
21 AGADR north	7,095	312,180	930M/20 Ton Crane/Dump	116	416	1,248	71	263	349F	4	46,827	37,462	84,289	3,370	3,195	6,565	588	1,948	2,536	50,785	42,605	93,390
22 AGADR south	7,560	430,920	930M/20 Ton Crane/Dump	160	356	61	280	349F	5	64,638	51,710	116,348	2,884	2,734	5,618	734	2,435	3,169	58,879	52,593	125,135	
23 Etrain	5,964	316,092																				

Closure Cost Estimate
Foundations & Buildings

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsx

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx

Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Buildings & Foundation Demolition - ARO Cost Summary

	Labor \$	Equipment \$	Materials \$	Totals \$
Building Demolition Cost	2,786,359	2,227,722	N/A	5,014,081
Wall Demolition Cost	91,765	87,111	N/A	178,876
Slab Demolition	36,583	121,263	N/A	157,846
Subtotal Demolition	2,914,707	2,436,096	0	5,350,803
Cover Placement Cost	76,116	196,914	N/A	273,030
Growth Media Placement Cost	0	0	N/A	0
Ripping/Scarfing Cost	5,329	7,737	N/A	13,066
Subtotal Earthworks	81,446	204,651	0	286,096
Revegetation Cost	10,560	3,346	13,545	27,051
TOTALS	3,006,712	2,644,593	13,545	5,864,850

Building & Foundation - Foundation Cover and Growth Media Costs

Description (required)	Material Volume cy	Foundation Cover						Growth Media						Total Cover & Growth Media Costs						
		Placement Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity LCY/hr	Total Fleet Hours hrs	Total Labor Cost \$	Total Equipment Cost \$	Total Cover Cost \$	Material Volume cy	Placement Fleet	Cycle Time min	Haul Fleet Size	Fleet Productivity LCY/hr	Total Fleet Hours hrs	Total Labor Cost \$	Total Equipment Cost \$	Total Cost \$	Total Labor Cost \$	Total Equipment Cost \$
1 Primary crushers	693	725C2/966MD7E	12.68	6	398	2	818	2,134	2,952						0	0	0	818	2,134	2,952
2 Crane above pocket	519	725C2/966MD7E	14.49	7	407	1	453	1,209	1,662						0	0	0	453	1,209	1,662
3 Secondary crusher MCC	206	725C2/966MD7E	14.49	7	407	1	453	1,209	1,662						0	0	0	453	1,209	1,662
4 Secondary crushers	1,489	725C2/966MD7E	14.49	7	407	4	1,811	4,837	6,648						0	0	0	1,811	4,837	6,648
5 Screen Bldg	427	725C2/966MD7E	14.49	7	407	1	453	1,209	1,662						0	0	0	453	1,209	1,662
6 Screen MCCs	133	725C2/966MD7E	9.05	4	375	1	322	783	1,105						0	0	0	322	783	1,105
7 Crusher Maint	296	725C2/966MD7E	9.05	4	375	1	322	783	1,105						0	0	0	322	783	1,105
8 Security	481	725C2/966MD7E	9.05	4	375	1	322	783	1,105						0	0	0	322	783	1,105
9 MCC for phase II pumps	43	725C2/966MD7E	9.05	4	375	1	322	783	1,105						0	0	0	322	783	1,105
10 Lab maint trailer	137	725C2/966MD7E	9.05	4	375	5	1,662	3,913	5,522						0	0	0	1,662	3,913	5,522
11 Inlined mag trailer	127	725C2/966MD7E	28.95	14	442	1	759	2,205	2,964						0	0	0	759	2,205	2,964
12 Project trailer	393	725C2/966MD7E	15.65	8	432	1	407	1,352	1,849						0	0	0	407	1,352	1,849
13 Fire trailer	37	725C2/966MD7E	14.49	7	407	1	453	1,209	1,662						0	0	0	453	1,209	1,662
14 Process maint trailer	278	725C2/966MD7E	14.49	7	407	1	453	1,209	1,662						0	0	0	453	1,209	1,662
15 Crusher Maint addition	185	725C2/966MD7E	14.49	7	407	1	453	1,209	1,662						0	0	0	453	1,209	1,662
16 Crusher Maint Jean to	74	725C2/966MD7E	14.49	7	407	1	453	1,209	1,662						0	0	0	453	1,209	1,662
17 AGADR 1995	3,056	725C2/966MD7E	14.49	7	407	8	3,623	9,674	13,297						0	0	0	3,623	9,674	13,297
18 Pipe access gallery	111	725C2/966MD7E	14.49	7	407	1	453	1,209	1,662						0	0	0	453	1,209	1,662
19 carbon strip & regen	495	725C2/966MD7E	14.49	7	407	1	453	1,209	1,662						0	0	0	453	1,209	1,662
20 Process maint trailer	278	725C2/966MD7E	14.49	7	407	1	453	1,209	1,662						0	0	0	453	1,209	1,662
21 AGADR north	1,314	725C2/966MD7E	14.49	7	407	3	1,359	3,628	4,987						0	0	0	1,359	3,628	4,987
22 AGADR south	1,400	725C2/966MD7E	14.49	7	407	3	1,359	3,628	4,987						0	0	0	1,359	3,628	4,987
23 Etrain	1,104	725C2/966MD7E	14.49	7	407	3	1,359	3,628	4,987						0	0	0	1,359	3,628	4,987
24 MCC fume scrubber	110	725C2/966MD7E	14.49	7	407	1	453	1,209	1,662						0	0	0	453	1,209	1,662
25 enrichment pump station	333	725C2/966MD7E	9.05	4	375	1	322	783	1,105						0	0	0	322	783	1,105
26 Ph V Pregr pump MCC	90	725C2/966MD7E	9.05	4	375	1	322	783	1,105						0	0	0	322	783	1,105
27 Ph V Pregr enrich MCC	171	725C2/966MD7E	9.05	4	375	1	322	783	1,105						0	0	0	322	783	1,105
28 Ph V Pregr enrich LVSC	37	725C2/966MD7E	9.05	4	375	1	322	783	1,105						0	0	0	322	783	1,105
29 Victor maint light vehicle shop	830	725C2/966MD7E	9.05	4	375	2	643	1,565	2,208						0	0	0	643	1,565	2,208
30 truck wash	625	725C2/966MD7E	12.68	6	398	2	818	2,134	2,952						0	0	0	818	2,134	2,952
31 truck shop	5,366	725C2/966MD7E	9.05	4	375	14	4,504	10,957	15,461						0	0	0	4,504	10,957	15,461
32 Mill maint warehouse	2,111	725C2/966MD7E	9.05	4	375	6	1,930	4,696	6,626						0	0	0	1,930	4,696	6,626
33 sump pump	44	725C2/966MD7E	12.68	6	398	1	409	1,061	1,476						0	0	0	409	1,061	1,476
34 conveyor shed	205	725C2/966MD7E	12.68	6	398	1	409	1,061	1,476			</								

Closure Cost Estimate
Foundations & Buildings

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Buildings & Foundation Demolition - ARO Cost Summary				
	Labor	Equipment	Materials	Totals
Building Demolition Cost	2,786,359	2,227,722	N/A	5,014,081
Wall Demolition Cost	91,765	87,111	N/A	178,876
Slab Demolition	36,583	121,263	N/A	157,846
Subtotal Demolition	2,914,707	2,436,096	0	5,350,803
Cover Placement Cost	76,116	196,914	N/A	273,030
Growth Media Placement Cost	0	0	N/A	0
Ripping/Scarifying Cost	5,329	7,737	N/A	13,066
Subtotal Earthworks	81,446	204,651	0	286,096
Revegetation Cost	10,560	3,346	13,545	27,051
TOTALS	3,006,712	2,644,593	13,545	5,664,850

Building & Foundation - Scarifying/Revegetation Costs

	Description (required)	Flat Area acres	Average Long Dimension (ripping distance ft)	Scarifying/Ripping			Revegetation			Total Scarify & Revegetation Costs					
				Ripping/ Scarifying Fleet	Scarifying/ Ripping Hours hrs	Scarifying/ Ripping Labor Costs \$	Total Scarifying/ Ripping Equipment Cost \$	Revegetation Labor Cost \$	Revegetation Equipment Cost \$	Revegetation Material Cost \$	Total Revegetation Cost \$	Total Labor Cost \$	Total Equipment Cost \$	Total Material Cost \$	
1 Primary crushers	0.10	78	D7E	1	73	106	179	146	53	120	319	219	159	120	498
2 Crane above pocket	0.10	85	D7E	1	73	106	179	146	53	120	319	219	159	120	498
3 Secondary crusher MCC	0.10	53	D7E	1	73	106	179	146	53	120	319	219	159	120	498
4 Secondary crushers	0.20	120	D7E	1	73	106	179	146	53	240	439	219	159	240	618
5 Screen Bldg	0.10	72	D7E	1	73	106	179	146	53	120	319	219	159	120	498
6 Screen MCCs	0.10	40	D7E	1	73	106	179	146	53	120	319	219	159	120	498
7 Crusher Maint	0.10	40	D7E	1	73	106	179	146	53	120	319	219	159	120	498
8 Security	0.10	65	D7E	1	73	106	179	146	53	120	319	219	159	120	498
9 MCC for phase II pumps	0.10	21	D7E	1	73	106	179	146	53	120	319	219	159	120	498
10 Lathe main trailer	0.20	150	D7E	1	73	106	179	146	53	240	439	219	159	240	618
11 Impact mgt trailer	0.10	57	D7E	1	73	106	179	146	53	120	319	219	159	120	498
12 Project trailer	0.10	53	D7E	1	73	106	179	146	53	120	319	219	159	120	498
13 Fire trailer	0.10	20	D7E	1	73	106	179	146	53	120	319	219	159	120	498
14 Process maint trailer	0.10	60	D7E	1	73	106	179	146	53	120	319	219	159	120	498
15 Crusher Maint addition	0.10	40	D7E	1	73	106	179	146	53	120	319	219	159	120	498
16 Crusher Maint lean to	0.10	40	D7E	1	73	106	179	146	53	120	319	219	159	120	498
17 AGADR 1995	0.40	165	D7E	1	73	106	179	146	53	478	677	219	159	478	856
18 Pipe access gallery	0.10	60	D7E	1	73	106	179	146	53	120	319	219	159	120	498
19 carbon strip & regen	0.10	107	D7E	1	73	106	179	146	53	120	319	219	159	120	498
20 Process maint trailer	0.10	60	D7E	1	73	106	179	146	53	120	319	219	159	120	498
21 AGADR north	0.20	165	D7E	1	73	106	179	146	53	240	439	219	159	240	618
22 AGADR south	0.20	108	D7E	1	73	106	179	146	53	240	439	219	159	240	618
23 Etrain	0.10	142	D7E	1	73	106	179	146	53	120	319	219	159	120	498
24 MCC fume scrubber	0.10	37	D7E	1	73	106	179	146	53	120	319	219	159	120	498
25 enrichment pump station	0.10	60	D7E	1	73	106	179	146	53	120	319	219	159	120	498
26 Ph V Pregr pump MCC	0.10	22	D7E	1	73	106	179	146	53	120	319	219	159	120	498
27 Ph V Pregr enrich MCC	0.10	42	D7E	1	73	106	179	146	53	120	319	219	159	120	498
28 Ph V Pregr enrich LVSC	0.10	20	D7E	1	73	106	179	146	53	120	319	219	159	120	498
29 Victor maint light vehicle shop	0.10	80	D7E	1	73	106	179	146	53	120	319	219	159	120	498
30 truck wash	0.10	75	D7E	1	73	106	179	146	53	120	319	219	159	120	498
31 truck shop	0.70	305	D7E	1	73	106	179	146	53	837	1,036	219	159	837	1,215
32 Mill maint warehouse	0.30	200	D7E	1	73	106	179	146	53	359	558	219	159	359	737
33 sump pump	0.10	16	D7E	1	73	106	179	146	53	120	319	219	159	120	498
34 conveyor shed	0.10	85	D7E	1	73	106	179	146	53	120	319	219	159	120	498
35 incoming corridor	0.10	175	D7E	1	73	106	179	146	53	120	319	219	159	120	498
36 Buckley main bldg	0.10	60	D7E	1	73	106	179	146	53	120	319	219	159	120	498
37 AGVL & AGDR	0.10	142	D7E	1	73	106	179	146	53	120	319	219	159	120	498
38 MCC & fume scrubber	0.10	37	D7E	1	73	106	179	146	53	120	319	219	159	120	498
39 VLFe2 enrichment pump station	0.10	60	D7E	1	73	106	179	146	53	120	319	219	159	120	498
40 VLFe2 enrichment pump station	0.10	60	D7E	1	73	106	179	146	53	120	319	219	159	120	498
41 Ph V Pregr pump MCC	0.10	22	D7E	1	73	106	179	146	53	120	319	219	159	120	498
42 Ph V Pregr enrich MCC	0.10	42	D7E	1	73	106	179	146	53	120	319	219	159	120	498
43 Ph V Pregr enrich LVSC	0.10	20	D7E	1	73	106	179	146	53	120	319	219	159	120	498
44 Squaw MCC	0.10	60	D7E	1	73	106	179	146	53	120	319	219	159</td		

Closure Cost Estimate
Other Demo & Equip Removal

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsx

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx

Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Other Demolition and Equipment Removal - ARO Cost Summary

	Labor \$	Equipment \$	Materials \$	Totals \$
Other Demolition	74,097	35,720	0	109,818
Equipment Removal	3,490	2,792	113,506	119,787
TOTALS	77,587	38,512	113,506	229,605

Other Demolition

	Facility Description																
	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Quantity	Units	Labor Unit Cost \$	Equipment Unit Cost \$	Material Unit Cost \$	Total Labor Cost \$	Total Equipment Cost \$	Total Material Cost \$	Total Cost \$
1	mill conveyor demolition		2009	Facilities Demolition				ARO+LOM+FA	1250	ft	\$8.90	0.00	0.00	11,124	0	0	11,124
2	Septic systems		2009	Facilities Demolition				ARO+LOM+FA	12	ea	\$5,146.91	2,976.70	0.00	61,763	35,720	0	97,483
3	ROM Conveyor		2009	Facilities Demolition				ARO+LOM+FA	136	ft	\$8.90	0.00	0.00	1,210	0	0	1,210
														74,097	35,720	0	109,818

Notes:

Equipment & Material Removal

	Facility Description																
	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Quantity	Units	Labor Unit Cost \$	Equipment Unit Cost \$	Material Unit Cost \$	Total Labor Cost \$	Total Equipment Cost \$	Total Material Cost \$	Total Cost \$
1	Lump sum from 2014 "11-Demolition", includes tanks & piping & contamination		2009	Facilities Demolition				ARO+LOM+FA	1	unit				113,506.00	0	0	113,506
2	10 Carbon columns		2009	Facilities Demolition				ARO+LOM+FA	13499	C.F.	\$0.16	0.13		2,187	1,749	0	3,936
3	intermediate		2009	Facilities Demolition				ARO+LOM+FA	8042	C.F.	\$0.16	0.13		1,303	1,042	0	2,345
4	2 1999 solution tanks		2009	Facilities Demolition				ARO+LOM+FA	7660	C.F.	\$0.16	0.13		1,241	993	0	2,234
5	5 1999 carbon columns		2009	Facilities Demolition				ARO+LOM+FA	6749	C.F.	\$0.16	0.13		1,093	875	0	1,968
6	kiln		2009	Facilities Demolition				ARO+LOM+FA	290	C.F.	\$0.16	0.13		47	38	0	85
7	carbon feed		2009	Facilities Demolition				ARO+LOM+FA	1256	C.F.	\$0.16	0.13		203	163	0	366
8	carbon quench		2009	Facilities Demolition				ARO+LOM+FA	706	C.F.	\$0.16	0.13		114	91	0	206
9	carbon strip		2009	Facilities Demolition				ARO+LOM+FA	604	C.F.	\$0.16	0.13		98	78	0	176
10	2 cyanide mix		2009	Facilities Demolition				ARO+LOM+FA	6627	C.F.	\$0.16	0.13		1,074	859	0	1,932
11	5 train D carbon columns		2009	Facilities Demolition				ARO+LOM+FA	7798	C.F.	\$0.16	0.13		1,263	1,011	0	2,274
12	Pregnant solution tanks		2009	Facilities Demolition				ARO+LOM+FA	5321	C.F.	\$0.16	0.13		862	690	0	1,552
13	D head		2009	Facilities Demolition				ARO+LOM+FA	805	C.F.	\$0.16	0.13		130	104	0	235
14	D transfer		2009	Facilities Demolition				ARO+LOM+FA	2352	C.F.	\$0.16	0.13		381	305	0	686
15	pre-dryer		2009	Facilities Demolition				ARO+LOM+FA	8738	C.F.	\$0.16	0.13		1,416	1,132	0	2,548
16	Victor fresh water		2009	Facilities Demolition				ARO+LOM+FA	6842	C.F.	\$0.16	0.13		1,108	887	0	1,995
17	detox		2009	Facilities Demolition				ARO+LOM+FA	1413	C.F.	\$0.16	0.13		229	183	0	412
18	4 Pregnant solution tanks		2009	Facilities Demolition				ARO+LOM+FA	27369	C.F.	\$0.16	0.13		4,434	3,547	0	7,981
19	fire water		2009	Facilities Demolition				ARO+LOM+FA	11083	C.F.	\$0.16	0.13		1,795	1,436	0	3,232
20	4 bulk storage		2009	Facilities Demolition				ARO+LOM+FA	9236	C.F.	\$0.16	0.13		1,496	1,197	0	2,693
21	2 SST solution		2009	Facilities Demolition				ARO+LOM+FA	3392	C.F.	\$0.16	0.13		550	440	0	989
22	fuel		2009	Facilities Demolition				ARO+LOM+FA	785	C.F.	\$0.16	0.13		127	102	0	229
23	fuel		2009	Facilities Demolition				ARO+LOM+FA	502	C.F.	\$0.16	0.13		81	65	0	146
24	fuel		2009	Facilities Demolition				ARO+LOM+FA	785	C.F.	\$0.16	0.13		127	102	0	229
25	prill		2009	Facilities Demolition				ARO+LOM+FA	25132	C.F.	\$0.16	0.13		4,071	3,257	0	7,328
26	20 carbon columns		2009	Facilities Demolition				ARO+LOM+FA	26998	C.F.	\$0.16	0.13		4,374	3,499	0	7,873
27	intermediate		2009	Facilities Demolition				ARO+LOM+FA	8042	C.F.	\$0.16	0.13		1,303	1,042	0	2,345
28	2 barrel		2009	Facilities Demolition				ARO+LOM+FA	29412	C.F.	\$0.16	0.13		4,765	3,812	0	8,577
29	acid mix		2009	Facilities Demolition				ARO+LOM+FA	1070	C.F.	\$0.16	0.13		173	139	0	312
30	acid neutralization		2009	Facilities Demolition				ARO+LOM+FA	1070	C.F.	\$0.16	0.13		173	139	0	312
31	acid neut scrubber		2009	Facilities Demolition				ARO+LOM+FA	1070	C.F.	\$0.16	0.13		173	139	0	312
32	concentrated acid		2009	Facilities Demolition				ARO+LOM+FA	936	C.F.	\$0.16	0.13		152	121	0	273
33	sodium hydroxide		2009	Facilities Demolition				ARO+LOM+FA	2674	C.F.	\$0.16	0.13		433	347	0	780
34	kiln		2009	Facilities Demolition				ARO+LOM+FA	290	C.F.	\$0.16	0.13		47	38	0	85
35	feed		2009	Facilities Demolition				ARO+LOM+FA	1256	C.F.	\$0.16	0.13		203	163	0	366
36	quench		2009	Facilities Demolition				ARO+LOM+FA	706	C.F.	\$0.16	0.13		114	91	0	206
37	strip		2009														

Closure Cost Estimate
Other Demo & Equip Removal

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0


Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Other Demolition and Equipment Removal - ARO Cost Summary

	Labor \$	Equipment \$	Materials \$	Totals \$
Other Demolition	74,097	35,720	0	109,818
Equipment Removal	3,490	2,792	113,506	119,787
TOTALS	77,587	38,512	113,506	229,605



Closure Cost Estimate
Well Abandonment

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Well Abandonment - ARO Cost Summary				
	Labor \$	Equipment \$	Materials \$	Totals \$
Production, Dewatering, Infiltration Wells	0	0	0	0
Monitoring Wells	39,581	60,460	2,919	102,960
TOTALS	39,581	60,460	2,919	102,960

Well seal thickness: 5 ft
 Minimum seal above groundwater table: 20 ft

Production, Dewatering and Infiltration Well Closure																														
	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Number of Holes	Casing Diam in	Average Depth ⁽¹⁾ ft bgs	Depth to First Water ft bgs	Original Static Water Level ft bgs	Top of Slotted Casing ⁽²⁾ ft bgs	Blank Casing Below Top of Screen ⁽²⁾ ft	Type of Pump (if any) (select)	Depth to Pump ft bgs	Hole Plug Method (select)	Casing Volume per ft cf	Perforation Length ^(3,4) ft	Grout Volume per Hole ^(4,5) cy	Inert Media Volume per Hole ⁽⁷⁾ cy	Pump Removal Labor Cost \$	Pump Removal Equip Cost \$	Perf Labor Cost \$	Perf Equip Cost ⁽⁸⁾ \$	Grout + Cement Labor Cost ⁽⁹⁾ \$	Grout + Cement Material Cost ⁽¹⁰⁾ \$	Inert Media Equip Cost ⁽⁹⁾ \$	Total Cost \$
(1) For previously abandoned holes enter "0" for depth.																														
(2) Wells abandoned per Nevada Administrative Code (NAC 534.420). Hole grouted and perforated from bottom to 50 feet (15.24m) above the top of the screen, or first water encountered or original static water level, depending on vertical hydraulic gradient and well construction parameters. Inert media (cuttings or alluvium) used from top of grout to top seal.																														
(3) Perforation length = amount of blank casing below first water (for confined aquifers) or predicted recovered water table (unconfined aquifers) + 50 feet (15.24m) of blank casing above water table																														
(4) Assumes 50' (15.24m) sanitary seal at top of hole. Therefore, perforation and grouting only required to bottom of sanitary seal.																														
(5) Assumes 100% loss to formation for grout (abandonite) for screened and perforated sections.																														
(6) Assumes 10' (3m) top seal of cement in casing only. See note 4.																														
(7) Inert material is cuttings or alluvium sourced locally.																														
(8) Includes perforation tool wear cost/ft of perforation (see Productivity Sheet).																														
(9) See Productivity Sheet for hourly production. Minimum 1 hr per hole + fixed hours per hole for move and setup. If no perforation required, use standard drill rig.																														
(10) See Productivity Sheet for hourly production. Minimum 1 hr per hole.																														
Notes:																														

Monitoring Well/Piezometer Closure																										
	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Number of Holes	Casing Diam in	Average Depth ⁽¹⁾ ft bgs	Top of Screen ⁽¹⁾ ft bgs	Hole Plug Method (select)	Casing Volume per ft ft3	Grout Volume/Well ^(2,3) cy	Cement Volume per Hole ⁽⁴⁾ cy	Inert Backfill Volume per Hole ⁽⁶⁾ cy	Total Grouting Hours/ Hole hrs	Total Inert Media Hours/ Hole hrs	Grout + Cement Labor Cost ⁽⁶⁾ \$	Grout + Cement Equip Cost ⁽⁶⁾ \$	Inert Material Labor Cost ⁽⁷⁾ \$	Inert Material Equip Cost ⁽⁷⁾ \$	Total Cost \$		
1 All Monitoring wells		2009	Drill Hole Abandonment					ARO+LOM+FA	71	4.0	227	140	Grout Only	0.090	0.93	0.02		3.5	0.0	39,581	60,460	2,919	0	0	0	102,960

Wells abandoned per NAC 534.420 with bentonite grout placed to 50 feet above the top of the screen (see note 1).
 (1) Assumes top of screen is at or above the static water level (in unconfined aquifers) or the depth of first water encountered (in confined aquifers).
 (2) Assumes 25% loss to formation for grouting.
 (3) Grouting only required to 50' (15.24m) above the top of screen because monitor wells are constructed with a seal in the annular space.
 (4) Assumes top 10' (3m) plugged with cement.
 (5) Assumes hole plugged with inert material (cuttings or alluvium) above grout up to cement surface plug.
 (6) See Productivity Sheet for hourly production. Minimum 1 hr per hole + fixed hours per hole for move and setup (see Productivity Sheet).
 (7) See Productivity Sheet for hourly production. Minimum 1 hr per hole.

Notes:

Closure Cost Estimate
Waste Disposal

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Waste Disposal - ARO Cost Summary

	Labor \$	Equipment \$	Materials \$	Fees \$	Totals \$
Solid Waste - On Site	0	0	N/A	N/A	0
Solid Waste - Off Site	N/A	0	N/A	N/A	0
Solid Waste Total	0	0	0		0
Hazardous Materials	N/A	N/A	N/A	2,824,899	2,824,899
Hydrocarbon Contaminated Soils	0	0	N/A	0	0
TOTALS	0	0	0	2,824,899	2,824,899

Waste Disposal - User Input - Solid Waste

	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Waste Type (select)	Disposal Method (select)	Landfill (Bulk) Disposal		Dumpster
											Quantity cy	Distance to Landfill ft	Slope to Landfill % grade

Notes:

1. All Physical parameters must be input even if manual overrides for volume or area are used.
2. If Slope from facility to borrow source is >20, downhill travel time may be underestimated due to limitation of uphill travel time curves and downhill speed tables from CAT Handbook (see Productivity Sheet)

Waste Disposal - User Input - Hazardous Materials

	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Waste Type (select)	Container Type (select)	Vacuum Truck Size (select)	Liquid Quantity gallons	Solid Quantity cy	One Way Travel Distance to Disposal Site mi	One Way Travel Time to Disposal Site hr
1	Waste			Facilities Demolition				ARO+LOM+FA	Waste Mgmt & Disposal	Liquid 55-gal drum		440,000		175	4.0

Notes:

1. Use Other Demo & Equip Removal Sheet for tank removal

Waste Disposal - User Input - Hydrocarbon Contaminated Soils

	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Waste Type (select)	Disposal Method (select)	Quantity cy	Travel Distance to Offsite Disposal mi
--	------------------------	---------	-------------------	------------------------	--------	-----------	------------	-----------	---------------------	--------------------------	-------------	--

Notes:

1. Use Yards or Landfills Sheets for bioremediation facility reclamation

Closure Cost Estimate
Waste Disposal

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Waste Disposal - ARO Cost Summary					
	Labor \$	Equipment \$	Materials \$	Fees \$	Totals \$
Solid Waste - On Site	0	0	N/A	N/A	0
Solid Waste - Off Site	N/A	0	N/A	N/A	0
Solid Waste Total	0	0	0	0	0
Hazardous Materials	N/A	N/A	N/A	2,824,899	2,824,899
Hydrocarbon Contaminated Soils	0	0	N/A	0	0
TOTALS	0	0	0	2,824,899	2,824,899

Waste Disposal - Assumptions & Calculations

Solid Waste Disposal

Off site disposal assumes use of average roll-off dumpster [30 cu (m3), 10 ton (tonne)]
 On site disposal assumes use of small loader/truck fleet for haulage
 Average density for on site disposal = 2,600 lb/cy (1,540 kg/m3)
 For on site disposal only 1 truck is required unless total truck hours > 8, only 2 trucks unless total truck hours are > 16

Hazardous Materials Disposal

Assumes all hazardous materials are known
 Enter EITHER solid or liquid quantity each line.
 If container type = 55 gallon (200 liter) drum then solid waste hauling costs apply
 Average density for solids assumed to be 2,600 lb/cy (1,540 kg/m3)
 Vacuum truck sizes: small = 2,200 gal (~8,300 litres), large = 5,000 gal (~19,000 litres)
 Vacuum truck on site for 4 hours for each load

Hydrocarbon Contaminated Soils Disposal

Assumes all hazardous materials are known
 On site disposal assumes biopad treatment
 Excavation productivity = 45 cu./hr (35 m3/hr) (Means Heavy Construction, 2006: 02315-424-0360)

Waste Disposal - Solid Waste Disposal

	Description (required)	Waste Volume cy	Number of Off Site Dumpster Loads	Landfill Fleet Equipment	Landfill Fleet Productivity LCY/hr	Number of Trucks	Off-Site		On-Site		
							Total Fleet Hours hrs	Total Dumpster Cost \$	Total Labor Cost \$	Total Equipment Cost \$	Total Waste Disposal Cost \$
		0					0	0	0	0	0

Waste Disposal - Hazardous Materials Disposal

	Description (required)	Liquid Waste Volume gallons	Solid Waste Volume cy	Number of Truck Loads	Tons of Waste Tons	Pick-up Fees \$	Transport Fees \$	Disposal Fees \$	Total Hazardous Material Cost \$
1	Waste	440,000		100	1,833	2,068,240	211,974	544,685	2,824,899
		440,000	0		1,833	2,068,240	211,974	544,685	2,824,899

Waste Disposal - Hydrocarbon Contaminated Soils


	Description (required)	Quantity cy	Total Fleet Hours hrs	Treatment Cost \$	Transport Fees \$	Disposal Fees \$	Total Labor Cost \$	Total Equipment Cost \$	Total Waste Disposal Cost \$
		0	0	0	0	0	0	0	0

Closure Cost Estimate
Misc. Costs

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Fence Removal													
	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Length ft	Costs			
										Type (select type)	Labor Cost \$	Equipment Cost \$	
1	Arequa fence removal		2009	Facilities Demolition				ARO+LOM+FA	3,450	Chain link 8 ft -10 ft Removal	9,833	3,416	13,249
2	Squaw fence removal		2009	Facilities Demolition				ARO+LOM+FA	8,835	Chain link 8 ft -10 ft Removal	25,180	8,747	33,927
											35,013	12,163	47,176

Notes:




Fence Installation										Input				Costs			
	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Length ft	Type (select type)	Labor Cost \$	Equipment Cost \$	Material Cost \$	Total Cost \$			
1	Cresson Fencing		2009	Facilities Demolition				ARO+LOM+FA	22,542	Chain link 8 ft -10 ft Install	201,075	31,108	882,294	1,114,477			
2	Globe Hill Fencing		2009	Facilities Demolition				ARO+LOM+FA	16,764	Chain link 8 ft -10 ft Install	149,535	23,134	656,143	828,812			
											350,610	54,242	1,538,437	1,943,289			

Notes:



Culvert & Buried Pipe Removal										Input				Costs			
	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Length ft	Type (select type)	Location (select.)	Labor Cost \$	Equipment Cost \$	Total Cost \$			
1	Ironclad Access Road Culvert 1		2021	Roads, Railroads, Airstrips				ARO+LOM+FA	80	24 in (600 mm) Diameter	On site	846	294	1,140			
2	Ironclad Access Road Culvert 2		2021	Roads, Railroads, Airstrips				ARO+LOM+FA	80	24 in (600 mm) Diameter	On site	846	294	1,140			
3	Ironclad Access Road Culvert 3		2021	Roads, Railroads, Airstrips				ARO+LOM+FA	80	24 in (600 mm) Diameter	On site	846	294	1,140			
4	Ironclad Access Road Culvert 4		2021	Roads, Railroads, Airstrips				ARO+LOM+FA	80	24 in (600 mm) Diameter	On site	846	294	1,140			
											3,384	1,176	4,560				

Notes:



Closure Cost Estimate
Misc. Costs

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Surface Pipe Removal

	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Length ft	Type (select type)	Location (select)	Input			Costs		
												Labor Cost \$	Equipment Cost \$	Total Cost \$			
1	Arequa Large Pipes		2009	Facilities Demolition				ARO+LOM+FA	6,900	20 in (500 mm) - 36 in (1 m)	Off site	70,104	8,556	78,660			
2	Arequa Small Pipes		2009	Facilities Demolition				ARO+LOM+FA	21,200	20 in (500 mm) - 36 in (1 m)	Off site	215,392	26,288	241,680			
3	Squaw Large Pipes		2009	Facilities Demolition				ARO+LOM+FA	4,082	20 in (500 mm) - 36 in (1 m)	Off site	41,473	5,062	46,535			
4	Squaw Small Pipes		2009	Facilities Demolition				ARO+LOM+FA	12,422	20 in (500 mm) - 36 in (1 m)	Off site	126,208	15,403	141,611			
5	TR76 barren pipe		2009	Facilities Demolition				ARO+LOM+FA	300	20 in (500 mm) - 36 in (1 m)	Off site	3,048	372	3,420			
												456,225	55,681	511,906			

Notes:

Power Line and Substation Removal

	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phase	Location	Property	Cost Type	Power Line Length miles	Power Line Type (select)	Number of Substations #	Location (select)	Input			Costs			Cost Breakdown	
													Power Line Removal \$	Substation Removal \$	Total Cost \$	Labor Cost \$	Equipment Cost \$			
1	Powerlines		2009	Facilities Demolition				ARO+LOM+FA	7.2	Single Pole Powerlines		On site	347,098	0	347,098	69,420	277,678			
2	Crusher and ADR 1 Lines		2009	Facilities Demolition				ARO+LOM+FA	1.9	Double Pole Powerlines		On site	106,333	0	106,333	21,267	85,066			
													453,431	0	453,431	90,687	362,744			

Notes: If substation owned by operator, use Other Demo & Equipment Removal sheet

User may need to add line items in Foundations & Buildings for substation slab demolition and fence removal

Labor/Equipment costs assume approximately 80% of cost are equipment and 20% are labor related costs

Assumed average spacing of 250 FT between poles

Rip-Rap & Rock Lining

	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Area S.Y.	Type (select type)	Crew (select type)	Input			Costs		
												Labor Cost \$	Equipment Cost \$	Material Cost \$	Total Cost \$		
												0	0	0	0		

Notes:

Closure Cost Estimate
Monitoring

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Reclamation Monitoring & Maintenance - ARO Cost Summary				
	Labor	Equipment	Lab & Materials	Totals
Reclamation Monitoring	183,850	13,485	N/A	197,335
Water Quality Monitoring	653,884	166,135	915,115	1,735,134
Pump Costs	N/A	2,872	N/A	2,872
TOTAL	0	837,734	182,492	915,115

Reclamation Monitoring														
	Description (required)	Staff	ID Code	Construction Year ⁽¹⁾	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Number of Staff	Number of Trucks	Hrs/Day	Days/Year	Number of Years
1	Field Work: Range Scientist	Range Scientist		2009	Monitoring				ARO+LOM+FA	1	1	10	5	10
2	Reporting: Range Scientist	Range Scientist		2009	Monitoring				ARO+LOM+FA	1		5	2	10
3	Travel: Range Scientist	Range Scientist		2009	Monitoring				ARO+LOM+FA	1		10	1	10
4	Ground & Surface Water Monitoring: R	Field Geologist/Engineer		2009	Monitoring				ARO+LOM+FA	1		8	5	14

Notes:

Water and Rock Sample Analysis																	Comments	
	Description (required)	Analysis Type	ID Code	Construction Year ⁽¹⁾	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Samples #	Events/Year #	No. Years #	First Sample Year closure year	No. of Samplers	Days/Event #	Hrs/Day #	Reporting Hours/Event	Comments
1	Water Analysis (Complete) (1)	Water Analysis (Profile I) (1)		2009	Monitoring				ARO+LOM+FA	21	4	14	1	1	4	10		
2	Water Analysis (Complete) (1)	Water Analysis (Profile II) (1)		2009	Monitoring				ARO+LOM+FA	14	4	14	1	1	4	10		
3	Water Analysis (Complete) (1)	Water Analysis (Profile III) (1)		2009	Monitoring				ARO+LOM+FA	1	12	14	1	1	1	10		

Notes:

- (1) This is the first year that the monitoring commitment is made (e.g. included in permit or approved monitoring plan)
- (2) Monitoring may not extend beyond the maximum number of schedule years (100)
- (3) First Sample Year can not be before first closure year shown in schedule (-21).

Groundwater Monitoring Pump Costs															
	Description (required)	ID Code	Construction Year ⁽¹⁾	Facility/Activity Type	Phases	Locations	Properties	Cost Type	No. of units	Replacement period (1) (yrs)	Replacement Period Start Year (closure year)	Replacement Period End Year (closure year)	Pump Cost	# Monitor Yrs in Schedule	Total \$
1	Ground & Surface Water Monitoring		2009	Monitoring				ARO+LOM+FA	1	14	1	13	2,872	14	2,872

Notes:

- (1) Replacement period = frequency of pump replacement

Reclamation Monitoring						
	Description (required)	Labor Rate \$/hr	Equipment Rate \$/hr	Labor Cost \$	Equipment Cost \$	Total \$
1	Field Work: Range Scientist	132.56	26.97	66,280	13,485	79,765
2	Reporting: Range Scientist	132.56	0.00	21,210	0	21,210
3	Travel: Range Scientist	132.56	0.00	13,256	0	13,256
4	Ground & Surface Water Monitoring: R	148.40	0.00	83,104	0	83,104
		183,850	13,485		197,335	

Water and Rock Sample Analysis									
	Description (required)	Analysis Cost \$/sample	Supplies \$/sample	Labor Cost \$	Equipment Cost \$	Material Cost \$	Lab Cost \$	Reporting Cost \$	Total \$
1	Water Analysis (Complete) (1)	423.33	6.71	237,776	60,413	7,885	497,836	0	803,910
2	Water Analysis (Complete) (1)	423.33	6.71	237,776	60,413	5,257	331,891	0	655,336
3	Water Analysis (Complete) (1)	423.33	6.71	178,332	45,310	1,126	71,119	0	295,889
		653,884	166,135	14,269	900,846	0			1,735,134

Closure Cost Estimate
Recl. Maint

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Reclamation Maintenance - Cost Summary

	Labor	Equipment	Lab & Materials	Totals
Revegetation Maintenance	64,043	23,323	192,472	279,838
Cover Maintenance	0	0	N/A	0
Growth Media Maintenance	28,479	85,438	N/A	113,917
TOTAL	92,522	108,761	192,472	393,755

Revegetation Maintenance

	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Revegetation Surface Area (user override)	% Area Requiring Reseeding	Seed Mix (select)	Area Requiring Reseeding acres	Seed \$/acres	Labor \$/acres	Equipment \$/acres	Labor Cost \$	Equipment Cost \$	Material Cost \$	Total \$
1	Revegetation Maintenance		2009	Monitoring				ARO+LOM+FA		10%	User Mix 1	439.7	437.75	145.66	53.05	64,043	23,323	192,472	279,838

Notes: 1) Calculated based on cost type and current filters - (See Reclamation Quantities sheet)
 2) Will use values from Reclamation Quantities sheet if user does not override
 3) Surface area is NOT the same as footprint disturbance area typically used for permitting purposes.

Total Cover Volume	Average Placement Cost
cy	\$/cy

Information from Reclamation Quantities Sheet: 66,733 4.07

Cover Maintenance

	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Total Cover Volume (1) (user override)	% Volume Requiring Maintenance	Average Placement Cost (1) (user override)	Volume Requiring Replacement cy	Labor (assume: 25%) \$/cy	Equipment (assume: 75%) \$/cy	Labor Cost \$	Equipment Cost \$	Total \$
1	Cover Maintenance		2009	Monitoring				ARO+LOM+FA				0	0	0	0	0	

Notes: 1) Will use values from Reclamation Quantities sheet if user does not override

Total GM Volume	Average Placement Cost
cy	\$/cy

Information from Reclamation Quantities Sheet: 2,287,498 2.49

Growth Media Maintenance

	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Total Volume (user override)	% Volume Requiring Maintenance	Average Placement Cost (user override)	Volume Requiring Replacement cy	Labor (assume: 25%) \$/cy	Equipment (assume: 75%) \$/cy	Labor Cost \$	Equipment Cost \$	Total \$
1	Erosion Maintenance		2009	Monitoring				ARO+LOM+FA		2%		45,750	0.62	1.87	28,479	85,438	113,917

Notes: 1) Will use values from Reclamation Quantities sheet if user does not override

Closure Cost Estimate
Constr. Mgmt

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsxm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsxm

Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Construction Management & Road Maintenance - ARO Cost Summary

	Labor	Equipment	Materials	Totals
Construction Management	\$ 2,734,234	\$ 724,954	N/A	\$ 3,459,188
Road Maintenance	\$ 903,859	\$ 1,970,842	N/A	\$ 2,874,701
Water Fees	N/A	N/A	0	0
TOTAL	\$ 3,638,093	\$ 2,695,796	0	\$ 6,333,889

Construction Management

	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Construction Management Staff			Construction Support		
									Duration mo.	Hours/ Month hrs	Number of Supervisors	Temporary Office Units	Temporary Toilet Units	First Construction Year closure year
1	Active Reclamation		2009	Consultants Services				ARO+LOM+FA	168	160	1			

Notes:

Road Maintenance

	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Water Truck (select)	Grader (select)	Fleet Size number	Duration mo.	First Maintenance Year closure year	Hours/ Month hrs	Equipment Fleet	Fleet Hours hrs	Labor Cost \$	Equipment Cost \$	Totals \$
1	Active Reclamation		2009	Roads, Railroads, Airstrips				ARO+LOM+FA	Large	Medium	1	48	1	160	621E (8,000 gal)/14M	7,680	\$ 903,859	\$ 1,970,842	\$ 2,874,701

Notes:

Water Fees

	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Gallons/Day	Days/ Month	Duration mo.	First Year closure year	Cost/Gallon \$	Totals \$
1	Active Reclamation													0

Notes:

Construction Management

	Supervisor Rate \$/hr	Labor Cost \$	Equipment Cost ⁽¹⁾ \$	Total \$	Construction Management Staff			Construction Support		
					Office Rental Rate \$/mo	Toilet Rental Rate \$/mo	Generator Cost \$/mo	Total \$	Construction Mgmt \$	
1	Active Reclamation	101.72	\$ 2,734,234	\$ 724,954	\$ 3,459,188	0	0	0	0	\$ 3,459,188

Notes: Office rental assumes only 1 generator required for every 4 trailers

Closure Cost Estimate
Other User

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Other Cost Items Calculated Elsewhere

	Description (required)	ID Code	Construction Year	Facility/Activity Type	Phases	Locations	Properties	Cost Type	Quantity	Units	Total Capital Cost \$	Material Unit Cost \$	Labor Unit Cost \$	Equipment/Operating Unit Cost \$	Total Cost \$	Comments
1	Safety signs		2009	Owner's Management (Post Closure)				ARO+LOM+FA	111		201.30	42.88			27,104	
2	Tire disposal		2009	Facilities Demolition				ARO+LOM+FA	50		1,005.07				50,254	
3	Tree planting; East Cresson Wildhorse		2009	Dumps , Stockpiles, Landfills				ARO+LOM+FA	89		1,104.09	42.88			101,736	
4	Tree planting; WHEX Grassy Valley		2009	Dumps , Stockpiles, Landfills				ARO+LOM+FA	0		1,104.09	42.88			0	
5	Tree planting; N Cresson		2009	Dumps , Stockpiles, Landfills				ARO+LOM+FA	23		1,104.09	42.88			26,380	
6	Tree planting; Main Cresson		2009	Dumps , Stockpiles, Landfills				ARO+LOM+FA	59		1,104.09	42.88			67,671	
7	Tree planting; E Cresson OSA		2009	Dumps , Stockpiles, Landfills				ARO+LOM+FA	229		1,104.09	42.88			262,656	
8	Tree planting; Squaw OSA		2009	Dumps , Stockpiles, Landfills				ARO+LOM+FA	42		1,104.09	42.88			48,058	
9	Tree planting; Arequa		2009	Heap Leach Pads Reclamation				ARO+LOM+FA	115		1,104.09	42.88			131,902	
10	Tree planting; Squaw		2009	Dumps , Stockpiles, Landfills				ARO+LOM+FA	85		1,104.09	42.88			97,492	
11	Tree planting; mill platform		2009	Facilities Demolition				ARO+LOM+FA	35		1,104.09	42.88			40,144	
12	Tree planting; 3 4 Ajax		2009	Dumps , Stockpiles, Landfills				ARO+LOM+FA	0		1,104.09	42.88			0	
13	Tree planting;Victor & Ironclad		2009	Dumps , Stockpiles, Landfills				ARO+LOM+FA	42		1,104.09	42.88			48,058	
14	Tree planting; Building footprint		2009	Facilities Demolition				ARO+LOM+FA	87		1,104.09	42.88			99,901	
15	Tree planting; Ancillary		2009	Dumps , Stockpiles, Landfills				ARO+LOM+FA	850		1,104.09	42.88			975,040	
16	Tree planting; replace areas that fail		2009	Monitoring				ARO+LOM+FA	327		1,104.09	42.88			375,174	
17	North Cresson Viewshed		2009	Owner's Management (Post Closure)				ARO+LOM+FA	1		1,531,823				1,531,823	
18	mob & demob		2009	Mobilization and Demobilization				ARO+LOM+FA	1		620,190.52				620,191	
19	Construct Closure Stormwater		2009	Drainage / Diversion Channels				ARO+LOM+FA	1		17,181,964				17,181,964	
20	Hoops: Rinsing VLF1 and VLF2		2009	Water Treatment-Leach Pad Drain Down				ARO+LOM+FA	1		66,634,831.23	40,524,409.21	2,905,747.45		110,064,988	
21	Drilling to perforate liner		2009	Water Treatment-Leach Pad Drain Down				ARO+LOM+FA	1		550,243				550,243	
22	VLF3 Rinse		2020	Water Treatment-Leach Pad Drain Down				LOM	1		0.00				0	
23	Chicago Tunnel		2009	Portals / Adits Underground Mines				ARO+LOM+FA	1		100,514				100,514	
24	Providence Mine		2009	Portals / Adits Underground Mines				ARO+LOM+FA	1		0				0	
									19,364,544	69,516,810	40,614,191	2,905,747			132,401,293	

Notes:

Capital cost is lump sum (i.e. not multiplied by the quantity).

Material, Labor and Equipment/Operating costs are unit costs (i.e. multiplied by the quantity).

mob/demob = 1% of labor & equipment costs from Earthwork/Recontouring

Closure Cost Estimate
Reclamation Quantities

Reclamation Quantity Summary - ARO																Unit Costs								
	Description	Total Regrade or Haul Volume cy	Total Regrade or Haul Cost \$	Total Backfill/Berm Volume cy	Backfill Cost \$	Total Cover Volume cy	Cover Placement Cost \$	Total Growth Media Volume cy	Growth Media Placement Cost \$	Revegetation Surface Area acres	Total Scarify Cost \$	Revegetation Cost \$	Geosynthetics ft2	Geosynthetics Cost \$	TOTALS \$	Regrade Unit Cost \$/CY	Backfill or Berm Construction Unit Cost \$/CY	Material Haul Unit Cost \$/CY	Cover Unit Cost \$/CY	Growth Media Unit Cost \$/ac	Scarify Unit Cost \$/ac	Revegetation Unit Cost \$/ac	Geosynthetics \$/ft2	Area Unit Cost \$/acres
1	Waste Rock Dumps	11,765,593	10,444,530	-	0	1,273,003	2,973,883	1,578.26	391,646	2,200,938	-	-	-	-	16,010,997	0.89	N/A	N/A	2.34	248.15	1,394.53	N/A	10,144.71	
2	Tailings Impoundments	-	0	-	0	-	0	-	0	0	0	0	0	0	-	N/A	N/A	N/A	2.69	177.75	1,394.54	N/A	7,106.10	
3	Heap Leach Pads	11,147,897	4,189,059	-	0	0	-	0	1,005,100	2,706,019	1,245.99	221,469	1,737,581	-	-	8,854,128	0.38	N/A	N/A	N/A	N/A	N/A	N/A	7,106.10
4	Open Pits	-	0	-	0	-	0	-	0	-	0	0	0	0	-	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
5	Quarries & Borrow Pits	-	0	-	0	-	0	-	0	-	0	0	0	0	-	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
6	Roads	-	0	-	0	-	0	-	0	-	0	0	0	0	-	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
7	Ponds	-	0	166,414	438,343	-	0	9,395	24,612	11.60	16,337	374	88,551	567,843	N/A	2.63	N/A	N/A	2.62	N/A	1,408.34	236.77	48,951.96	
8	Yards	-	0	-	0	-	0	-	0	1,549.80	275,364	2,161,244	-	-	2,436,608	N/A	N/A	N/A	N/A	N/A	177.68	1,394.53	N/A	1,572.21
9	Landfills	-	0	-	0	-	0	-	0	-	0	0	0	0	-	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
10	Generic Haulage/Backfill	24,883,444	39,979,480	-	0	-	0	-	0	-	0	0	0	0	39,979,480	N/A	N/A	1.61	N/A	N/A	N/A	N/A	N/A	
11	Buildings	-	0	-	0	66,733	271,368	-	0	11.20	12,887	27,632	-	311,887	N/A	N/A	N/A	4.07	N/A	1,150.63	2,467.15	-	27,847.06	
12	Diversion Ditches	-	0	-	0	-	0	-	0	-	0	-	0	0	-	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
13	Sediment Ponds	-	0	-	0	-	0	-	0	-	0	0	0	0	-	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
14	Exploration Roads	-	0	-	0	-	0	-	0	-	0	0	0	0	-	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
15	Exploration Trenches	-	0	-	0	-	0	-	0	-	0	0	0	0	-	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
16	Adit/Decline Backfilling1	-	0	-	0	-	0	-	0	-	0	0	0	0	-	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
17	Shaft Backfilling	-	0	-	0	-	0	-	0	-	0	0	0	0	-	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
TOTALS		47,796,934	54,613,069	166,414	438,343	66,733	271,368	2,287,498	5,704,514	4,396.85	901,366	6,143,732	374	88,551	68,160,943									
Average Costs		per CY	1.14	per CY	2.63	per CY	4.07	per CY	2.49	per acre	205.00	6.82	per CY	236.77	15,502	per acre								

Closure Cost Estimate

Labor Rates

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Color Code Key	
User Input - Direct Input	Direct Input
User Input - Pull Down List	Pull Down Selection
Program Constant (can override)	Alternate Input
Program Calculated Value	Locked Cell - Formula or Reference

ZONE ADJUSTMENTS			
Cost Basis/Project Region	AM-14 CC&V - US	Adjusted for escalation, Labor: 1.03, Equipment: 1.03, Tires: 1.03, Reclamation Materials: 1.03, Misc. Costs: 1.03	
Power Equipment Operators	0-50 miles	0.00	
Truck Drivers	0-50 miles	0.00	
Laborers	0-50 miles	0.00	

**Closure Cost Estimate
Labor Rates**

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Color Code Key		
User Input - Direct Input	Direct Input	
User Input - Pull Down List	Pull Down Selection	
Program Constant (can override)	Alternate Input	
Program Calculated Value	Locked Cell - Formula or Reference	

ZONE ADJUSTMENTS		
Cost Basis/Project Region	AM-14 CC&V - US	Adjusted for escalation, Labor: 1.03, Equipment: 1.03, Tires: 1.03, Reclamation Materials: 1.03, Misc. Costs: 1.03
Power Equipment Operators	0-50 miles	0.00
Truck Drivers	0-50 miles	0.00
Laborers	0-50 miles	0.00
INDIRECT COSTS		
Unemployment (%)	3.12%	
Retirement/SS/Medicare (%)	7.96%	
Workman's Compensation (%)	7.80%	
Other Indirects		
State Payroll Tax (13),(15),(17),(18)		
Total Other Indirects	0.00%	

HOURLY LABOR RATE TABLE												
Other Equipment												
420F2		40.31	0.00	40.31	26.05	3.21	1.26	3.15	0.00			0 73.98
430F2		40.31	0.00	40.31	26.05	3.21	1.26	3.15	0.00			0 73.98
CS54B		38.79	0.00	38.79	26.05	3.09	1.21	3.03	0.00			0 72.17
CS64B		38.79	0.00	38.79	26.05	3.09	1.21	3.03	0.00			0 72.17
CP54B		38.79	0.00	38.79	26.05	3.09	1.21	3.03	0.00			0 72.17
CP68B		38.79	0.00	38.79	26.05	3.09	1.21	3.03	0.00			0 72.17
Light Truck - 1.5 Ton		38.79	0.00	38.79	26.05	3.09	1.21	3.03	0.00			0 72.17
Supervisor's Truck		38.79	0.00	38.79	26.05	3.09	1.21	3.03	0.00			0 72.17
Flatbed Truck		38.79	0.00	38.79	26.05	3.09	1.21	3.03	0.00			0 72.17
Air Compressor + tools		37.25	0.00	37.25	26.05	2.96	1.16	2.91	0.00			0 70.34
Welding Equipment		40.31	0.00	40.31	26.05	3.21	1.26	3.15	0.00			0 73.98
Heavy Duty Drill Rig		39.41	0.00	39.41	26.05	3.14	1.23	3.08	0.00			0 72.90
Pump (plugging) Drill Rig		39.41	0.00	39.41	26.05	3.14	1.23	3.08	0.00			0 72.90
Concrete Pump					26.05							0
Gas Engine Vibrator		38.79	0.00	38.79	26.05	3.09	1.21	3.03	0.00			0 72.17
Generator 5KW					26.05							0
HDEP Welder (pipe or liner)					26.05							0
5 Ton Crane		40.31	0.00	40.31	26.05	3.21	1.26	3.15	0.00			0 73.98
20 Ton Crane		40.31	0.00	40.31	26.05	3.21	1.26	3.15	0.00			0 73.98
50 Ton Crane		40.31	0.00	40.31	26.05	3.21	1.26	3.15	0.00			0 73.98
120 Ton Crane		40.31	0.00	40.31	26.05	3.21	1.26	3.15	0.00			0 73.98

NOTES:												
(1) Equipment Type:	Caterpillar model or equivalent, LeTourneau											
(2) Equipment Operator Source:	BP22 +3%											
(3) Zone Basis:												

Truck Drivers (4)												
725C2		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
730C2		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
735C		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
740C		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
770G		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
773G		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
777G		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
785D		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
789D		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
793F		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
797F		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
613E (5,000 gal)		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
621E (8,000 gal)		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
777G H2O Truck		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
785D H2O Truck		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
Dump Truck (10-12 yd3)		33.09	0.00	33.09	4.37	2.63	1.03	2.58	0.00			0 43.71
Tractor/Trailer (20 ton)		0.00		0.00	4.37	0.00	0.00	0.00	0.00			0 4.37
Tractor/Trailer (50 ton)		0.00		0.00	4.37	0.00	0.00	0.00	0.00			0 4.37
Tractor/Trailer (80 ton)		0.00		0.00	4.37	0.00	0.00	0.00	0.00			0 4.37

NOTES:												
(4) Truck Driver Source:												
(5) Zone Basis:												

Closure Cost Estimate

Labor Rates

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Page 163 of 174 | March 2024

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US

Color Code Key	
User Input - Direct Input	Direct Input
User Input - Pull Down List	Pull Down Selection
Program Constant (can override)	Alternate Input
Program Calculated Value	Locked Cell - Formula or Reference

ZONE ADJUSTMENTS

Cost Basis/Project Region	AM-14 CC&V - US	Adjusted for escalation, Labor: 1.03, Equipment: 1.03, Tires: 1.03, Reclamation Materials: 1.03, Misc. Costs: 1.03
Power Equipment Operators	0-50 miles	0.00
Truck Drivers	0-50 miles	0.00
Laborers	0-50 miles	0.00

INDIRECT COSTS

Unemployment (%)	3.12%	
Retirement/SS/Medicare (%)	7.96%	
Workman's Compensation (%)	7.80%	
Other Indirects		
State Payroll Tax (13),(15),(17),(18)		
Total Other Indirects	0.00%	

HOURLY LABOR RATE TABLE

Laborers (6,7)

General Laborer		26.74	0.00	26.74	11.09	2.13	0.83	2.09	0.00				0	42.88
Skilled Laborer		27.26	0.00	27.26	11.09	2.17	0.85	2.13	0.00				0	43.50
Driller's Helper		27.00	0.00	27.00	11.09	2.15	0.84	2.11	0.00				0	43.19
Rodmen (reinforcing concrete)		26.74	0.00	26.74	11.09	2.13	0.83	2.09	0.00				0	42.88
Cement finisher		27.00	0.00	27.00	11.09	2.15	0.84	2.11	0.00				0	43.19
Carpenter		37.70	0.00	37.70	0.00	3.00	1.18	2.94	0.00				0	44.81

NOTES:

(6) Laborer Source:	BP22 + 3%
(7) Carpenter Source:	BP22 + 3%
(8) Zone Basis:	

Project Management and Technical Labor (9)

NOTES:

(9) Project Manager:	BP22 + 3%
(9) Foreman Source:	BP22 + 3%
(9) Technical Labor Source:	BP22 + 3%
Other Labor Source:	
Other Labor Source:	Mechanic/Fitter: SRCE_AM13_FW_V2.xlsx, with 1.032 scaling factor for US labor
+Additional User Markups	
(These are added by the user to the base rate to account for site-specific conditions or corporate requirements)	

Closure Cost Estimate
Equipment Costs

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsxm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsxm

Monthly Rental Basis: 160 hrs month

Wet Rates? No

EQUIPMENT RENTAL RATE TABLE

EQUIPMENT TYPE (1)	Monthly Owner/Rental Rate \$/mo	Equipment Hourly Rate \$/hr	Fuel/Lube/ Wear \$/hr	Total Rate \$/hr
Bulldozers				
D6T	11,250.84	70.32	30.23	100.55
D6R w/ Winch	11,250.84	70.32	30.23	100.55
D7E	12,279.92	76.75	28.81	105.56
D8T	23,371.63	146.07	46.06	192.13
D9T	31,381.42	196.13	61.18	257.32
D10T2	43,496.90	271.86	82.96	354.81
D11T	67,897.60	424.36	117.43	541.79
Wheeled Dozers				
824K			29.15	29.15
834K			34.19	34.19
844K			38.70	38.70
854K			49.02	49.02
Motor Graders				
12M2	10,386.21	64.91	32.23	97.15
14M	14,932.17	93.33	44.59	137.92
16M3	23,339.80	145.87	56.46	202.34
24M	25,673.78	160.46	74.69	235.15
Track Excavators				
312F	5,707.64	35.67	14.19	49.86
320F	6,439.66	40.25	19.15	59.40
325F	9,007.04	56.29	20.74	77.03
330F	11,685.81	73.04	26.26	99.30
349F	15,452.01	96.58	40.29	136.87
374F	19,899.83	124.37	44.73	169.10
390F	24,347.66	152.17	51.48	203.65
Scrapers				
631K	26,835.47	167.72	70.85	238.57
637K	37,131.50	232.07	102.41	334.48
Wheeled Loaders				
926M	5,145.37	32.16	19.04	51.19
930M	5,622.77	35.14	20.10	55.24
950M	8,221.98	51.39	27.81	79.20
966M	11,791.90	73.70	34.48	108.18
972M	14,932.17	93.33	39.31	132.63
980M	14,932.17	93.33	45.34	138.66
988K	24,888.71	155.55	67.40	222.95
990K	45,862.71	286.64	103.49	390.14
992K	66,836.70	417.73	134.95	552.68
994K	73,520.37	459.50	189.98	649.48
L2350			170.28	170.28
Shovels				
PC2000			95.46	95.46
PC3000			129.00	129.00
PC4000			180.60	180.60
PC5500			307.02	307.02
PC8000			384.42	384.42
EX2500			131.58	131.58
Hydraulic Hammers				
H120Es (fits 325)	6,163.83	38.52	5.96	44.49
H160Es (fits 349)	12,985.42	81.16	11.65	92.81
H180Es (fits 374/390)	17,526.07	109.54	13.80	123.34
Demolition Shears				
S3050 (fits 320/325/330)			0.00	0.00
S3070 (fits 330/349)			0.00	0.00
S3090 (fits 374/390)			0.00	0.00
Demolition Grapples				
G315B (fits 320/325)			0.00	0.00
G320B (fits 325/330)			0.00	0.00
G330 (fits 349/374)			0.00	0.00
Other Equipment				
420F2	2,864.43	17.90	20.31	38.22
430F2	3,660.11	22.88	21.21	44.08
CS54B	8,635.73	53.97	8.64	62.62
CS64B	8,635.73	53.97	8.64	62.62
CP54B	8,635.73	53.97	8.64	62.62
CP68B	8,635.73	53.97	9.29	63.26
Light Truck - 1.5 Ton	4,290.28	26.81	4.16	30.97
Supervisor's Truck	3,855.31	24.10	2.87	26.97
Flatbed Truck	4,290.28	26.81	13.72	40.54
Air Compressor + tools	6,099.11	38.12	2.58	40.70
Welding Equipment	3,220.89	20.13	5.16	25.29
Heavy Duty Drill Rig	34,799.64	217.50	30.96	248.46
Pump (plugging) Drill Rig	34,799.64	217.50	25.80	243.30
Concrete Pump	8,985.82	56.16	25.80	81.96
Gas Engine Vibrator	587.74	3.67	2.58	6.25
Generator 5KW	1,752.61	10.95	3.87	14.82
HDEP Welder (pipe or liner)	9,312.58	58.20	5.16	63.36
5 Ton Crane	8,252.74	51.58	7.74	59.32
20 Ton Crane	12,650.17	79.06	10.32	89.38
50 Ton Crane	12,650.17	79.06	12.13	91.19
120 Ton Crane	13,915.19	86.97	13.42	100.39
Trucks				
725C2	16,231.77	101.45	40.77	142.22
730C2	16,231.77	101.45	41.68	143.13
735C	16,231.77	101.45	54.72	156.17
740C	16,231.77	101.45	58.20	159.65
770G	22,968.49	143.55	30.74	174.30
773G	36,097.12	225.61	46.69	272.29
777G	59,092.13	369.33	71.25	440.57
785D	65,001.34	406.26	110.07	516.33
789D	71,501.48	446.88	110.07	556.96
793F	78,651.63	491.57	170.28	661.86
797F	86,516.79	540.73	234.85	775.58
613E (5,000 gal)	7,033.77	43.96	24.94	68.90
621E (8,000 gal)	11,903.30	74.40	44.30	118.70
777G H2O Truck	59,092.13	369.33	71.25	440.57
785D H2O Truck	65,001.34	406.26	110.07	516.33
Dump Truck (10-12 yds3)	12,533.47	78.33	14.51	92.84
Tractor/Trailer (20 ton)	13,786.82	86.17	36.12	122.29
Tractor/Trailer (50 ton)	15,165.50	94.78	46.44	141.22
Tractor/Trailer (80 ton)	16,682.05	104.26	56.76	161.02

NOTES:

Power Equipment Source:	Caterpillar model or equivalent, LeTourneau loader, Komatsu shovels
Power Equipment Type:	
Drilling Equipment Source:	
Other Equipment Source:	

Note: Drill rig includes support (pipe) truck

**Closure Cost Estimate
Equipment Costs**

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsx

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx

FUEL, LUBE AND WEAR CALCULATIONS

EQUIPMENT TYPE	PM Cost ⁽¹⁾ \$/hr	Under carriage or Tires \$/hr	G.E.T. Consumption ⁽²⁾ \$/hr	Fuel Use Rate gal/hr ⁽³⁾	Fuel Cost@ 2.58/gal	Total Hourly Equipment Cost \$/hr
Bulldozers						
D6T	8.09		5.50	6.45	16.64	30.23
D6R w/ Winch	8.09		5.50	6.45	16.64	30.23
D7E	8.09		5.50	5.90	15.22	28.81
D8T	8.54		10.68	10.40	26.83	46.06
D9T	9.74		16.61	13.50	34.83	61.18
D10T2	11.46		23.25	18.70	48.25	82.96
D11T	15.61		34.22	26.20	67.60	117.43
Wheeled Dozers						
824K		0.00		11.30	29.15	29.15
834K		0.00		13.25	34.19	34.19
844K		0.00		15.00	38.70	38.70
854K		0.00		19.00	49.02	49.02
Motor Graders						
12M2	4.92	5.94	11.44	3.85	9.93	32.23
14M	6.13	8.90	16.53	5.05	13.03	44.59
16M3	6.41	11.35	22.58	6.25	16.13	56.46
24M	7.05	12.49	24.83	11.75	30.32	74.69
Track Excavators						
312F	4.63		4.28	2.05	5.29	14.19
320F	4.93		4.93	3.60	9.29	19.15
325F	4.97		6.23	3.70	9.55	20.74
330F	6.12		6.85	5.15	13.29	26.26
349F	8.13		7.01	9.75	25.16	40.29
374F	7.47		10.68	10.30	26.57	44.73
390F	6.81		14.35	11.75	30.32	51.48
Scrapers						
631K	8.21	14.64	9.00	15.12	39.01	70.85
637K	13.65	14.64	11.31	24.35	62.81	102.41
Wheeled Loaders						
926M	3.74	5.90	4.74	1.80	4.64	19.04
930M	4.39	5.90	4.90	1.90	4.90	20.10
950M	5.46	5.22	9.12	3.10	8.00	27.81
966M	5.70	7.66	11.45	3.75	9.68	34.48
972M	6.44	7.66	14.50	4.15	10.71	39.31
980M	6.44	10.20	14.50	5.50	14.19	45.34
988K	12.06	12.96	15.54	10.40	26.83	67.40
990K	12.71	19.77	25.61	17.60	45.41	103.49
992K	13.36	26.57	35.68	23.00	59.34	134.95
994K	14.69	29.23	39.25	41.40	106.81	189.98
L2350				66.00	170.28	170.28
Shovels						
PC2000				37.00	95.46	95.46
PC3000				50.00	129.00	129.00
PC4000				70.00	180.60	180.60
PC5500				119.00	307.02	307.02
PC8000				149.00	384.42	384.42
EX2500				51.00	131.58	131.58
Hydraulic Hammers						
H120Es (fits 325)	N/A		5.96			5.96
H160Es (fits 349)	N/A		11.65			11.65
H180Es (fits 374/390)	N/A		13.80			13.80
Demolition Shears						
S3050 (fits 320/325/330)	N/A					0.00
S3070 (fits 330/349)	N/A					0.00
S3090 (fits 374/390)	N/A					0.00
Demolition Grapples						
G315B (fits 320/325)	N/A					0.00
G320B (fits 325/330)	N/A					0.00
G330 (fits 349/374)	N/A					0.00
Other Equipment						
420F2	4.55	0.86	3.81	4.30	11.09	20.31
430F2	4.31	0.86	3.91	4.70	12.13	21.21
CS54B				3.35	8.64	8.64
CS64B				3.35	8.64	8.64
CP54B				3.35	8.64	8.64
CP68B				3.60	9.29	9.29
Light Truck - 1.5 Ton		0.29		1.50	3.87	4.16
Supervisor's Truck		0.29		1.00	2.58	2.87
Flatbed Truck		1.60		4.70	12.13	13.72
Air Compressor + tools			N/A	1.00	2.58	2.58
Welding Equipment			N/A	2.00	5.16	5.16
Heavy Duty Drill Rig				12.00	30.96	30.96
Pump (plugging) Drill Rig				10.00	25.80	25.80
Concrete Pump			N/A	10.00	25.80	25.80
Gas Engine Vibrator			N/A	1.00	2.58	2.58
Generator 5KW			N/A	1.50	3.87	3.87
HDEP Welder (pipe or liner)			N/A	2.00	5.16	5.16
5 Ton Crane				3.00	7.74	7.74
20 Ton Crane				4.00	10.32	10.32
50 Ton Crane				4.70	12.13	12.13
120 Ton Crane				5.20	13.42	13.42
Trucks						
725C2	9.05	15.28	3.42	5.05	13.03	40.77
730C2	9.05	15.28	3.42	5.40	13.93	41.68
735C	9.05	24.33	3.42	6.95	17.93	54.72
740C	9.05	25.61	3.42	7.80	20.12	58.20
770G	6.70	7.45	3.82	4.95	12.77	30.74
773G	8.30	12.82	4.29	8.25	21.29	46.69
777G	11.87	19.63	4.78	13.55	34.96	71.25
785D	13.06	26.99	5.26	25.10	64.76	110.07
789D	14.36	29.69	5.79	36.85	95.07	144.92
793F	15.80	32.66	6.37	44.75	115.46	170.28
797F	17.38	35.93	7.01	67.65	174.54	234.85
613E (5,000 gal)	5.43	4.03	0.00	6.00	15.48	24.94
621E (8,000 gal)	7.68	8.89	0.00	10.75	27.74	44.30
777G H2O Truck	11.87	19.63	4.78	13.55	34.96	71.25
785D H2O Truck	13.06	26.99	5.26	25.10	64.76	110.07
Dump Truck (10-12 yd3)	N/A	1.09	N/A	5.20	13.42	14.51
Tractor/Trailer (20 ton)	N/A		N/A	14.00	36.12	36.12
Tractor/Trailer (50 ton)	N/A		N/A	18.00	46.44	46.44
Tractor/Trailer (80 ton)	N/A		N/A	22.00	56.76	56.76

Notes:

(1) PM Source:

(2) G.E.T. Source:

(3) Fuel Use Source: Caterpillar Handbook, Edition 46, Ch. 20; or estimated average for smaller vehicles

Closure Cost Estimate
Equipment Costs

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsx

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsx

TIRE COST TABLES

Equipment	Tire Size	# of Tires Per Piece of Equipment	Cost Per Tire	Tire Cost ⁽¹⁾⁽²⁾ \$	Life Expectancy Hours (Low/Zone A) ⁽³⁾	Tire Cost per Hour \$/hr
Bulldozers						
D6T			N/A			
D6R w/ Winch			N/A			
D7E			N/A			
D8T			N/A			
D9T			N/A			
D10T2			N/A			
D11T			N/A			
Wheeled Dozers						
824K	29.5R25	4		0	3,500	0.00
834K	35/65-R33	4		0	3,500	0.00
844K	45/65-R39	4		0	3,500	0.00
854K	45/65-R45	4		0	3,500	0.00
Motor Graders						
12M2	13PR24	6	3,465	20,793	3,500	5.94
14M	20.5R25	6	5,194	31,163	3,500	8.90
16M3	23.5R25	6	6,623	39,736	3,500	11.35
24M	23.5R25	6	7,285	43,709	3,500	12.49
Track Excavators						
312F			N/A			
320F			N/A			
325F			N/A			
330F			N/A			
349F			N/A			
374F			N/A			
390F			N/A			
Scrapers						
631K	37.25R35	4	14,636	58,543	4,000	14.64
637K	37.25R35	4	14,636	58,543	4,000	14.64
Wheeled Loaders						
926M	17.5R25	4	6,643	26,571	4,500	5.90
930M	17.5R25	4	6,643	26,571	4,500	5.90
950M	26.5R25	4	5,876	23,503	4,500	5.22
966M	26.5R25	4	8,615	34,461	4,500	7.66
972M	26.5R25	4	8,615	34,461	4,500	7.66
980M	29.5R25	4	11,480	45,918	4,500	10.20
988K	35/65-33	4	14,579	58,314	4,500	12.96
990K	41.25/70-39	4	22,237	88,946	4,500	19.77
992K	45/65R45	4	29,895	119,578	4,500	26.57
994K	55/85R57	4	32,884	131,536	4,500	29.23
L2350	55/85R57	4		0	4,500	
Shovels						
PC2000			N/A			
PC3000			N/A			
PC4000			N/A			
PC5500			N/A			
PC8000			N/A			
EX2500			N/A			
Hydraulic Hammers						
H120Es (fits 325)			N/A			
H160Es (fits 349)			N/A			
H180Es (fits 374/390)			N/A			
Demolition Shears						
S3050 (fits 320/325/330)			N/A			
S3070 (fits 330/349)			N/A			
S3090 (fits 374/390)			N/A			
Demolition Grapples						
G315B (fits 320/325)			N/A			
G320B (fits 325/330)			N/A			
G330 (fits 349/374)			N/A			
Other Equipment						
420F2	340/80R18-19.5LR24	2	1,289	2,578	3,000	0.86
430F2	340/80R18-16.9R28	2	1,289	2,578	3,000	0.86
CS54B			N/A			
CS64B			N/A			
CP54B			N/A			
CP68B			N/A			
Light Truck - 1.5 Ton		4	218	871	3,000	0.29
Supervisor's Truck		4	218	871	3,000	0.29
Flatbed Truck		22	218	4,789	3,000	1.60
Air Compressor + tools			N/A			
Welding Equipment			N/A			
Heavy Duty Drill Rig		4		0	3,000	
Pump (plugging) Drill Rig		4		0	3,000	
Concrete Pump			N/A			
Gas Engine Vibrator			N/A			
Generator 5KW			N/A			
HDEP Welder (pipe or liner)			N/A			
5 Ton Crane		4		0	3,000	
20 Ton Crane		4		0	3,000	
50 Ton Crane		6		0	3,000	
120 Ton Crane		6		0	3,000	
Trucks						
725C2	23.5R25	6	5,093	30,560	2,000	15.28
730C2	23.5R25	6	5,093	30,560	2,000	15.28
735C	26.5R25	6	8,109	48,655	2,000	24.33
740C	29.5R25	6	8,537	51,222	2,000	25.61
770G	18.00R33	6	7,448	44,689	6,000	7.45
773G	24.00R35	6	10,683	64,100	5,000	12.82
777G	27.00R49	6	16,359	98,151	5,000	19.63
785D	33.00R51	6	17,994	107,966	4,000	26.99
789D	40.00R57	6	19,794	118,763	4,000	29.69
793F	40.00R57	6	21,773	130,639	4,000	32.66
797F	40.00R57	6	23,951	143,703	4,000	35.93
613E (5,000 gal)	23.5R25	6	4,031	24,186	6,000	4.03
621E (8,000 gal)	33.25R29	6	11,849	71,094	8,000	8.89
777G H2O Truck	27.00R49	6	16,359	98,151	5,000	19.63
785D H2O Truck	33.00R51	6	17,994	107,966	4,000	26.99
Dump Truck (10-12 yd3)		10	654	6,545	6,000	1.09
Tractor/Trailer (20 ton)			N/A			
Tractor/Trailer (50 ton)			N/A			
Tractor/Trailer (80 ton)			N/A			

Notes:

(1) Unit Cost Basis:

(2) Cost Basis: BP22 inflated 3%

(3) Tire Cost Source:

(4) Tire Wear Source:

Closure Cost Estimate

Material Costs

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Revegetation Materials			
Seed Mixes			
Seed Mix	Description		Cost \$/acres
None			
Mix 1	Basins		311.58
Mix 2	Low Hills		342.73
Mix 3	Uplands		373.89
Mix 4	Riparian or Custom		405.05
User Mix 1	Slater Work 2021 + 3% incr		\$437.75
User Mix 2	AdherenceWork Fall 2021 + 3%		\$325.48
User Mix 3			
User Mix 4			\$1,104.09
	Cost/lb	Ibs/Acre	Cost/Acre
User Mix 5 (from Seed Mix sheet)	#DIV/0!	0.00	0.00
Notes:			
Mulch			
Item	Cost/lb	Ibs/Acre	Cost \$/acres
None			
Straw Mulch	0.18	2000	350.20
Hydro Mulch	0.26	2000	515.00
Notes:			
BP22+3%			

Closure Cost Estimate Material Costs

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Amendments			
Item	Cost/lb	Ibs/Acre	Cost \$/acres
None			
Organic Matter	0.72	2000	1,442.00
Treated Sludge			
Chemical	0.61	400	243.08
Notes:	BP22+3%		

Closure Cost Estimate

Material Costs

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE 2.0 FW AM14 April 2024.xlsxm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14 Newmont CCV FW CDF.xlsm

Cost Estimate Type: ABO Cost Basis: AM-14 CC&V - US

Well Abandonment Materials			
Description	Cost/50lb bag	Units	Cost* \$/unit
Cement	7.80	cy	37.13
Grout (Low Grade Bentonite)	9.12	cy	43.44
Inert Material/Cuttings		cy	
BP22+3%			
BP22+3%			

Closure Cost Estimate Material Costs

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Fuel, Etc.			
Description	Units	Cost \$/unit	User Overrides
Off-road Diesel - delivered (1)	gal	2.580	
Pickup Truck Mileage	\$/mi	0.580	
Electrical Power	\$/kWh	0.100	
Diesel= \$USD 2.58/Gal, As per BP23 Economic Guidance for CC&V distributed in July 2022 (Economic Gui			
BP22+3%			
BP22+3%			
A Munt email 14th July 2017			

Closure Cost Estimate Material Costs

Revegetation Method				
Slopes				
Disturbance Type	Seed Application Method	Labor \$/acres	Equipment \$/acres	Total \$/acres
Waste Rock Dumps	Mechanical Broadcast	145.66	53.05	198.70
Heap Leach	Mechanical Broadcast	145.66	53.05	198.70
Tailings	Hand Broadcast	145.66	53.05	198.70
Quarries & Borrow Pits	Mechanical Broadcast	145.66	53.05	198.70
Flat Areas and Undifferentiated				
Disturbance Type	Seed Application Method	Labor \$/acres	Equipment \$/acres	Total \$/acres
Exploration Trenches	Mechanical Broadcast	145.66	53.05	198.70
Exploration Roads	Mechanical Broadcast	145.66	53.05	198.70
Waste Rock Dumps	Mechanical Broadcast	145.66	53.05	198.70
Heap Leach	Mechanical Broadcast	145.66	53.05	198.70
Tailings	Mechanical Broadcast	145.66	53.05	198.70
Quarries & Borrow Pits	Mechanical Broadcast	145.66	53.05	198.70
Roads	Mechanical Broadcast	145.66	53.05	198.70
Pits	Mechanical Broadcast	145.66	53.05	198.70
Haul Material	Mechanical Broadcast	145.66	53.05	198.70
Foundations & Buildings	Mechanical Broadcast	145.66	53.05	198.70
Sediment & Drainage Control	Mechanical Broadcast	145.66	53.05	198.70
Process Ponds	Mechanical Broadcast	145.66	53.05	198.70
Landfills	Mechanical Broadcast	145.66	53.05	198.70
Yards, Etc.	Mechanical Broadcast	145.66	53.05	198.70
Revegetation Maintenance	Mechanical Broadcast	145.66	53.05	198.70

Closure Cost Estimate
Misc. Unit Costs

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Revegetation

	Means Number	Unit	Crew	Daily Output	Daily Output User	Materials	Labor	Equipment	Total
Seeding - Broadcast Manual		acres					145.66	53.05	198.70
Seeding - Broadcast Mechanical		acres					145.66	53.05	198.70
Seeding - Drill		acres		365			145.66	127.31	272.96
Seeding - Hydroseeding				365			260.10	159.14	419.24
Shrub Planting - bare root 6-10 in (150- 250mm)	02910-400-0561	ea.	1 Clab	365			0.94	0.00	0.94
Tree Planting - bare root 11-16 in (270- 400mm)	02910-400-0562	ea.	1 Clab	260			1.32	0.00	1.32
Cactus Planting		ea.	1 Clab						0.00

NOTES:

Seeding Source:	BP22+3%
Shrub Source:	
Tree Source:	
Cactus Source:	

Building and Wall Demolition

Hourly productivity rates and crew composition from Means Heavy Construction 2005 Edition by permission of R.S.Means/Reed Construction Data .

All equipment, labor and material unit costs are from Labor Costs, Equipment Costs and Material Costs spreadsheets

	Means Number	Unit	Crew	Daily Output	Daily Output User	Labor	Equipment	Premium	Total
Building Demolition									
Lg. steel	02220-110-0012	C.F.	B-8	21500		0.15	0.12		0.27
Lg. concrete	02220-110-0050	C.F.	B-8	15300		0.22	0.17		0.39
Lg. masonry	02220-110-0080	C.F.	B-8	20100		0.17	0.13		0.30
Lg. mixed	02220-110-0100	C.F.	B-8	20100		0.17	0.13		0.30
Sm. steel	02220-110-0500	C.F.	B-3	14800		0.18	0.13		0.31
Sm. concrete	02220-110-0600	C.F.	B-3	11300		0.24	0.17		0.41
Sm. masonry	02220-110-0650	C.F.	B-3	14800		0.18	0.13		0.31
Sm. wood	02220-110-0700	C.F.	B-3	14800		0.18	0.13		0.31
Wall Demolition									
Block 4 in (100 mm) thick	02220-130-2000	S.F.	1 Clab	180		1.91	0.00	20%	2.29
Block 6 in (150 mm) thick	02220-130-2040	S.F.	1 Clab	170		2.02	0.00	20%	2.42
Block 8 in (200 mm) thick	02220-130-2080	S.F.	1 Clab	150		2.29	0.00	20%	2.75
Block 12 in (300 mm) thick	02220-130-2100	S.F.	1 Clab	150		2.29	0.00	20%	2.75
Conc 6 in (150 mm) thick	02220-130-2400	S.F.	B-9	160		2.14	2.04	10%	4.60
Conc 8 in (200 mm) thick	02220-130-2420	S.F.	B-9	140		2.45	2.33	10%	5.26
Conc 10 in (250 mm) thick	02220-130-2440	S.F.	B-9	120		2.86	2.71	10%	6.13
Conc 12 in (300 mm) thick	02220-130-2500	S.F.	B-9	100		3.43	3.26	10%	7.36

Closure Cost Estimate
Misc. Unit Costs

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Waste Disposal

Unit rates from Means Heavy Construction 2006 Edition by permission of R.S.Means/Reed Construction Data .

	Means Number	Unit	Crew	Daily Output	Materials	Labor	Equipment		Total
Rubbish Handling									
Dumpster delivery (average for all sizes)	02220-350-0910	ea.			53.05				53.05
Haul (average for all sizes)	02220-350-0920	ea.			165.83				165.83
Rent per month (average for all sizes)	02220-350-0940	ea.			56.65				56.65
Disposal fee per ton (tonne) (average for all sizes)	02220-350-0950	ton			62.32				62.32

NOTES:

Dumpster Cost Source: BP22+3%

Disposal Fee Source: BP22+3%

Hazardous Material Handling - Solids (+ Liquids in drums)

Pickup fees 55 gal. drums	02110-300-1100	ea.		258.53					258.53
Bulk material (average)	02110-300-1220/1230	ton		421.79					421.79
Transport - truck load (80 drums, 25 cy (m3), 18 tons)	02110-300-1260/1270	mile		6.06					6.06
Dump site disposal fee	02110-300-6000/6020	ton		297.16					297.16

NOTES:

Solid Handling Cost Source: BP22+3%

Solid Disposal Fee Source: BP22+3%

Hazardous Material Handling - Liquids

Vacuum Truck Pickup (2200 gal or 9,700 litres)	02110-300-3110	hr.		151.41					151.41
Vacuum Truck Pickup (5000 gal or 2,000 litres)	02110-300-3120	hr.		219.39					219.39
Dump site disposal fee	02110-300-6000/6020	ton		297.16					297.16

NOTES:

Liquid Handling Cost Source: BP22+3%

Liquid Disposal Fee Source: BP22+3%

Hydrocarbon Contaminated Soils (HCS)

Insitu Bioretention	02115-200-2020/2021	C.Y.							0.00
HCS disposal fee	02115-200-2050/2055	C.Y.							0.00

NOTES:

Insitu Treatment Cost Source:

HCS Disposal Fee Source:

Closure Cost Estimate
Misc. Unit Costs

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Concrete Structure Installation

Weekly dumpster rental rates from Means Heavy Construction 2005 Edition with permission by R.S.Means/Reed Construction Data .

Weekly dumpster rental rates include haul to off-site disposal site and disposal fees

	Means Number	Unit	Crew	Daily Output	Materials	Labor	Equipment	Premium	Total
Reinforced Concrete Bulkheads and Shaft Covers									
Grade walls - 15 in thick, 8 ft high	03310-240-4300	C.Y.	C-14D	80.02	167.89	126.07	11.52		305.48
Grade walls - 15 in thick, 12 ft high	03310-240-4350	C.Y.	C-14D	26.2	167.89	385.05	35.17		588.11
Elevated conc, 1-way beam & slab - 15ft span	03310-240-2700	C.Y.	C-14B	20.59	286.34	505.24	44.75		836.33
Elevated conc, 1-way beam & slab - 25ft span	03310-240-2750	C.Y.	C-14B	28.36	272.95	366.82	32.49		672.26
Bat Gate/Foam Plug Installation									
Bat Gate		ea.			3,468.64				
Culvert Gate		ea.			6,937.27				
Adit Foam Plug		ea./C.Y.			346.86				
Production Opening Foam Plug		ea./C.Y.			346.86				
NOTES:									
Bat Gate Source:	BP22+3%								
Foam Plug Source:	BP22+3%								

Closure Cost Estimate
Misc. Unit Costs

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Misc. Linear Projects

Hourly productivity rates and crew composition from Means Heavy Construction 2005 Edition by permission of R.S.Means/Reed Construction Data .

All equipment, labor and material unit costs are from Labor Costs, Equipment Costs and Material Costs spreadsheets

	Means Number	Unit	Crew	Daily Output	Materials	Labor	Equipment	Premium	Total
Fencing Installation									
Barbed 3-strand	02820-170-1650	L.F.	B-80A	760	0.53	2.11	0.33		2.97
Barbed 4-strand	extrapolated	L.F.	B-80A	570	0.70	2.82	0.43		3.95
Barbed 5-strand	02820-130-0920	L.F.	B-80A	456	0.88	3.52	0.54		4.94
Chain link 8 ft -10 ft Install	02820-130-0920	L.F.	B-80C	180	39.14	8.92	1.38		49.44
Wood stockade fence 6 ft high - Install	02820-510-1240	L.F.	B-80C	150	16.48	10.71	1.65		28.84
	user	L.F.							0.00
	user	L.F.							0.00
	user	L.F.							0.00
	user	L.F.							0.00
Fencing Removal									
Barbed 3-strand Removal	02220-220-1600	L.F.	2 Clab	430		2.94	0.58		3.52
Barbed 4-strand Removal	extrapolated	L.F.	2 Clab	355		3.56	0.70		4.26
Barbed 5-strand Removal	02220-220-1650	L.F.	2 Clab	280		4.51	0.88		5.39
Chain link 8 ft -10 ft Removal	02220-220-1700	L.F.	B-6	445		2.85	0.99		3.84
Wood, all types 4 ft -6 ft high Removal	02220-220-1775	L.F.	2 Clab	430		2.94	0.58		3.52
	user	L.F.							0.00
	user	L.F.							0.00
	user	L.F.							0.00
	user	L.F.							0.00
Culvert Removal									
12 in (300 mm) Diameter	02220-220-2900	L.F.	B-6	175		7.25	2.53		9.78
18 in (450 mm) Diameter	02220-220-2930	L.F.	B-6	150		8.46	2.95		11.41
24 in (600 mm) Diameter	02220-220-2960	L.F.	B-6	120		10.58	3.68		14.26
36 in (1m) Diameter	02220-220-3000	L.F.	B-6	90		14.10	4.91		19.01
Pipeline Removal									
Plastic Pipe 3/4 in (mm) - 4 in (100 mm) diameter	02220-381-1600	L.F.	B-20	700		2.90	0.35		3.25
6 in (150 mm) - 8 in (200 mm)	02220-381-1700	L.F.	B-20	500		4.06	0.50		4.56
10 in (250 mm) - 18 in (450 mm)	02220-381-1800	L.F.	B-20	300		6.77	0.83		7.60
20 in (500 mm) - 36 in (1 m)	02220-381-1900	L.F.	B-20	200		10.16	1.24		11.40
Pipe and Drainpipe Installation									
Water 4in (100mm) 40ft (12m) length, welded HDPE	02510-760-0100	L.F.	B-22A	400	2.78	6.97	5.06		14.81
Water 6in (150mm) 40ft (12m) length, welded HDPE	02510-760-0200	L.F.	B-22A	380	6.03	7.33	5.32		18.68
Water 12in (300mm) 40ft (12m) length, welded HDPE	02510-760-0500	L.F.	B-22A	260	0.00	10.72	7.78		18.50
Drain 4in (100mm) perforated PVC	02620-630-2100	L.F.	B-14	315	1.79	10.49	1.76		14.04
Drain 6in (150mm) perforated PVC	02620-630-2110	L.F.	B-14	300	4.35	11.02	1.85		17.22
Drain 4in (100mm) corrugated, perf or plain	02620-660-0040	L.F.	2 Clab	1200	0.80	1.05	0.21		2.06
Drain 6in (150mm) corrugated., perf or plain	02620-660-0060	L.F.	2 Clab	900	2.25	1.40	0.28		3.93

**Closure Cost Estimate
Misc. Unit Costs**

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Note: HDPE Water Pipe in 40ft (12m) lengths, welded

Closure Cost Estimate
Misc. Unit Costs

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Drain Rock Preparation

Crushing		C.Y.						0.52
Screening		C.Y.						0.52
TOTAL								1.03

Misc.

Backhoe work	02210-700-0120	C.Y.	B-11M	28	21.14	10.92		32.06
--------------	----------------	------	-------	----	-------	-------	--	-------

Powerline and Transformer Removal

Single Pole Powerlines		mile						48,208.12
Double Pole Powerlines		mile						55,094.70
Substation		ea.						60,766.91

NOTES:

Single Pole Source:	BP22+3%
Double Pole Source:	BP22+3%
Transformer Source:	BP22+3%

Erosion and Sedimentation Control

Hourly productivity rates and crew composition from Means Heavy Construction 2005 Edition by permission of R.S.Means/Reed Construction Data .

All equipment, labor and material unit costs are from Labor Costs, Equipment Costs and Material Costs spreadsheets

* some crews modified to reflect actual crews used for riprap placement at mine sites

	Means Number	Unit	Crew	Means Daily Output	Materials	Labor	Equipment	User Daily Output	Total
--	--------------	------	------	--------------------	-----------	-------	-----------	-------------------	-------

Rip-Rap & Rock Lining

Rip-Rap 3/8 to 1/4 CY pieces, grouted	02370-450-0110	S.Y.	B-13	80	25.75	34.09	9.12		68.96
Rip-Rap 18-inch min thick, no grout	02370-450-0200	S.Y.	B-13	53	7.88	51.46	13.76		73.10
Rip-Rap 3/8 to 1/4 CY pieces, grouted	02370-450-0110*	S.Y.	B-12G	80	25.75	22.01	21.62		69.38
Rip-Rap 18-inch min thick, no grout	02370-450-0200*	S.Y.	B-12G	53	7.88	33.23	32.63		73.74
Gabions, 6 in (150 mm) deep	02370-450-0400	S.Y.	B-13	200	7.26	13.64	3.65		24.55
Gabions, 9 in (250 mm) deep	02370-450-0500	S.Y.	B-13	163	10.15	16.73	4.48		31.36
Gabions, 12 in (300 mm) deep	02370-450-0200	S.Y.	B-13	153	14.73	17.82	4.77		37.32
Gabions, 18 in (450 mm) deep	02370-450-0200	S.Y.	B-13	102	18.90	26.74	7.15		52.79
Gabions, 36 in (1m) deep	02370-450-0200	S.Y.	B-13	60	31.93	45.45	12.16		89.54

HDEP Liner Installation

Finish grading large area	2310-100-0100	S.F.	B-11L	54000	0.02	0.02		0.04
Compaction-riding, vibrating roller - 12in (300mm) lifts	2315-310-5100	C.Y.	B-10Y	2600	0.35	0.19		0.54
Geotextile	2660-610-0010	S.F.	3 Skwk	1600	1.02	0.51		1.53
Geonet	2660-610-0010	S.F.	3 Skwk	1600	1.02	0.51		1.53
Geogrid	2660-610-0010	S.F.	3 Skwk	1600	1.02	0.51		1.53
60 mil HDPE	2660-610-0010	S.F.	3 Skwk	1600	0.59	1.02	0.51	2.12
80 mil HDPE	user	S.F.	3 Skwk	149	\$9.00	10.98	5.45	25.43
40 mil VLDPE	user	S.F.	3 Skwk	150	\$7.00	10.91	5.42	23.33
	user	S.F.	3 Skwk					0.00

Closure Cost Estimate
Misc. Unit Costs

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

	user	S.F.	3 Skwk				0.00
--	------	------	--------	--	--	--	------

Closure Cost Estimate
Misc. Unit Costs

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Transport Costs

Ship/Barge Transport Cost		cost/lb/mi							
Rail Transport Cost		cost/lb/mi							
Air Transport Cost		cost/lb/mi							
Escort Vehicle Deadhead Rate (\$/mi)		cost/lb/mi							

Construction Management Support

Office Trailer, Furnished, no hook-ups	0150-500-0250	mo.		203.94				203.94
Toilet Portable, chemical	1590-400-6410	mo.		220.63				220.63
TOTAL				424.57				424.57

Pump and Casing Removal

	Pump Type	Measurement	Unit			Labor	Equipment		Total
--	-----------	-------------	------	--	--	-------	-----------	--	-------

Pump Removal

Submersible		L.F.			7.96	20.01		27.97
Line Shaft		L.F.			7.96	20.01		27.97

NOTES:

Pump Removal Source: BP22+3%

Closure Cost Estimate
Fleets (Crews)

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

EQUIPMENT FLEETS						
ACTIVITY AND FLEET		Standard Labor Crew	User Defined Labor Crew	EQUIPMENT UNIT COST (Hourly)	TOTAL LABOR UNIT COST (Hourly)	TOTAL COST (Hourly)
RIPPING						
Rip road Waste rock dumps, heaps, tails - rip flat surfaces Surface preparation Scarify						
Small Dozer w/ multi-shank						
D7E				105.56	72.90	178.46
Totals				105.56	72.90	178.46
Medium Dozer w/ multi-shank						
D9T				257.32	72.90	330.22
Totals				257.32	72.90	330.22
Large Dozer w/ multi-shank						
D10T2				354.81	72.90	427.71
Totals				354.81	72.90	427.71
Grader w/ multi-shank						
16M3				202.34	73.98	276.32
Totals				202.34	73.98	276.32
GRADING						
Grading storage and structure areas Grading waste rock dumps and heaps Grading landfills Constructing pit safety berms						
Small Dozer Fleet						
D7E				105.56	72.90	178.46
Totals				105.56	72.90	178.46
Medium Dozer Fleet						
D9T				257.32	72.90	330.22
Totals				257.32	72.90	330.22
Large Dozer Fleet						
D10T2				354.81	72.90	427.71
Totals				354.81	72.90	427.71
EXPLORATION GRADING						
Backfilling and grading exploration trenches Grading flat exploration roads						
Small Dozer Fleet						
D6T				100.55	72.90	173.45
Totals				100.55	72.90	173.45
Medium Dozer Fleet						
D7E				105.56	72.90	178.46
Totals				105.56	72.90	178.46
Large Dozer Fleet						
D8T				192.13	72.90	265.03
Totals				192.13	72.90	265.03

Closure Cost Estimate
Fleets (Crews)

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

EQUIPMENT FLEETS						
ACTIVITY AND FLEET		Standard Labor Crew	User Defined Labor Crew	EQUIPMENT UNIT COST (Hourly)	TOTAL LABOR UNIT COST (Hourly)	TOTAL COST (Hourly)
EXCAVATING						
Earthen Berms Diversion ditch excavation and backfill Underground openings backfill - excavate and place Pit berm construction (excavator option)						
Small Excavator						
325F				77.03	73.98	151.01
	Totals			77.03	73.98	151.01
Medium Excavator						
349F				136.87	73.98	210.85
	Totals			136.87	73.98	210.85
Large Excavator						
390F				203.65	73.98	277.63
	Totals			203.65	73.98	277.63
EXCAVATE AND RECONTOUR						
Recontour large roads (haul roads, access roads, etc.) Ponds - Excavate and pull liner and bury						
Small Excavator + Dozer						
325F				77.03	73.98	151.01
D7E				105.56	72.90	178.46
	Total Equipment			182.59	146.88	329.47
Medium Excavator + Dozer						
349F				136.87	73.98	210.85
D9T				257.32	72.90	330.22
	Totals			394.19	146.88	541.07
Large Excavator + Dozer						
390F				203.65	73.98	277.63
D10T2				354.81	72.90	427.71
	Totals			558.46	146.88	705.34
EXPLORATION ROAD/PAD RECONTOUR						
Recontour small roads (exploration roads, service roads, etc.) Cut and Fill reclamation on slopes Drill pad recountour Drill sump backfill						
Small Dozer						
D6T				100.55	72.90	173.45
	Totals			100.55	72.90	173.45
Large Dozer						
D8T				192.13	72.90	265.03
	Totals			192.13	72.90	265.03
Grader						
14M				137.92	73.98	211.90
	Totals			137.92	73.98	211.90
Small Excavator						
325F				77.03	73.98	151.01
	Totals			77.03	73.98	151.01
Medium Excavator						
330F				99.30	73.98	173.28

***Closure Cost Estimate
Fleets (Crews)***

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

EQUIPMENT FLEETS						
ACTIVITY AND FLEET		Standard Labor Crew	User Defined Labor Crew	EQUIPMENT UNIT COST (Hourly)	TOTAL LABOR UNIT COST (Hourly)	TOTAL COST (Hourly)
	Totals			99.30	73.98	173.28

**Closure Cost Estimate
Fleets (Crews)**

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

EQUIPMENT FLEETS						
ACTIVITY AND FLEET		Standard Labor Crew	User Defined Labor Crew	EQUIPMENT UNIT COST (Hourly)	TOTAL LABOR UNIT COST (Hourly)	TOTAL COST (Hourly)
LOAD CRUSHER/TRAM BACKFILL						
Load crusher with wheeled loader Tram backfill into portals						
Small Crusher Loader Fleet						
966M		1		108.18	73.98	182.16
Totals				108.18	73.98	182.16
Medium Crusher Loader Fleet						
988K		1		222.95	73.98	296.93
Totals				222.95	73.98	296.93
Large Crusher Loader Fleet						
992K		1		552.68	73.98	626.66
Totals				552.68	73.98	626.66
Extra Large Crusher Loader Fleet						
994K		1		649.48	73.98	723.46
Totals				649.48	73.98	723.46
COMPACT COVER						
From Means Heavy Construction - Costs in Misc. Unit Costs. Assumes compaction-riding, vibrating roller - 12in (300mm) lifts						
Compactor						
CS54B		1		62.62	72.17	134.79
Totals				62.62	72.17	134.79
LOAD, HAUL AND PLACE MATERIAL						
Rock placement Haul overburden for backfill Haul borrow for backfill Haul cover or growth media						
Small Truck/Loader Fleet						
725C2				142.22	43.71	185.93
966M	Loader			108.18	73.98	182.16
D7E		1		105.56	72.90	178.46
Totals				355.96	190.59	546.55
Medium Truck/Loader Fleet						
740C				159.65	43.71	203.36
988K	Loader			222.95	73.98	296.93
D8T		1		192.13	72.90	265.03
Totals				574.73	190.59	765.32
Large Truck/Loader Fleet						
777G				440.57	43.71	484.28
992K	Loader			552.68	73.98	626.66
D10T2		1		354.81	72.90	427.71
Totals				1,348.06	190.59	1,538.65
Extra Large Truck/Loader Fleet						
793F				661.86	43.71	705.57
994K	Loader			649.48	73.98	723.46
D10T2		1		354.81	72.90	427.71
Totals				1,666.15	190.59	1,856.74
Scraper/Dozer Fleet						
631K				238.57	72.90	311.47
D10T2				354.81	72.90	427.71
D7E		1		105.56	72.90	178.46
Totals				698.94	218.70	917.64

**Closure Cost Estimate
Fleets (Crews)**

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

EQUIPMENT FLEETS						
ACTIVITY AND FLEET	Standard Labor Crew	User Defined Labor Crew	EQUIPMENT UNIT COST (Hourly)	TOTAL LABOR UNIT COST (Hourly)	TOTAL COST (Hourly)	
Tandem Scraper Fleet						
637K			334.48	73.98	408.46	
D7E	1		105.56	72.90	178.46	
Totals			440.04	146.88	586.92	
MISC. LOAD AND HAUL AND EARTHWORKS						
Sludge removal						
Drainage controls						
Misc. - Cat 325B Excavator / 10-12 yd3 Truck						
325F			77.03	73.98	151.01	
Dump Truck (10-12 yd3)			92.84	43.71	136.55	
Totals			169.87	117.69	287.56	
Misc. - Cat D9R Dozer/ Loader (5 yd3) / 10-12 yd3 Truck						
D9T			257.32	72.90	330.22	
966M			108.18	73.98	182.16	
Dump Truck (10-12 yd3)			92.84	43.71	136.55	
Totals			458.34	190.59	648.93	
Misc. - Cat D6 Dozer / Cat 966 Loader / 10-12 yd3 Truck						
D6T			100.55	72.90	173.45	
966M			108.18	73.98	182.16	
Dump Truck (10-12 yd3)			92.84	43.71	136.55	
Totals			301.57	190.59	492.16	
LINER REMOVAL						
Liner removal						
Small - Cat 325B Excavator w/ H140D s Hammer						
325F			77.03	73.98	151.01	
General Laborer	2		0.00	85.76	85.76	
Totals			77.03	159.74	236.77	

**Closure Cost Estimate
Fleets (Crews)**

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

EQUIPMENT FLEETS						
ACTIVITY AND FLEET		Standard Labor Crew	User Defined Labor Crew	EQUIPMENT UNIT COST (Hourly)	TOTAL LABOR UNIT COST (Hourly)	TOTAL COST (Hourly)
CONCRETE BREAKING						
Slab demolition						
Footing demolition						
Wall demolition						
Small - Cat 325F Excavator w/ H120E s Hammer						
325F				77.03	73.98	151.01
H120Es (fits 325)				44.49	0.00	44.49
D9T				257.32	72.90	330.22
Totals				378.84	146.88	525.72
Medium - Cat 349F Excavator w/ H160E s Hammer						
349F				136.87	73.98	210.85
H160Es (fits 349)				92.81	0.00	92.81
D9T				257.32	72.90	330.22
Totals				487.00	146.88	633.88
Large - Cat 374F Excavator w/ H180E s Hammer						
374F				169.10	73.98	243.08
H180Es (fits 374/390)				123.34	0.00	123.34
D9T				257.32	72.90	330.22
Totals				549.76	146.88	696.64
DRILL HOLE ABANDONMENT						
Drill Hole - Grout or Cement						
Pump (plugging) Drill Rig				243.30	72.90	316.20
Driller's Helper		2		0.00	86.38	86.38
Totals				243.30	159.28	402.58
Drill Hole - Inert Media (Means Crew B-11M+ 1 Laborer)						
420F2				38.22	73.98	112.20
General Laborer		1		0.00	42.88	42.88
Totals				38.22	116.86	155.08
Drill Hole - Casing Perforation or Removal						
Heavy Duty Drill Rig				248.46	72.90	321.36
Driller's Helper		2		0.00	86.38	86.38
Totals				248.46	159.28	407.74
MAINTENANCE FLEET						
Road Grading, Dust Suppression, Clean Up						
Maintenance - Small Water Truck and Cat 14G Grader						
613E (5,000 gal)				68.90	43.71	112.61
12M2				97.15	73.98	171.13
Totals				166.05	117.69	283.74
Maintenance - Medium Water Truck and Cat 16G Grader						
613E (5,000 gal)				68.90	43.71	112.61
14M				137.92	73.98	211.90
Totals				206.82	117.69	324.51
Maintenance - Large Water Truck and Cat 16G Grader						
621E (8,000 gal)				118.70	43.71	162.41
16M3				202.34	73.98	276.32
Totals				321.04	117.69	438.73
PROJECT SUPERVISION						
Foreman		1		0.00	95.40	95.40
Supervisor's Truck		1		26.97	72.17	99.14
Totals				26.97	167.57	194.54

**Closure Cost Estimate
Fleets (Crews)**

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

EQUIPMENT FLEETS						
ACTIVITY AND FLEET		Standard Labor Crew	User Defined Labor Crew	EQUIPMENT UNIT COST (Hourly)	TOTAL LABOR UNIT COST (Hourly)	TOTAL COST (Hourly)
MEANS CREW DEFINITIONS						
Crew composition from Means Heavy Construction 2005 Edition by permission of R.S.Means/Reed Construction Data . For use with misc. unit costs where Means is the source for productivity						
1 Clab - Seedling Planting/Block Wall Demolition						
General Laborer		1		0.00	42.88	42.88
	Totals			0.00	42.88	42.88
2 Clab - Barbed Wire/Wood Fence Removal, Drainpipe Installation, Pumping, Evaporation						
General Laborer		2		0.00	85.76	85.76
Light Truck - 1.5 Ton		1		30.97	72.17	103.14
	Totals			30.97	157.93	188.90
2 Clab + Excavator - Pond Liner Cut and Fold						
General Laborer		2		0.00	85.76	85.76
325F				77.03	73.98	151.01
	Totals			77.03	159.74	236.77
2 Clab + Welder - Bat Gates						
General Laborer		2		0.00	85.76	85.76
Welding Equipment				25.29	73.98	99.27
Light Truck - 1.5 Ton		1		30.97	72.17	103.14
	Totals			56.26	231.91	288.17
3 Clab - Foam Adit Plugs						
General Laborer		2		0.00	85.76	85.76
420F2				38.22	73.98	112.20
Light Truck - 1.5 Ton		1		30.97	72.17	103.14
	Totals			69.19	231.91	301.10
3 Clab + Welder - Culvert Bat Gate						
General Laborer		2		0.00	85.76	85.76
Welding Equipment				25.29	73.98	99.27
420F2				38.22	73.98	112.20
Light Truck - 1.5 Ton		1		30.97	72.17	103.14
	Totals			94.48	305.89	400.37
3 Clab D - 3 Laborers + Foreman - Decontamination						
General Laborer		3		0.00	128.64	128.64
Foreman		1		0.00	95.40	95.40
Supervisor's Truck		1		26.97	72.17	99.14
Light Truck - 1.5 Ton		1		30.97	72.17	103.14
	Totals			57.94	368.38	426.32
3 SKWK - Liner Installation						
Skilled Laborer		3		0.00	130.50	130.50
HDEP Welder (pipe or liner)		1		63.36	0.00	63.36
420F2		1		38.22	73.98	112.20
				0.00		0.00
				0.00		0.00
				0.00		0.00
	Totals			101.58	204.48	306.06

Closure Cost Estimate Fleets (Crews)

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

EQUIPMENT FLEETS						
ACTIVITY AND FLEET		Standard Labor Crew	User Defined Labor Crew	EQUIPMENT UNIT COST (Hourly)	TOTAL LABOR UNIT COST (Hourly)	TOTAL COST (Hourly)
B-3 - Small Building Demolition						
LABOR						
General Laborer		2		0.00	85.76	85.76
Foreman		1		0.00	95.40	95.40
				0.00		0.00
				0.00		0.00
				0.00		0.00
				0.00		0.00
EQUIPMENT						
930M		1		55.24	72.90	128.14
Dump Truck (10-12 yd3)		2		185.68	87.42	273.10
				0.00		0.00
				0.00		0.00
				0.00		0.00
				0.00		0.00
				0.00		0.00
				0.00		0.00
				0.00		0.00
Totals				240.92	341.48	582.40
B-6 - Chain Link Fence/Culvert Removal						
General Laborer		2		0.00	85.76	85.76
930M		1		55.24	72.90	128.14
Totals				55.24	158.66	213.90
B-8 - Large Building Demolition						
LABOR						
General Laborer		2		0.00	85.76	85.76
Foreman		1		0.00	95.40	95.40
				0.00		0.00
				0.00		0.00
				0.00		0.00
EQUIPMENT						
930M		1		55.24	72.90	128.14
20 Ton Crane		1		89.38	73.98	163.36
Dump Truck (10-12 yd3)		2		185.68	87.42	273.10
				0.00		0.00
				0.00		0.00
				0.00		0.00
				0.00		0.00
				0.00		0.00
				0.00		0.00
				0.00		0.00
				0.00		0.00
				0.00		0.00
				0.00		0.00
				0.00		0.00
				0.00		0.00
Totals				330.30	415.46	745.76
B-9 - Concrete Wall Demolition						
General Laborer		4		0.00	171.52	171.52
Foreman		1		0.00	95.40	95.40
Air Compressor + tools				40.70	70.34	111.04
Totals				40.70	337.26	377.96

**Closure Cost Estimate
Fleets (Crews)**

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsxm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsxm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

EQUIPMENT FLEETS						
ACTIVITY AND FLEET		Standard Labor Crew	User Defined Labor Crew	EQUIPMENT UNIT COST (Hourly)	TOTAL LABOR UNIT COST (Hourly)	TOTAL COST (Hourly)
B-10Y - General Compaction						
General Laborer		1		0.00	42.88	42.88
CS54B		1		62.62	72.17	134.79
Totals				62.62	115.05	177.67
B-11L - Fine Grading for Evaporation Pond Liner Base						
General Laborer		1		0.00	42.88	42.88
14M		1		137.92	73.98	211.90
Totals				137.92	116.86	254.78
B-11M - Backhoe Work						
420F2		1		38.22	73.98	112.20
Totals				38.22	73.98	112.20
B-12G - Rip-Rap Machine Placed (Modified)						
General Laborer		2		0.00	85.76	85.76
966M		1		108.18	73.98	182.16
325F		1		77.03	73.98	151.01
Light Truck - 1.5 Ton		1		30.97	72.17	103.14
Totals				216.18	220.13	436.31
B-13 - Grouted Rip-Rap & Gabion Baskets						
General Laborer		4		0.00	171.52	171.52
Foreman		1		0.00	95.40	95.40
50 Ton Crane		1		91.19	73.98	165.17
Totals				91.19	340.90	432.09
B-14 PVC Drain Pipe Installation						
Foreman		1		0.00	95.40	95.40
General Laborer		4		0.00	171.52	171.52
420F2		1		38.22	73.98	112.20
Light Truck - 1.5 Ton		1		30.97	72.17	103.14
Totals				69.19	413.07	482.26
B-20 - Remove Pipelines						
Foreman		1		0.00	95.40	95.40
Skilled Laborer		1		0.00	43.50	43.50
General Laborer		1		0.00	42.88	42.88
Light Truck - 1.5 Ton		1		30.97	72.17	103.14
Totals				30.97	253.95	284.92
B-22A - HDEP Installation - Pipe or Liner						
Skilled Laborer		1		0.00	43.50	43.50
General Laborer		2		0.00	85.76	85.76
D7E		1		105.56	72.90	178.46
Light Truck - 1.5 Ton		1		30.97	72.17	103.14
420F2		1		38.22	73.98	112.20
Generator 5KW		1		14.82	0.00	14.82
HDEP Welder (pipe or liner)		1		63.36	0.00	63.36
Totals				252.93	348.31	601.24
B-34N - Equipment Mobilization (40-ton)						
Skilled Laborer		1		0.00	43.50	43.50
General Laborer		2		0.00	85.76	85.76
D7E		1		105.56	72.90	178.46
Light Truck - 1.5 Ton		1		30.97	72.17	103.14
420F2		1		38.22	73.98	112.20
Generator 5KW		1		14.82	0.00	14.82
HDEP Welder (pipe or liner)		1		63.36	0.00	63.36
Totals				252.93	348.31	601.24

**Closure Cost Estimate
Fleets (Crews)**

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

EQUIPMENT FLEETS						
ACTIVITY AND FLEET		Standard Labor Crew	User Defined Labor Crew	EQUIPMENT UNIT COST (Hourly)	TOTAL LABOR UNIT COST (Hourly)	TOTAL COST (Hourly)
B-34U - Equipment Mobilization (20-ton)						
Skilled Laborer		1		0.00	43.50	43.50
General Laborer		2		0.00	85.76	85.76
D7E		1		105.56	72.90	178.46
Light Truck - 1.5 Ton		1		30.97	72.17	103.14
420F2		1		38.22	73.98	112.20
Generator 5KW		1		14.82	0.00	14.82
HDEP Welder (pipe or liner)		1		63.36	0.00	63.36
Totals				252.93	348.31	601.24
B-34V - Equipment Mobilization (50-ton)						
Skilled Laborer		1		0.00	43.50	43.50
General Laborer		2		0.00	85.76	85.76
D7E		1		105.56	72.90	178.46
Light Truck - 1.5 Ton		1		30.97	72.17	103.14
420F2		1		38.22	73.98	112.20
Generator 5KW		1		14.82	0.00	14.82
HDEP Welder (pipe or liner)		1		63.36	0.00	63.36
Totals				252.93	348.31	601.24
B-80A - Install Barbed Wire Fence						
General Laborer		3		0.00	128.64	128.64
Light Truck - 1.5 Ton		1		30.97	72.17	103.14
Totals				30.97	200.81	231.78
B-80C - Install Chain Link Fence (Flatbed truck has small crane)						
General Laborer		3		0.00	128.64	128.64
Light Truck - 1.5 Ton		1		30.97	72.17	103.14
Totals				30.97	200.81	231.78
C-14B - Elevated Concrete Slabs (Reinforced Concrete Shaft Covers)						
Foreman		1		0.00	95.40	95.40
Supervisor's Truck		1		26.97	72.17	99.14
Carpenter		16		0.00	716.96	716.96
General Laborer		2		0.00	85.76	85.76
Rodmen (reinforcing concrete)		4		0.00	171.52	171.52
Cement finisher		2		0.00	86.38	86.38
Gas Engine Vibrator		1		6.25	72.17	78.42
Concrete Pump		1		81.96	0.00	81.96
Totals				115.18	1,300.36	1,415.54
C-14D - Concrete Walls Formed in Place (Reinforced Concrete Adit Bulkheads)						
Foreman		1		0.00	95.40	95.40
Supervisor's Truck		1		26.97	72.17	99.14
Carpenter		18		0.00	806.58	806.58
General Laborer		2		0.00	85.76	85.76
Rodmen (reinforcing concrete)		2		0.00	85.76	85.76
Cement finisher		1		0.00	43.19	43.19
Gas Engine Vibrator		1		6.25	72.17	78.42
Concrete Pump		1		81.96	0.00	81.96
Totals				115.18	1,261.03	1,376.21

Closure Cost Estimate
Productivity

Productivity - Bulldozers

Dozer Specifications					
Description	D6T	D7E	D8T	D9T	D10T2
Blade Width (SU) (ft)	10.67	12.17	12.92	14.08	16.25
Shank Gauge (3 shanks) (ft)	6.58	5.92	7.08	7.67	8.67
Pocket Spacing (ft)	3.25	2.92	3.58	3.86	4.33
Ripping Width (Ripper + 1 Pocket) (ft)	9.83	8.84	10.66	11.53	13
Ripping Speed (mph)	1	1	1	1	1
Ripping Maneuver (turn) Time (min)	0.25	0.25	0.25	0.25	0.25
Altitude Deration Factor	1	0.99	1	1	1
Ripping Hourly Production (excluding maneuvering time) (ft)	5,280	5,016	5,280	5,280	5,280
	4,541				


Source: Caterpillar Performance Handbook Edition 47

Dozer Productivity vs. Grading Distance					
Average Dozing Distance (feet)	Production (LCY/hr)				
	D6T	D7E	D8T	D9T	D10T2
50	550	950	1,050	1,750	2,550
100	350	580	620	1,100	1,580
200	205	340	380	630	900
300	150	230	280	430	630
400	180	210	330	480	700
500	150	180	280	380	570
600	120	150	230	330	460

Source: Caterpillar Performance Handbook Edition 47

dozer productivity = $k \times \text{Dozing Distance}^p$
(see graph)

$k =$	9623.7	26451	23933	49152	74681	101567
$p =$	-0.727	-0.833	-0.788	-0.833	-0.844	-0.835




Closure Cost Estimate
Productivity

Productivity - Bulldozers (cont.)

% Grade vs. Dozing Factor	
% Grade	Dozing Factor
-30	1.6
-20	1.4
-10	1.2
0	1
10	0.8
20	0.55
30	0.3

Source: Caterpillar Performance Handbook Edition 47
 % Grade Dozing Factor = $-0.0214x + 0.9786$
 (see graph)



Job Condition Correction Factors - Bulldozers	
OPERATOR	Average 0.75
MATERIAL (1)	
Loose stockpile	1.2
Normal	1
Hard to cut; frozen — with tilt cylinder	0.8
Hard to drift; "dead" (dry, non-cohesive material) or very sticky material	0.8
Rock, rippled or blasted	0.6
SLOT DOZING OR SIDE BY SIDE (1)	1.2
VISIBILITY	
Good conditions	1
OPERATOR SKILL	Average 0.75
JOB EFFICIENCY	
50 min/hr	0.83

(1) Selected in facility worksheets.
 Other factors included as standard factors.
 Source: Caterpillar Performance Handbook Edition 47

Material Densities(1)	
Material	Ib/yd ³
Alluvium	2,900
Basalt	3,300
Clay - Dry	2,500
Granite - broken	2,800
Gravel	2,550
Limestone - broken	2,600
Limestone - crushed	2,600
Sandstone	2,550
Shale	2,100
Stone - crushed	2,700
Tailings - Coarse (dry, loose sand)	2,400
Tailings - Slimes (loose sand & clay)	2,700
Topsoil	1,600

(1) Source: Caterpillar Performance Handbook Edition 47

Note: uses Sand & Gravel - Dry from Caterpillar Handbook

Closure Cost Estimate
Productivity

Productivity - Scrapers

Scraper Specifications		
Description	631K	637K
Empty Weight (lb)	102,750	112,760
Payload Capacity (yd ³)		
Struck	24	24
Heaped	34	34
Average	29	29
Loaded by	One D10	Self*
Load Time (min)	0.50	0.50
Maneuver and Spread (min)	0.70	0.60
Operator Skill	1.00	1.00
Job Efficiency	0.83	0.83
Rolling Resistance**	2.50	2.50
Altitude Deration Factor	0.97	0.8

* Requires pass undulating, maintained fairly regularly, watered

Source: Caterpillar Performance Handbook Edition 47

Weight of Materials			Scaper Load (lb/yd ³)	Loaded Weight (lb)	Downhill Speed (mph) - Grade Retarding vs. Effective Grade (%Grade - Rolling Resistance)										637K PP										
					18	16	14	12	10	8	6	4	2	18	16	14	12	10	8	6	4	2			
Alluvium	2,900	84,100	186,850	8	8	8	8	10.6	14.3	19.2	26	35	196,860	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6		
Basalt	3,300	95,700	198,450	8	8	8	8	10.6	14.3	19.2	26	35	208,460	8	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	
Clay - Dry	2,500	72,500	175,250	8	8	8	8	10.6	10.6	14.3	19.2	26	35	185,260	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	
Granite - broken	2,800	81,200	183,950	8	8	8	8	10.6	14.3	19.2	26	35	193,960	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6		
Gravel	2,550	73,950	176,700	8	8	8	8	10.6	10.6	14.3	19.2	26	35	186,710	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	
Limestone - broken	2,600	75,400	178,150	8	8	8	8	10.6	14.3	19.2	26	35	188,160	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6		
Limestone - crushed	2,600	75,400	178,150	8	8	8	8	10.6	14.3	19.2	26	35	188,160	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6		
Sandstone	2,550	73,950	176,700	8	8	8	8	10.6	10.6	14.3	19.2	26	35	186,710	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	
Shale	2,100	60,900	163,650	8	8	8	8	10.6	10.6	14.3	19.2	35	35	173,660	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	
Stone - crushed	2,700	78,300	181,050	8	8	8	8	10.6	14.3	19.2	26	35	191,060	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6		
Tailings - Coarse (dry, loose sand)	2,400	69,600	172,350	8	8	8	8	10.6	10.6	14.3	19.2	35	35	182,360	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	
Tailings - Slimes (loose sand & clay)	2,700	78,300	181,050	8	8	8	8	10.6	14.3	19.2	26	35	191,060	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6		
Topsoil	1,600	46,400	149,150	8	8	10.6	14.3	19.2	26	35	35	35	159,160	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6	10.6		
			Empty	14.3	14.3	14.3	14.3	19.2	19.2	26	35	35	35	Empty	14.2	19.2	19.2	19.2	19.2	19.2	19.2	19.2	19.2	19.2	19.2

Source: Caterpillar Performance Handbook Edition 46

Weight of Materials			Scaper Load (lb/yd ³)	Loaded Weight (lb)	Uphill Speed (mph) - Rimpull vs. Total Resistance (%Grade + Rolling Resistance)										637K PP									
					18	16	14	12	10	8	6	4	2	18	16	14	12	10	8	6	4	2		
Alluvium	2,900	84,100	186,850	4	5.5	6.5	7.4	9	11.2	15	22.3	33.2	196,860	6.7	7.6	8.7	9.4	12	15.2	20.5	29.8	35		
Basalt	3,300	95,700	198,450	3.9	4.1	6.1	7	8.5	11	14	22.3	32	208,460	6.5	6.9	8.3	9.2	11.5	14.2	19.1	28.8	35		
Clay - Dry	2,500	72,500	175,250	4.1	6.1	6.9	8.2	9.2	12	16.2	23	33	185,260	6.9	8.2	9	10.7	12.5	15.9	21.6	31	35		
Granite - broken	2,800	81,200	183,950	4.1	6	6.6	7.8	9	11.5	15.9	23	32	193,960	6.8	7.8	8.8	9.6	12	15.3	20.9	30.2	35		
Gravel	2,550	73,950	176,700	4.2	6.1	6.8	8.8	9.2	11.9	16	23.2	33	186,710	6.9	8.2	9	10.6	12.5	15.8	21.5	30.8	35		
Limestone - broken	2,600	75,400	178,150	4.1	6	6.7	8.2	9	11.8	15.8	23	32	188,160	6.9	8.1	9	10.4	12.5	15.7	21.3	30.8	35		
Limestone - crushed	2,600	75,400	178,150	4.1	6	6.7	8.2	9	11.8	15.8	23	32	188,160	6.9	8.1	9	10.4	12.5	15.7	21.3	30.8	35		
Sandstone	2,550	73,950	176,700	4.2	6.1	6.8	8.8	9.2	11.9	16	23.2	33	186,710	6.9	8.2	9	10.6	12.5	15.8	21.5	30.8	35		
Shale	2,100	60,900	163,650	5.8	6.5	7	8.8	9.5	12.5	16.6	26	34	173,660	7.8	8.7	9.3	11.4	13.5	16.6	22.6	31.6	35		
Stone - crushed	2,700	78,300	181,050	4.2	6	6.6	8	9	11.4	15.5	22.5	33	191,060	6.8	8	8.9	10	12	15.5	21.1	30.4	35		
T																								

**Closure Cost Estimate
Productivity**

**Closure Cost Estimate
Productivity**

Exposure Cost Estimate Productivity

Productivity - Haul Trucks

Haul Truck Specifications							
Description	770G	773G	777G	785D	789D	793F	797F
Chassis Weight (lb)	56,144	77,582	115,171	180,827	222,233	269,006	472,880
Body Weight (lb)	17,103	24,358	35,429	50,700	58,656	59,289	97,610
Standard Liner Weight (lb)	6,195	8,218	12,555	17,886	21,367	13,688	16,870
Total Truck Weight (lb)	79,442	110,158	163,155	249,413	302,256	341,983	587,360
Payload Capacity (yd ³)							
Struck	24	34.5	54.6	77	106	173	315
Heaped	33.9	46	78.6	102	141	230	350
Average	28.7	40.25	66.6	89.5	123.5	201.5	332.5
Maneuver to Load Time (min)	0.7	0.7	0.7	0.7	0.7	0.7	0.7
Maneuver and Dump Time (min)	1.1	1.1	1.1	1.1	1.1	1.1	1.1
Operator Skill	1	1	1	1	1	1	1
Job Efficiency	0.83	0.83	0.83	0.83	0.83	0.83	0.83
Rolling Resistance**	2.5	2.5	2.5	2.5	2.5	2.5	2.5
Altitude Deration Factor	0.97	1	1	1	0.93	1	1

**A firm, smooth, rolling roadway with dirt or light surfacing, flexing slightly under load or undulating, maintained fairly regularly, watered

Source: Caterpillar Performance Handbook Edition 47

Weight of Materials				Downhill Speed (mph) - Grade Retarding vs. Effective Grade (%Grade - Rolling Resistance)																					
				770G									773G												
Material	lb/yd ³	Truck 770G Load (lb)	Truck 773G Load (lb)	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2	0	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2	0
Alluvium	2,900	83,230	116,725	162,672	7	10	10	13.5	18	18	25	35	35	226,883	10.6	10.6	10.6	10.6	19.2	19.2	19.2	35	35	35	
Basalt	3,300	94,710	132,825	174,152	7	7	10	10	13.5	18	25	35	35	242,983	10.6	10.6	10.6	10.6	14.2	19.2	19.2	35	35	35	
Clay - Dry	2,500	71,750	100,625	151,192	10	10	10	13.5	18	25	33.5	35	35	210,783	10.6	10.6	10.6	10.6	19.2	19.2	25.9	35	35	35	
Granite - broken	2,800	80,360	112,700	159,802	7	10	10	13.5	18	18	25	35	35	222,858	10.6	10.6	10.6	10.6	19.2	19.2	19.2	35	35	35	
Gravel	2,550	73,185	102,638	152,627	10	10	10	13.5	18	25	33.5	35	35	212,796	10.6	10.6	10.6	10.6	19.2	19.2	25.9	35	35	35	
Limestone - broken	2,600	74,620	104,650	154,062	7	10	10	13.5	18	25	33.5	35	35	214,808	10.6	10.6	10.6	10.6	19.2	19.2	25.9	35	35	35	
Limestone - crushed	2,600	74,620	104,650	154,062	7	10	10	13.5	18	25	33.5	35	35	214,808	10.6	10.6	10.6	10.6	19.2	19.2	25.9	35	35	35	
Sandstone	2,550	73,185	102,638	152,627	10	10	10	13.5	18	25	33.5	35	35	212,796	10.6	10.6	10.6	10.6	19.2	19.2	25.9	35	35	35	
Shale	2,100	60,270	84,525	139,712	10	10	13.5	18	18	25	33.5	35	35	194,683	10.6	10.6	10.6	10.6	19.2	19.2	25.9	35	35	35	
Stone - crushed	2,700	77,490	108,675	156,932	10	10	10	13.5	18	25	33.5	35	35	218,833	10.6	10.6	10.6	10.6	19.2	19.2	25.9	35	35	35	
Tailings - Coarse (dry, loose sand)	2,400	68,880	96,600	148,322	10	10	10	13.5	18	25	33.5	35	35	206,758	10.6	10.6	10.6	10.6	19.2	19.2	25.9	35	35	35	
Tailings - Slimes (loose sand & clay)	2,700	77,490	108,675	156,932	10	10	10	13.5	18	25	33.5	35	35	218,833	10.6	10.6	10.6	10.6	19.2	19.2	25.9	35	35	35	
Topsoil	1,600	45,920	64,400	125,362	10	13.5	13.5	18	25	25	33.5	35	35	174,558	10.6	10.6	10.6	14.2	19.2	19.2	25.9	35	35	35	
				Empty	18	25	33.5	33.5	33.5	35	35	35	35	Empty	14.2	19.2	19.2	25.9	35	35	35	35	35	35	

Source: Caterpillar Performance Handbook Edition 4

Weight of Materials				Downhill Speed (mph) - Grade Retarding vs. Effective Grade (%Grade - Rolling Resistance)																					
				777G									785D												
Material	lb/yd ³	Truck 777G Load (lb)	Truck 785D Load (lb)	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2	0	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2	0
Alluvium	2,900	193,140	259,550	356,295	8	9	9	9	13	16.8	16.8	22.8	35	35	508,963	7.8	7.8	7.8	10.5	10.5	14.2	19.2	35	35	
Basalt	3,300	219,780	295,350	382,935	8	9	9	13	13	16.8	22.8	35	35	35	544,763	7.8	7.8	7.8	10.5	10.5	14.2	19.2	26.1	35	
Clay - Dry	2,500	166,500	223,750	329,655	9	9	13	13	17	22.8	30.6	35	35	35	473,163	7.8	7.8	10.5	10.5	14.2	14.2	19.2	35	35	
Granite - broken	2,800	186,480	250,600	349,635	9	9	9	13	17	16.8	22.8	35	35	35	500,013	7.8	7.8	7.8	10.5	10.5	14.2	19.2	35	35	
Gravel	2,550	169,830	228,225	332,985	9	9	13	13	17	22.8	30.6	35	35	35	477,638	7.8	7.8	10.5	10.5	14.2	14.2	19.2	35	35	
Limestone - broken	2,600	173,160	232,700	336,315	9	9	9	13	13	17	22.8	30.6	35	35	35	482,113	7.8	7.8	7.8	10.5	14.2	14.2	19.2	35	35
Limestone - crushed	2,600	173,160	232,700	336,315	9	9	9	9	13	17	22.8	30.6	35	35	35	482,113	7.8	7.8	7.8	10.5	14.2	14.2	19.2	35	35
Sandstone	2,550	169,830	228,225	332,985	9	9	13	13	17	22.8	30.6	35	35	35	477,638	7.8	7.8	10.5	10.5	14.2	14.2	19.2	35	35	
Shale	2,100	139,860	187,950	303,015	9	9	13	17	17	22.8	30.6	35	35	35	437,363	7.8	7.8	10.5	10.5	14.2	19.2	26.1	35	35	
Stone - crushed	2,700	179,820	241,650	342,975	9	9	9	13	17	16.8	22.8	35	35	35	491,063	7.8	7.8	7.8	10.5	10.5	14.2	19.2	35	35	
Tailings - Coarse (dry, loose sand)	2,400	159,840	214,800	322,995	9	9	13	13	17	22.8	30.6	35	35	35	464,213	7.8	7.8	10.5	10.5	14.2	19.2	19.2	35	35	
Tailings - Slimes (loose sand & clay)	2,700	179,820	241,650	342,975	9	9	9	13	17	16.8	22.8	35	35	35	491,063	7.8	7.8	10.5	10.5	14.2	14.2	19.2	35	35	
Topsoil	1,600	106,560	143,200	269,715	9	12.5	12.5	16.8	22.8	22.8	30.6	35	35	35	392,613	7.8	10.5	10.5	14.2	14.2	19.2	26.1	35	35	
				Empty	22.8	22.8	22.8	30.6	35	35	35	35	35	Empty	14.2	14.2	19.2	19.2	26.1	35	35	35	35		

Source: Caterpillar Performance Handbook Edition 4

Weight of Materials				Downhill Speed (mph) - Grade Retarding vs. Effective Grade (%Grade - Rolling Resistance)																					
				789D									793F												
Material	lb/yd ³	Truck 789D Load (lb)	Truck 793F Load (lb)	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2	0	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2	0
Alluvium	2,900	358,150	584,350	660,406	7.8	7.8	7.8	7.8	10.5	10.5	19.2	26.1	35	926,333	8.1	8.1	10.9	10.9	14.8	20	26.1	35	35	35	
Basalt	3,300	407,550	664,950	709,806	7.8	7.8	7.8	7.8	10.5	10.5	14.4	26.1	35	1,006,933	8.1	8.1	8.1	8.1	10.9	14.8	20	26.1	35	35	
Clay - Dry	2,500	308,750	503,750	611,006	7.8	7.8	7.8	7.8	10.5	10.5	14.4	19.2	26.1	35	845,733	8.1	8.1	8.1	10.9	0	14.8	20	35	35	35
Granite - broken	2,800	345,800	564,200	648,056	7.8	7.8	7.8	7.8	10.5	10.5	14.4	19.2	26.1	35	906,183	8.1	8.1	8.1	10.9	10.9	14.8	20	26.1	35	35
Gravel	2,550	314,925	513,825	617,181	7.8	7.8	7.8	7.8	10.5	10.5	14.4	19.2	26.1	35	855,808	8.1	8.1	8.1	10.9	0	14.8	20	35	35	35
Limestone - broken	2,600	321,100	523,900	623,356	7.8	7.8	7.8	7.8	10.5	10.5	14.4	19.2	26.1	35	865,883	8.1	8.1	8.1	10.9	10.9	14.8	20	35	35	35
Limestone - crushed	2,600	321,100	523,900	623,356	7.8	7.8	7.8	7.8	10.5	10.5	14.4	19.2	26.1	35	865,883	8.1	8.1	8.1	10.9	10.9	14.8	20	35	35	35
Sandstone	2,550	314,925	513,825	617,181	7.8	7.8	7.8	7.8	10.5	10.5	14.4	19.2	26.1	35	855,808	8.1	8.1	8.1	10.9	0	14.8	20	35	35	35
Shale	2,100	259,350	423,150	561,606	7.8	7.8	7.8	7.8	10.5	10.5	14.4	19.2	26.1	35	765,133	8.1	8.1	10.9	10.9	14.8	20	26.1	35	35	35
Stone - crushed	2,700	333,450	544,050	635,706	7.8	7.8	7.8	7.8	10.5	10.5	14.4	19.2	26.1	35	886,033	8.1	8.1	8.1	10.9	10.9	14.8	20	35	35	35
Tailings - Coarse (dry, loose sand)	2,400	296,400	483,600	598,656	7.8	7.8	7.8	7.8	10.5	10.5	14.4	19.2	26.1	35	825,583	8.1	8.1	8.1	10.9	14.8	14.8	20	35	35	35
Tailings - Slimes (loose sand & clay)	2,700	333,450	544,050	635,706	7.8	7.8	7.8	7.8	10.5	10.5	14.4	19.2	26.1	35	886,033	8.1	8.1	8.1	10.9	10.9	14.8	20	35	35	35
Topsoil	1,600	197,600	322,400	499,856	7.8	7.8	10.5	10.5	14.4	19.2	19.2	35	664,383	8.1	10.9	10.9	14.8	20	26.1	35	35	35	35		
				Empty	10.5	14.4	14.4	19.2	19.2	26.1	35	35	35	Empty	14.8	20	20	26.1	35	35	35	35	35		

Source: Caterpillar Performance Handbook Edition 4

Closure Cost Estimate
Productivity

Weight of Materials			Downhill Speed (mph) - Grade Retarding vs. Effective Grade (%Grade - Rolling Resistance)											
			797F											
Material	Ib/yd ³	Truck 797F Load (lb)	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2	0	
Alluvium	2,900	964,250	1,551,610	5.4	6.8	7.2	8.7	9.6	13.8	17.3	23.2	35	35	
Basalt	3,300	1,097,250	1,664,610	5.4	5.4	7.2	7.2	9.6	12.9	17.2	23.4	35	35	
Clay - Dry	2,500	831,250	1,418,610	6.3	7.2	7.5	9.6	11.4	12.9	17.2	23.4	35	35	
Granite - broken	2,800	931,000	1,518,360	5.4	6.9	7.2	9	9.6	12.9	17.2	23.4	35	35	
Gravel	2,550	847,875	1,435,235	6.3	7.2	7.2	9.6	11.2	12.9	17.2	23.4	35	35	
Limestone - broken	2,600	864,500	1,451,860	6	7.2	7.2	9.6	10.7	12.9	17.2	23.4	35	35	
Limestone - crushed	2,600	864,500	1,451,860	6	7.2	7.2	9.6	10.7	12.9	17.2	23.4	35	35	
Sandstone	2,550	847,875	1,435,235	6.3	7.2	7.2	9.6	11.2	12.9	17.2	23.4	35	35	
Shale	2,100	698,250	1,285,610	7.2	7.2	9.6	9.6	12.9	15	19.8	31.5	35	35	
Stone - crushed	2,700	897,750	1,495,110	6.8	7.2	7.2	9.6	10	12.9	17.2	23.4	35	35	
Tailings - Coarse (dry, loose sand)	2,400	798,000	1,385,360	6.6	7.2	8	9.6	11.8	12.9	17.2	26	35	35	
Tailings - Slimes (loose sand & clay)	2,700	897,750	1,485,110	6.8	7.2	7.2	9.6	10	12.9	17.2	23.4	35	35	
Topsoil	1,600	532,000	1,119,360	6.5	9.6	9.6	12.9	17.2	23.4	31.5	35	35	35	
		Empty	13.8	17.3	17.3	23.2	23.3	31.4	35	35	35	35	35	

Weight of Materials			Uphill Speed (mph) - Rimpull vs. Total Resistance (%Grade + Rolling Resistance)											
			770G											
Material	Ib/yd ³	Truck 770G Load (lb)	Truck 773G Load (lb)	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2	
Alluvium	2,900	83,230	116,725	162,672	4	5	6.3	7.5	8.9	11.3	15.2	22.3	35	226,883
Basalt	3,300	94,710	132,825	174,152	4	4.4	5.9	6.8	8.5	10.6	14.6	21.6	35	242,983
Clay - Dry	2,500	71,750	100,625	151,192	4.8	6	6.8	8.4	9.5	12.1	16.4	24.8	35	210,783
Granite - broken	2,800	80,360	112,700	159,802	4.2	5.3	6.5	12.8	14	11.6	15.5	22.5	35	222,858
Gravel	2,550	73,185	102,638	152,627	4.5	6	6.8	8.3	9.5	12	16.2	23.4	35	212,796
Limestone - broken	2,600	74,620	104,650	154,062	4.3	5.8	6.7	8.2	9.3	12	16	24.5	35	214,808
Limestone - crushed	2,600	74,620	104,650	154,062	4.3	5.8	6.7	8.2	9.3	12	16	24.5	35	214,806
Sandstone	2,550	73,185	102,638	152,627	4.5	6	6.8	8.3	9.5	12	16.2	23.4	35	212,796
Shale	2,100	60,270	84,525	139,712	5.3	6.5	7.5	8.7	10.5	12.5	16.8	27	35	194,683
Stone - crushed	2,700	77,490	108,675	156,932	4.3	5.5	6.6	8	9.2	11.8	15.8	23.1	35	218,833
Tailings - Coarse (dry, loose sand)	2,400	68,880	96,600	148,322	4.9	6.2	7.1	8.5	10	12.3	16.5	25.7	35	206,758
Tailings - Slimes (loose sand & clay)	2,700	77,490	108,675	156,932	4.3	5.5	6.6	8	9.2	11.8	15.8	23.1	35	218,833
Topsoil	1,600	45,920	64,400	125,362	6.5	7.5	8.5	9.8	11.8	15	20.2	29.5	35	174,556
		Empty	11.4	12.5	15	17	21.2	26	34.7	35	35	Empty	13.1	14.5
														16.7
														19.2
														23
														29.4
														35

Weight of Materials			Uphill Speed (mph) - Rimpull vs. Total Resistance (%Grade + Rolling Resistance)											
			773G											
Material	Ib/yd ³	Truck 770G Load (lb)	Truck 773G Load (lb)	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2	
Alluvium	2,900	83,230	116,725	162,672	4	5	6.3	7.5	8.9	11.3	15.2	22.3	35	226,883
Basalt	3,300	94,710	132,825	174,152	4	4.4	5.9	6.8	8.5	10.6	14.6	21.6	35	242,983
Clay - Dry	2,500	71,750	100,625	151,192	4.8	6	6.8	8.4	9.5	12.1	16.4	24.8	35	210,783
Granite - broken	2,800	80,360	112,700	159,802	4.2	5	6.5	12.8	14	11.6	15.5	22.5	35	222,858
Gravel	2,550	73,185	102,638	152,627	4.5	6	6.8	8.3	9.5	12	16.2	23.4	35	212,796
Limestone - broken	2,600	74,620	104,650	154,062	4.3	5.8	6.7	8.2	9.3	12	16	24.5	35	214,808
Limestone - crushed	2,600	74,620	104,650	154,062	4.3	5.8	6.7	8.2	9.3	12	16	24.5	35	214,806
Sandstone	2,550	73,185	102,638	152,627	4.5	6	6.8	8.3	9.5	12	16.2	2		

Closure Cost Estimate
Productivity

Weight of Materials			Uphill Speed (mph) - Rimpull vs. Total Resistance (%Grade + Rolling Resistance)										
			797F										
Material	Ib/yd³	Truck 797F Load (lb)	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2	
Alluvium	2,900	964,250	1,551,610	4	5	6.1	6.6	8.5	10.5	13.6	20.9	35	
Basalt	3,300	1,097,250	1,684,610	3.2	4	5.8	6.5	7.8	9	12	19.4	35	
Clay - Dry	2,500	831,250	1,418,610	4.1	6	6.5	7.8	8.8	11.2	15	21.2	35	
Granite - broken	2,800	931,000	1,518,360	4	5.5	6.2	7	8.6	10.9	14.4	21	35	
Gravel	2,550	847,875	1,435,235	4	5.9	6.5	7.5	8.8	11.2	15	21	35	
Limestone - broken	2,600	864,500	1,451,860	4	5.6	6.5	7.5	8.8	11.1	14.9	21	35	
Limestone - crushed	2,600	864,500	1,451,860	4	5.6	6.5	7.5	8.8	11.1	14.9	21	35	
Sandstone	2,550	847,875	1,435,235	4	5.9	6.5	7.5	8.8	11.2	15	21	35	
Shale	2,100	698,250	1,285,610	5.8	6.4	7	8.5	10	11.8	15.8	25.7	35	
Stone - crushed	2,700	897,750	1,485,110	4	5.5	6.4	7.1	8.8	11	14.2	21	35	
Tailings - Coarse (dry, loose sand)	2,400	798,000	1,385,360	5	6	6.5	7.9	8.8	11.5	15.4	23	35	
Tailings - Slimes (loose sand & clay)	2,700	897,750	1,485,110	4	5.5	6.4	7.1	8.8	11	14.2	21	35	
Topsoil	1,600	532,000	1,119,360	6.5	7	8.2	9.4	11.5	14.5	19.5	28.2	35	
			Empty	10.8	13.2	15.2	17	21	26.3	33.3	35	35	

Source: Caterpillar Performance Handbook Edition 47

Productivity - Articulated Trucks													
Articulated Truck Specifications													
Description	725C2	730C2	735C	740C									
Empty Weight (lb)	50,795	53,131	69,446	79,366									
Payload Capacity (yd³)													
Struck	14.4	17.4	19.6	23.5									
Heaped	19.6	23	26.8	30.1									
Average	17	20.2	23.2	26.8									
Maneuver to Load Time (min)	0.7	0.7	0.7	0.7									
Maneuver and Dump Time (min)	1.1	1.1	1.1	1.1									
Operator Skill	1	1	1	1									
Job Efficiency	0.83	0.83	0.83	0.83									
Rolling Resistance**	2.5	2.5	2.5	2.5									
Altitude Duration Factor	1	1	0.99	0.99									

*A firm, smooth, rolling roadway with dirt or light surfacing, flexing slightly under load

or undulating, maintained fairly regularly, watered

Source: Caterpillar Performance Handbook Edition 47

Weight of Materials			Downhill Speed (mph) - Grade Retarding vs. Effective Grade (%Grade - Rolling Resistance)														725C2							730C2						
																	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2	0			
Material	Ib/yd³	Truck 725C2 Load (lb)	Truck 730C2 Load (lb)	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2	0	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2	0					
Alluvium	2,900	49,300	58,580	100,095	6	7	8	9	11	13.5	18	25.5	34	34	111,711	5	10	10	10	15	23	23	35	35	35					
Basalt	3,300	56,100	66,660	106,895	6	7	8	9	11	13	17	25.5	34	34	119,791	5	10	10	10	15	23	35	35	35	35					
Clay - Dry	2,500	42,500	50,500	93,295	6	8	10	12	14.5	20	27	34	34	34	103,631	10	10	10	15	15	23	30	35	35	35					
Granite - broken	2,800	47,600	56,560	99,395	6	7	8	9	11	14	17.8	27.3	34	34	109,691	10	10	10	15	15	23	31	35	35	35					
Gravel	2,550	43,350	51,510	94,145	6	7	10	10	12	14.5	18.5	27	34	34	104,641	10	15	10	15	15	23	30	35	35	35					
Limestone - broken	2,600	44,200	52,520	94,995	6	7	8	9	11	14.5	18.5	27.5	34	34	105,651	10	15	10	15	15	23	30	35	35	35					
Limestone - crushed	2,600	44,200	52,520	94,995	6	7	8	9	11	14.5	18.5	27.5	34	34	105,651	10	15	10	15	15	23	30	35	35	35					
Sandstone	2,550	43,350	51,510	94,145	6	7	10	10	12	14.5	18.5	27	34	34	104,641	10	15	10	15	15	23	30	35	35	35					
Shale	2,100	35,700	42,420	88,495	7	8	9	10	13	15.5	20	29.5	34	34	95,551	10	15	15	23	23	35	35	35	35						
Stone - crushed	2,700	45,900	54,540	96,695	6	7	8	10	11	14.3	18	28	34	34	107,671	10	10	15	15	23	31	35	35	35						
Tailings - Coarse (dry, loose sand)	2,400	40,800	48,480	91,959	7	8	9																							

Closure Cost Estimate
Productivity

Weight of Materials			Uphill Speed (mph) - Rimpull vs. Total Resistance (%Grade + Rolling Resistance)																				
			725C2								730C2												
Material	Ib/yd³	Truck 725C2 Load (lb)	Truck 730C2 Load (lb)	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2
Alluvium	2,900	49,300	58,580	100,095	5.2	6.1	6.9	8	9.5	11.6	15.1	20.5	31.9	111,711	6	6.7	7.6	8.8	10.5	13.2	17	23.2	33.3
Basalt	3,300	56,100	66,660	106,895	4.6	5.7	6.5	7.6	8.9	10.9	14.1	19.6	31.1	119,791	5.7	6.3	7.1	8.2	9.8	12.3	16.1	22.1	32.7
Clay - Dry	2,500	42,500	50,500	93,295	5.8	6.6	7.4	8.4	10.2	12.2	16.1	21.8	32.7	103,631	6.5	7.2	8.2	9.4	11.2	14.2	18.1	24.4	33.8
Granite - broken	2,800	47,600	56,560	98,395	5.3	6.2	7.1	8.1	9.7	11.8	15.3	20.6	32.2	109,691	6.1	6.8	7.7	8.9	10.7	13.4	17.3	23.5	33.4
Gravel	2,550	43,350	51,510	94,145	5.7	6.5	7.4	8.3	10.1	12.1	16	21.5	32.7	104,641	6.5	7.1	8.2	9.3	11.1	14	18	24.2	33.8
Limestone - broken	2,600	44,200	52,520	94,995	5.7	6.4	7.3	8.3	10	12.1	15.9	21.5	32.8	105,651	6.4	7.1	8.1	9.2	11	13.9	17.9	24.1	33.7
Limestone - crushed	2,600	44,200	52,520	94,995	5.7	6.4	7.3	8.3	10	12.1	15.9	21.5	32.8	105,651	6.4	7.1	8.1	9.2	11	13.9	17.9	24.1	33.7
Sandstone	2,550	43,350	51,510	94,145	5.7	6.5	7.4	8.3	10.1	12.1	16	21.5	32.7	104,641	6.5	7.1	8.2	9.3	11.1	14	18	24.2	33.8
Shale	2,100	35,700	42,420	86,495	6.3	7.1	7.9	9.1	10.9	12.9	17	23	33.3	95,551	7	7.8	8.9	10.2	12.3	15.3	19.2	25.9	34.4
Stone - crushed	2,700	45,900	54,540	98,695	5.5	6.3	7.2	8.2	9.8	11.9	15.6	21.2	32.4	107,671	6.3	7	7.9	9.1	10.8	13.6	17.6	23.8	33.6
Tailings - Coarse (dry, loose sand)	2,400	40,800	48,480	91,595	5.9	6.7	7.6	8.5	10.4	12.4	16.4	22	33	101,611	6.6	7.3	8.4	9.6	11.4	14.5	18.4	24.8	34
Tailings - Slimes (loose sand & clay)	2,700	45,900	54,540	96,695	5.5	6.3	7.2	8.2	9.8	11.9	15.6	21.2	32.4	107,671	6.3	7	7.9	9.1	10.8	13.6	17.6	23.8	33.6
Topsoil	1,600	27,200	32,320	77,995	6.9	7.8	8.5	10.1	12	14.7	18.5	24.6	33.9	85,451	7.8	8.7	9.9	11.3	13.7	16.7	20.9	27.9	34.9
				Empty	10.4	11.6	12.7	14.9	17.8	20.4	25.2	31.7	35	Empty	12.6	14	15.9	17.8	20.4	24	29.2	33.7	35

Source: Caterpillar Performance Handbook Edition 47

Weight of Materials			Uphill Speed (mph) - Rimpull vs. Total Resistance (%Grade + Rolling Resistance)																				
			735C								740C												
Material	Ib/yd³	Truck 735C Load (lb)	Truck 740C Load (lb)	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2	Loaded Weight (lb)	18	16	14	12	10	8	6	4	2
Alluvium	2,900	67,280	77,720	136,728	5.4	6.6	7.4	9	10.2	12.4	18	24	33	157,088	5.6	6.2	7.4	8.7	10.4	12.8	17.2	24	34
Basalt	3,300	76,560	88,440	146,005	5.1	5.8	6	8.2	9.8	12.1	16.8	22	32.8	167,806	5.2	5.8	7	8	10	12.2	16	22.4	34
Clay - Dry	2,500	58,000	67,000	127,446	6	7.1	8.9	9.6	11.2	13.5	19.2	26.8	33.2	146,366	6	7	7.9	9.6	11.1	13.4	19.3	25.7	34
Granite - broken	2,800	64,960	75,040	134,406	5.8	6.8	7.5	9.1	10.4	12.7	18.5	25.5	32.8	154,406	5.7	6.6	7.5	9	10.6	12.8	17.3	22.9	34
Gravel	2,550	59,160	68,340	128,606	6	7	8.9	9.5	11.2	13	19	26.7	33.2	147,706	5.9	7	7.8	9.5	11	13.3	19.2	25.7	34
Limestone - broken	2,600	60,320	69,766	129,766	5.9	6.8	7.8	9.5	11	13	19.2	24.5	33	149,046	5.8	6.8	7.8	9.5	10.9	13.2	19.2	25.7	34
Limestone - crushed	2,600	60,320	69,680	129,766	5.9	6.8	7.8	9.5	11	13	19.2	24.5	33	149,046	5.8	6.8	7.8	9.5	10.9	13.2	19.2	25.7	34
Sandstone	2,550	59,160	68,340	128,606	6	7	8.9	9.5	11.2	13	19	26.7	33.2	147,706	5.9	7	7.8	9.5	11	13.3	19.2	25.7	34
Shale	2,100	48,720	56,280	118,166	6.7	7.4	9.1	10.2	11.8	15.4	20.5	27.5	33.5	135,646	6.4	7.4	8.6	10.2	11.9	14.3	20.2	28.4	34
Stone - crushed	2,700	62,640	72,360	132,086	5.4	6.8	7.4	9.2	10.6	12.7	18.5	25	33	151,726	5.7	6.7	7.7	9.3	10.8	13	18.3	25.6	34
Tailings - Coarse (dry, loose sand)	2,400	55,680	64,320	125,126	6.1	7	8.2	9.6	11.3	14.6	19.6	27	33.2	143,686	6	7.2	8	9.8	11.1	13.8	19.3	27	34
Tailings - Slimes (loose sand & clay)	2,700	62,640	72,360	132,086	5.4	6.8	7.4	9.2	10.6	12.7	18.5	25	33	151,726	5.7	6.7	7.7	9.3	10.8				

Closure Cost Estimate
Productivity


Shovel/Excavator Specifications (Komatsu or Hitachi equivalent)						
Description	PC2000	PC3000	PC4000	PC5500	PC8000	EX2500
Payload Capacity (yd ³)						
Struck	10.46	18.84	26.16	33.48	47.09	
Heaped	14.39	25.9	35.97	46.04	64.75	
Average	12.43	22.37	31.07	39.76	55.92	19.63
Matched Truck	740	777D	785C	793C	797B	789C
Average Cycle Time (min)	0.49	0.49	0.59	0.59	0.69	0.68
Passes to Fill Truck	2.05	2.84	3.38	4.69	5.11	6
Altitude Deration Factor	0.96	0.96	0.96	0.96	0.96	0.96
Operator Skill	1	1	1	1	1	1
Job Efficiency	0.83	0.83	0.83	0.83	0.83	0.83
Time to Fill Truck	1.68	2.33	3.32	4.61	5.86	5.9168
Rolling Resistance**	2.5	2.5	2.5	2.5	2.5	2.5
Shovel matched to small truck fleet						
Shovel matched to medium truck fleet						
Shovel matched to large truck fleet						
Shovel matched to extra large truck fleet						

**A firm, smooth, rolling roadway with dirt or light surfacing, flexing slightly under load or undulating, maintained fairly regularly, watered

Source: Caterpillar Performance Handbook Edition 46; Komatsu actual Peruvian mine (Lagunas Norte) operating data for PC4000.

Loader Travel Times - Empty										
Loader Model	Distance (ft)								a	b
	16.4041995	32.808399	65.616798	114.8293965	164.041995	328.08399	492.125985	656.16798		
950M	0.04	0.05	0.07	0.09	0.12	0.19	0.27	0.34	0.42	0.0015
966M	0.04	0.05	0.06	0.08	0.11	0.19	0.27	0.35	0.43	0.0016
972M	0.04	0.05	0.06	0.08	0.12	0.20	0.28	0.36	0.44	0.0016
980M	0.03	0.05	0.06	0.08	0.11	0.18	0.26	0.33	0.41	0.0015
988K	0.01	0.01	0.03	0.05	0.07	0.15	0.23	0.31		0.0016
990K	0.02	0.03	0.06	0.10	0.14	0.26	0.40	0.53		0.0026
992K	0.02	0.03	0.06	0.10	0.15	0.30	0.44	0.59		0.0029
994K	0.01	0.02	0.05	0.09	0.13	0.25	0.38	0.51		0.0026
Travel Time (min) =	$a(d) + b$									


Source: Caterpillar Performance Handbook Edition 47



Loader Travel Times - Loaded										
Loader Model	Distance (ft)								a	b
	16.4041995	32.808399	65.616798	114.8293965	164.041995	328.08399	492.125985	656.16798		
950M	0.03	0.04	0.06	0.08	0.10	0.19	0.28	0.36	0.44	0.0017
966M	0.04	0.05	0.06	0.09	0.12	0.22	0.30	0.40	0.48	0.0018
972M	0.04	0.05	0.07	0.10	0.12	0.21	0.30	0.40	0.48	0.0018
980M	0.03	0.04	0.06	0.08	0.11	0.20	0.27	0.35	0.42	0.0016
988K	0.01	0.02	0.03	0.05	0.08	0.16	0.24	0.31		0.0016
990K	0.02	0.03	0.06	0.09	0.13	0.26	0.40	0.53		0.0026
992K	0.02	0.03	0.06	0.10	0.15	0.30	0.44	0.59		0.0029
994K	0.01	0.02	0.05	0.09	0.13	0.25	0.38	0.51		0.0026
Travel Time (min) =	$a(d) + b$									

Source: Caterpillar Performance Handbook Edition 47

**Closure Cost Estimate
Productivity**



Productivity - Motor Graders

Motor Grader Specifications				
Description	12M2	14M	16M3	24M
Grader Width (ft)	8.25	9.2	11.2	14
Blade Width (ft)	12	14	16	24
Number of Shanks	5	7	7	7
Ripper Width (7 shanks) (ft)	7.6	8.5	9.75	12.83
Road Maintenance Speed (mph)				
Minimum	3	3	3	3
Maximum	9.5	9.5	9.5	9.5
Average	6.25	6.25	6.25	6.25
Hourly Production (ft)	33,000	33,000	33,000	33,000
Ripping Speed (mph)	1	1	1	1
Minimum	0	0	0	0
Maximum	3	3	3	3
Average	1.5	1.5	1.5	1.5
Altitude Deration Factor	1	1	1	0.91
Ripping Hourly Production (with job efficiency correction & altitude deration factors) (excluding manuever time) (ft)	6.574	6.574	6.574	5.982
Maneuver time per pass (min)	0.5	0.5	0.5	0.5
Operator Skill	1	1	1	1
Job Efficiency	0.83	0.83	0.83	0.83

Source: Caterpillar Performance Handbook Edition 47

Productivity - Excavators

Track Excavator Specifications							
Description	312F	320F	325F	330F	349F	374F	390F
Bucket Capacity (yd ³)	0.68	1.57	2.22	2.22	3.00	4.60	7.30
Fill Factor	0.9	0.9	0.9	0.9	0.9	0.9	0.9
Average Bucket Load (yd ³)	0.612	1.413	1.998	1.998	2.7	4.14	6.57
Soil Type	Packed earth	hard clay					
Job Condition	med-hard	med-hard	med-hard	med-hard	med-hard	med-hard	med-hard
Cycle Times (minutes) - based on hard clay							
Load Bucket	0.07	0.09	0.09	0.09	0.13	0.1	0.19
Swing Loaded	0.06	0.06	0.06	0.07	0.07	0.09	0.06
Dump Bucket	0.03	0.03	0.04	0.04	0.02	0.04	0.03
Swing Empty	0.05	0.05	0.06	0.07	0.06	0.07	0.07
Total Cycle Time	0.21	0.23	0.25	0.27	0.28	0.3	0.35
Job Efficiency	0.83	0.83	0.83	0.83	0.83	0.83	0.83
Operator Skill	1	1	1	1	1	1	1
Altitude Deration Factor	0.78	0.83	1	1	0.93	1	1
Corrected Productivity (LCY/hr)	113	254	398	369	447	687	935
Exploration Road Cycle Time ⁽¹⁾ (min)	N/A	0.38	0.4	N/A	0.42	N/A	N/A
Exploration Road Corr Prod (LCY/hr)	N/A	154	249	N/A	298	N/A	N/A
Track Width (ft)	8.17	9.17	9.83	10.5	11.42	11.5	11.5

Source: Caterpillar Performance Handbook Edition 47

Concrete Breaking Production

Track Excavator w/Hammer Specifications			
Description	320F	349F	374F
Hydraulic Hammer	H120Es	H160Es	H180Es
Material	reinforced concrete		
Min Shift Production (yd ³ /8hr)	160	300	385
Max Shift Production (yd ³ /8hr)	300	850	1,705
Avg Shift Production (8hr)	230	575	1,045
Job Efficiency	0.83	0.83	0.83
Altitude Deration Factor	0.83	0.93	1

Source: Caterpillar Performance Handbook Edition 47

Drill Hole Plugging Productivity

Drill Hole Plugging Productivity		
Description	Drill Rig	Pump Rig
Move-to-hole, set-up, tear-down ⁽¹⁾	2 hrs	2 hrs
Trip in tremie pipe (1) (ft/hr)	500	
Pulling casing (threaded, not cemented) (1) (ft/hr)	200	
FALSE	Productivity (all passes) (2) (ft/hr)	Passes
4	60	4
6	60	4
8	50	4
12	45	6
18	40	9
24	28	12
Perforation setup, trip in/out, tear-down time	2 hrs	
Perforation tool cost (wear cost) ⁽³⁾	2.5 hrs	
Inert Material Placement (backfill)		
Grouting/Cement ⁽⁴⁾ (cy/hr)		5.33
Cuttings (see below) (cy/hr)		3.5
1. Drillers daily logs from Newmont, Barrick, New West Gold, Agnico Eagle, Sources: Idaho General Mines Inc.		
2. Drillers daily logs from Newmont, Barrick, Target Minerals		
3. Drillers daily logs from Newmont		
4. WDC Exploration, Dec 2005		
Cuttings Placement Productivity		
Shift productivity (Means 02210-700-0120; Crew B11M)	28	(yd ³ /shift)
Shift length	8	hours
Estimated Hourly Productivity	3.5	(yd ³ /hr)

Source: WDC Exploration, Dec 2005

Closure Cost Estimate
Productivity

Altitude Deration Table										
MODEL	Elevation									
	0-760 m (0-2500')		760-1500 m (2500-5000')		1500-2300 m (5000-7000')		2300-3000 m (7500-10,000')		3000-3800 m (10,000-12,000')	
	CAT	User	CAT	User	CAT	User	CAT	User	CAT	User
Bulldozers										
D6T	100		100		100		100		100	
D6R w/ Winch	100		100		100		100		100	
D7E	100		100		100		99		95	
D8T	100		100		100		100		100	
D9T	100		100		100		100		100	
D10T2	100		100		100		100		100	
D11T	100		100		100		100		86	
Wheeled Dozers										
824K	100		100		100		92		84	
834K	100		100		100		98		85	
844K	100		100		100		93		83	
854K	100		100		100		93		79	
Graders										
12M2	100		100		100		100		99	
14M	100		100		100		100		100	
16M3	100		100		100		100		100	
24M	100		100		100		91		86	
Excavators										
312F	100		100		100		83		78	
320F	100		100		100		87		83	
325F	100		100		100		100		100	
330F	100		100		100		100		100	
349F	100		100		100		100		93	
374F	100		100		100		100		98.5	
390F	100		100		100		100		95.5	
Scrapers										
631K	100		100		100		97		90	
637K	100		100		100		98		80	
Loaders										
926M	100		100		100		92		81	
930M	100		100		100		90		77	
950M	100		100		100		97		91	
966M	100		100		100		99		79	
972M	100		100		100		99		79	
980M	100		100		100		100		88	
988K	100		100		100		98		85	
990K	100		100		100		98		93	
992K	100		100		100		98		79	
994K	100		100		100		99		97	
L2350	100		100		100		96		90	
Shovels										
PC2000	100		100		100		96		90	
PC3000	100		100		100		96		90	
PC4000	100		100		100		96		90	
PC5500	100		100		100		96		90	
PC8000	100		100		100		96		90	
EX2500	100		100		100		96		90	
Other Equipment										
H120Es (fits 325)	99		97		95		91		91	
H160Es (fits 349)	99		97		95		91		91	
H180Es (fits 374/390)	100		100		98		95		91	
Demolition Shears	100		100		100		91		86	
S3050 (fits 320/325/330)	100		100		98		95		100	
S3070 (fits 330/349)	100		100		100		91		86	
S3090 (fits 374/390)										
Demolition Grapples										
G315B (fits 320/325)										
G320B (fits 325/330)										
G330 (fits 349/374)										
Other Equipment										
420F2	100		100		100		100		100	
430F2	100		100		100		100		100	
CS54B										
CS64B										
CP54B										
CP68B										
Light Truck - 1.5 Ton										
Supervisor's Truck										
Flatbed Truck										
Trucks										
725C2	100		100		100		100		95	
730C2	100		100		100		100		95	
735C	100		100		100		99		91	
740C	100		100		100		99		91	
770G	100		100		100		99		89	
773G	100		100		100		100		100	
777G	100		100		100		100		100	
785D	100		100		100		100		98.5	
789D	100		100		100		95.5		93	
793F	100		100		100		100		100	
797F	100		100		100		100		100	
613E (5,000 gal)	100		100		100		100		95	
621E (8,000 gal)	100		100		100		100		97	
777G H2O Truck	100		100		100		100		93	
785D H2O Truck	100		100		100		93		87	
							86		80	
Notes:	User entered deration value will override values from CAT Performance Handbook (Ed. 47), except L2350 Loader: data from actual mine performance in Chile. Komatsu altitude deration assumed from LeTourneau L2350									

**Closure Cost Estimate
Productivity**

Fuel Use

EQUIPMENT TYPE (1)	Fuel Use (1) gal/hr	User Override	Fuel Use (1) gal/hr
Bulldozers			
D6T	6.45		6.45
D6R w/ Winch	6.45		6.45
D7E	5.9		5.90
D8T	10.4		10.40
D9T	13.5		13.50
D10T	18.7		18.70
D11T	26.2		26.20
Wheeled Dozers			
824K	11.3		11.30
834K	13.25		13.25
844K	15		15.00
854K	19		19.00
Motor Graders			
12M2	3.85		3.85
14M	5.05		5.05
16M3	6.25		6.25
24M	11.75		11.75
Track Excavators			
312F	2.05		2.05
320F	3.6		3.60
325F	3.7		3.70
330F	5.15		5.15
349F	9.75		9.75
374F	10.3		10.30
390F	11.75		11.75
Scrapers			
631K	15.12		15.12
637K	24.345		24.35
Wheeled Loaders			
926M	1.8		1.80
930M	1.9		1.90
950M	3.1		3.10
966M	3.75		3.75
972M	4.15		4.15
980M	5.5		5.50
988K	10.4		10.40
990K	17.6		17.60
992K	23		23.00
994K	41.4		41.40
L2350	66		66.00
Shovels			
PC2000	37		37.00
PC3000	50		50.00
PC4000	70		70.00
PC5500	119		119.00
PC8000	149		149.00
EX2500	51		51.00
Hydraulic Hammers			
H120Es (fts 325)	N/A		
H160Es (fts 349)	N/A		
H180Es (fts 374/390)	N/A		
Demolition Shears			
S3050 (fts 320/325/330)	N/A		
S3070 (fts 330/349)	N/A		
S3090 (fts 374/390)	N/A		
Demolition Grapples			
G315B (fts 320/325)	N/A		
G320B (fts 325/330)	N/A		
G330 (fts 349/374)	N/A		
Other Equipment			
420F2	4.3		4.30
430F2	4.7		4.70
CS54B	3.35		3.35
CS64B	3.35		3.35
CP54B	3.35		3.35
CP68B	3.6		3.60
Light Truck - 1.5 Ton	1.5		1.50
Supervisor's Truck	1		1.00
Flatbed Truck	4.7		4.70
Air Compressor + tools	1		1.00
Welding Equipment	2		2.00
Heavy Duty Drill Rig	12		12.00
Pump (plugging) Drill Rig	10		10.00
Concrete Pump	10		10.00
Gas Engine Vibrator	1		1.00
Generator 5KW	1.5		1.50
HDEP Welder (pipe or liner)	2		2.00
5 Ton Crane	3		3.00
20 Ton Crane	4		4.00
50 Ton Crane	4.7		4.70
120 Ton Crane	5.2		5.20
Trucks			
725C2	5.05		5.05
730C2	5.4		5.40
735C	6.95		6.95
740C	7.8		7.80
770G	4.95		4.95
773G	8.25		8.25
777G	13.55		13.55
785D	25.1		25.10
789D	36.85		36.85
793F	44.75		44.75
797F	67.65		67.65
613E (5,000 gal)	6		6.00
621E (8,000 gal)	10.75		10.75
777G H2O Truck	13.55		13.55
785D H2O Truck	25.1		25.10
Dump Truck (10-12 yd ³)	5.2		5.20
Tractor/Trailer (20 ton)	14		14.00
Tractor/Trailer (50 ton)	18		18.00
Tractor/Trailer (80 ton)	22		22.00



NOTES:

(1) Fuel use source: Caterpillar Performance Handbook (Ed. 47)
(2) assumes 24 hr tank


FIGURES

These figures show key inputs to the model and important calculations used by the model


Slope Regrading Volumes




Slope Regrading Push Distance




Slope/Flat Area Calculations




Tailings Impoundments




Tailings Embankments




Road Regrading Volume Calculations



Exploration Road Calculations






3) Enter road and drill pad widths

4) Enter number of pads = 2

5) Enter length of drill pad = 100

Pond Volume Calculations



Area and Volume of the Frustum of a Pyramid


$$\text{Surface Area} = ab + cd + (a+b+c+d) \times \frac{s}{2}$$

$$\text{Volume} = \frac{h(ab + cd + \sqrt{abcd})}{3}$$

Berm Volume Calculations


Cross Sectional Area =

Berm Volume = Berm Length x Cross Sectional Area




Ditch Volume Calculations


$$\frac{(a + b)}{2} \times d$$




Portal/Adit Measurements




Shaft Measurements



Production Well



Monitor Well



STANDARDIZED RECLAMATION COST ESTIMATOR

User Settings

Version 2 - Beta 01

Cost Estimate Type	Alias*
Life-of-Mine	LOM
Financial Assurance	FA
Asset Retirement Obligation	ARO

Note: Aliases **cannot** use any of the following characters: \ / * ? : []

Other Settings	
Road Transport Speed (mph)	80
Site Speed limit (mph) <small>(determines maximum speed for all haul fleets)</small>	35.0
Maximum Loader Haul to Crusher (ft)	200.0

Set Recalculation Options

Several of the actions in the worksheet will recalculate the entire workbook when completed. This can reduce the efficiency of the model. The options below allow the user to determine which of these actions will include a recalculation command at the end of the action.

For example, when adding numerous facilities to different sheets, it is best to turn off recalculation for the Add Facility action by selecting FALSE below.

These options are only active if MANUAL is selected on the Formulas/Calculation Options menu. If FALSE is selected, then recalculation will not occur and must be requested manually, by entering Ctrl-Shift-W (recalculates current worksheet), Ctrl-Shift-R (recalculates entire model).

Note: Pressing the F9 key or selecting CALCULATE NOW from the Formulas/Calculation Options menu will recalculate all open workbooks.

Action	Recalc?
Add Facility	FALSE
Delete Facility	FALSE
Import User Data	FALSE

**Closure Cost Estimate
User 04 Chicago Tunnel**

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Sheet Name: Chicago Tunnel

Year	Cost	Comment
BP2020	\$ 95,022.18	
2023	\$ 98,062.89	Escalated 3.%
2024	\$ 100,514.46	Escalated 2.5%

Closure Cost Estimate

User 09 Stormwater Construction

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Sheet Name: Stormwater Construction

Stormwater Construction	\$	16,274,652.00
Escalated for 2023	\$	16,762,891.56
Escalated for 2024	\$	17,181,963.85

Closure Cost Estimate
User 10 Rinsing Cost Rate VLF1

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
 Version: Version 2.0
 Cost Data User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US
 Sheet Name: Rinsing Cost Rate VLF1

Inputs	Item	Unit	Value	Source
Gas	Tons	400,516.7400	Escalated AM14	
User		0.00031201	Escalated 3% for 2023. Escalated 2.5% for 2024	
KWH	Gallon	1.1902		
Cost of H2O2	Gallon	3,65134721	Escalated 2.5% for BP2024	2024
Generator	Gallon	1.1902		
Mechanic	Shr	57.29		
Pump maintenance	Smooth	15971.1401	Escalated 2.5% for BP2024	
Generator maintenance	Smooth	90.00	Escalated 2.5% for BP2024	
drip irrigation supplies	Smooth	2240.9000	Escalated 2.5% for BP2024	
Support vehicle	Smooth	672.027100	Escalated 2.5% for BP2024	

Assumptions	Item	Unit	Value	Source
Make up water	Volume	1,400	Process Application	
Site volume	Volume	1,400	From Process Ops	
Baron & Preg Pump Flow Rate	CPM	15000	From Process Ops	
Baron & Preg KWH (\$15,000 CPM day)	KWH/day	125193	From Process Ops Budget, option 1B scaled to 15,000gpm	
Make up water	CPM	300	From Sitelets verified by Process Ops	

Outputs	Item	Unit	Value
Make up water	Volume	201,400,000.00	
Site Volume	Volume	8,717,770	
Rinse Volume	Volume	178491630.11	
One Rinse Cycle Time	Day	817	
Two Rinse Cycle Time	Day	1634	
All Rinse Time	Day	2451	
All Rinse Time	30-day Month	82	
First Rinse	\$	21,076,759.00	
Second Rinse	\$	21,076,759.00	
Third Rinse	\$	21,076,759.00	
All Three Rinses	\$	61,394,173.94	
Discount for 1st Rinse	\$	40,311,414.00	

Item	Quantity	Unit	Assumptions	Equipment	Labor	Materials
Make up water	900.00	Gallons				
Baron & Preg Power Cost	123193.00	KWH day				
H2O2	362000.00	Month				
Drip Irrigation supplies	27.24	Month				
Operators	12.00	Per 24 hour	12 hour shift			
Mechanics	2.00	Per 24 hour	12 hour shift			
H2O2 Mechanic	1.00	Per 12 hour	12 hour shift			
Pump Maintenance	27.24	Month				
Generator Maintenance	27.24	Month				
Generator Maintenance	27.24	Month				
Support Vehicle	3.00	Each				

Item	Unit	First Rinse		Second Rinse		Third Rinse	
		Equipment	Labor	Equipment	Labor	Equipment	Labor
Make up water	Volume	\$ 3,710,428.52	\$ 3,710,428.52	\$ 10,065,988.02	\$ 10,065,988.02	\$ 10,065,988.02	\$ 10,065,988.02
Baron & Preg Power Cost	Volume	\$ 1,321,797.11	\$ 1,321,797.11	\$ 610,119.15	\$ 610,119.15	\$ 610,119.15	\$ 610,119.15
H2O2	Volume	\$ 5,045,307.57	\$ 5,045,307.57	\$ 1,123,075.11	\$ 1,123,075.11	\$ 1,123,075.11	\$ 1,123,075.11
Drip Irrigation supplies	Volume	\$ 561,537.56	\$ 561,537.56	\$ 430,000.00	\$ 430,000.00	\$ 430,000.00	\$ 430,000.00
Operators	Hour	\$ 435,000.00	\$ 435,000.00	\$ 22,879.47	\$ 22,879.47	\$ 22,879.47	\$ 22,879.47
Mechanics	Hour	\$ 435,000.00	\$ 435,000.00	\$ 22,879.47	\$ 22,879.47	\$ 22,879.47	\$ 22,879.47
H2O2 Mechanic	Hour	\$ 435,000.00	\$ 435,000.00	\$ 22,879.47	\$ 22,879.47	\$ 22,879.47	\$ 22,879.47
Pump Maintenance	Hour	\$ 435,000.00	\$ 435,000.00	\$ 22,879.47	\$ 22,879.47	\$ 22,879.47	\$ 22,879.47
Generator Maintenance	Hour	\$ 435,000.00	\$ 435,000.00	\$ 22,879.47	\$ 22,879.47	\$ 22,879.47	\$ 22,879.47
Generator Maintenance	Hour	\$ 435,000.00	\$ 435,000.00	\$ 22,879.47	\$ 22,879.47	\$ 22,879.47	\$ 22,879.47
Support Vehicle	Hour	\$ 435,000.00	\$ 435,000.00	\$ 22,879.47	\$ 22,879.47	\$ 22,879.47	\$ 22,879.47
Total		\$ 3,710,428.52	\$ 3,710,428.52	\$ 10,065,988.02	\$ 10,065,988.02	\$ 10,065,988.02	\$ 10,065,988.02

Item	Unit	First and third		Second and third	
		First Rinse	Second Rinse	First Rinse	Second Rinse
Equipment	Volume	\$ 1,025,631.31	\$ 12,898,302.92	\$ 26,393,430.58	\$ 21,076,759.00
Labor	Hour	\$ 1,025,631.31	\$ 12,898,302.92	\$ 26,393,430.58	\$ 21,076,759.00
Materials	Volume	\$ 1,025,631.31	\$ 12,898,302.92	\$ 26,393,430.58	\$ 21,076,759.00
Total		\$ 1,025,631.31	\$ 12,898,302.92	\$ 26,393,430.58	\$ 21,076,759.00

All Rinses

\$ 72,269,788.01

Closure Cost Estimate
User 11 Rinsing Cost Rate VLF2

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
 Date of Submittal: April 2024
 File Name: SRCE_2.0_FW_AM14_April 2024.xlsx
 Model Version: Version 2.0
 Cost Data: User Data
 Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
 Cost Estimate Type: ARO Cost Basis: AM-14 CC&V - US
 Sheet Name: Rinsing Cost Rate VLF2

Inputs	Item	Unit	Source
VLF	Tons	453,000,000	Updated AM14
water	\$ Gallon	0.003612375	Escalated 3% for 2023. Escalated 2.5% for 2024
KWH	\$	0.1000	
Cost of H2O2	\$/per gallon	3.651347271	Escalated 2.5% for BP2024
Operator	\$/hr.	42.88	
Mechanic	\$/hr.	57.27	
Pump maintenance	\$/month	15973.1491	Escalated 2.5% for BP2024
Generator maintenance	\$/month	840.0338813	Escalated 2.5% for BP2024
drip irrigation supplies	\$/month	22400.9033	Escalated 2.5% for BP2024
Support vehicle	\$/month	672.027105	Escalated 2.5% for BP2024

Assumptions	Item	Unit	Source
Density	tons/cy	1.485	Process Ops/Steffens
pore volume	%	28	From Process Ops
Barren Pump Flow Rate	GPM	16500	From Process Ops
Barren KWH	KWH/day	67608	From Process Ops Budget
Preg Pump Flow Rate	GPM	16500	From Process Ops
Preg Pump KWH	KWH/day	7159	From Process Ops Budget
Make up water	GPM	900	from Steffens verified by Process Ops

Outputs	Item	Unit	
Cubic Yards		yards	305,050,505.05
Rinse Volume		Yards	85414141
Rinse Volume		Gallons	17252546162
One Rinse Cycle Time		Day	726
One Rinse Cycle Time		30-day Month	24
All Rinse Time		Day	2178
All Rinse Time		30-day Month	73
All Rinse Time		Years	6
First Rinse	\$	\$	16,718,440.83
Second Rinse	\$	\$	16,718,440.83
Third Rinse	\$	\$	15,233,932.30
All three Rinses	\$	\$	48,670,813.96
Discount for 1st Operational Rinse	\$	\$	31,952,373.13

Item	Quantity	Unit	Assumptions	Equipment	Labor	Materials	First Rinse	Second Rinse	Third Rinse
Make up water	900.00	Gallons					\$ 3,305,313.07	\$ 3,305,313.07	\$ -
Barren Power Cost	67608.00	KWH/day					\$ 4,909,133.60	\$ 4,909,133.60	\$ 4,909,133.60
Preg Power costs	7159.00	KWH/day					\$ 519,827.35	\$ 519,827.35	\$ 519,827.35
H2O2	362000.00	Gallons					\$ 1,321,787.71	\$ -	\$ 1,321,787.71
Drip Irrigation supplies	24.20	Month					\$ 542,189.43	\$ 542,189.43	\$ 542,189.43
Operators	12.00	Per 24 hour	12 hour shift				\$ 5,988,201.94	\$ 5,988,201.94	\$ 5,988,201.94
Mechanics	2.00	Per 24 hour	12 hour shift				\$ 998,033.66	\$ 998,033.66	\$ 998,033.66
H2O2 Mechanic	1.00	Per 12 hour	12 hour shift				\$ 499,016.83	\$ -	\$ 499,016.83
Pump Maintenance	24.20	Month					\$ 386,612.64	\$ 386,612.64	\$ 386,612.64
Generator Maintenance	24.20	Month					\$ 20,332.10	\$ 20,332.10	\$ 20,332.10
Support Vehicle	3.00	Each					\$ 48,797.05	\$ 48,797.05	\$ 48,797.05

Second and third			First Rinse	Second Rinse	Third Rinse
Equipment	Labor	Materials	Total	Total	Total
\$ 911,483.59	\$ 14,471,488.02	\$ 16,569,401.52	\$ 16,718,440.83	\$ 16,718,440.83	\$ 15,233,932.30

All Rinses Equipment Labor Materials Total

All Rinses	Equipment	Labor	Materials	Total
\$ 1,367,225.39	\$ 21,457,723.61	\$ 25,845,864.96	\$ 48,670,813.96	

**Closure Cost Estimate
User 15 Tree Thinning**

Project Name: AM-14 Financial Warranty Update - Reclamation Plan
Date of Submittal: April 2024
File Name: SRCE_2.0_FW_AM14_April 2024.xlsm
Model Version: Version 2.0
Cost Data: User Data
Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm
Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US
Sheet Name: Tree Thinning

3.1 Tree Thinning Cost Estimate

18 days for thinning (assumed) and 8 hours per day in the field
Total Time needed = 8 x 18 = 144 hours with each machine and an operator
Feller Buncher (\$46.22/hr machine rental + \$50.77/hr operator + \$43.28/hr maintenance and fuel) = \$140.27/hr * 144 hrs = \$20,198 (Source: RS Means, 2017)
Skid Steer (15.35/hr machine rental + \$50.77/hr operator + \$17.82/hr maintenance and fuel) = \$83.94/hr * 144 hrs = \$12,087 (Source: RS Means, 2017)

Truck to Haul Trees = (35 Ton Haul Truck(Cat 735) @ \$126.97/hr total rate + 50.77/hr operator)= \$177.74/hr * 144 hrs = \$25,595 (Source: Equipment Costs and Labor Rates tabs)

Road Building and Maintenance (D7 Dozer @ \$84.78/hr total rate + \$50.77 operator)= \$135.55/hr * 70 hours = \$9,489 (Source: Equipment Costs and Labor Rates tabs)

Supervisor Costs = \$78.92/hr for construction supervision of crew * 140 hrs = \$11,049 (Source: Labor Rates tab)

Contractor's Thinning Costs = \$20,198+\$12,087+\$25,595+\$9,489+\$11,049 = \$78,418

Oversight and Direction of Field Activities = assume 10% of Contractor's Costs = \$7,842

Contingency (assumed to be 15% of Contractor's Costs) = (0.15 x \$78,418) = \$11,763

Total Tree Thinning Costs = \$78,418 + \$7,842 + \$11,763 = 98023

Source: RS Means 2017	
Feller Buncher	rent/week 2218.32
# of weeks 2.571429 (assume 3 wks)	cos/hr rent 46.215
operating cr 43.28	
Skid Steer	736.66
cos/hr rent 15.34708	
operating cr 17.82	

Tree Thinning			
	Equipmt	Labor	Material
Sub-Total	\$ 20,198.00	\$ 12,087.00	\$ 25,595.00
	\$ 9,489.00	\$ 11,049.00	
2017	\$ 78,418.00	\$ 19,605.00	\$ -
Chk =	\$ 98,023.00		

3.2 Harvesting of Salvageable Trees and Hauling to Nursery (Source: Equipment Costs and Labor Rates tabs, except where noted)

Based on Randy Mandel's experience with similar projects:

3000 Trees Total to be harvested (3000 additional trees will be purchased or dug up elsewhere to make the total of 6000 trees needed)

Dig up trees with a mini-excavator (not proposing to use a conventional tree spade)

\$5 per tree for containers and supplies like burlap and ties

40 trees can be harvested per day with the mini-excavator and a two man crew

Shipping offsite to a nursery in either Colorado Springs or Canon City for care until needed in reclamation

Mini-excavator (3/4 CY) at \$5,616.90/month rental = \$5,616.90/ 160 hrs = \$35.10/hr +\$33.09/hr operating cost = \$68.19 total cost (RS Means, 2017)

Operator for excavator @ \$50.77/hr

Total cost for mini-ex = \$68.19+\$50.77= \$118.96/hr

3000 trees / 40 trees per day = 75 days x 8 hrs/day = 600 hours

600 hrs x \$118.96/ hr = \$71,376 for Mini-Ex + operator digging trees

Extra field hand at \$50.77/hr for 600 hrs = \$30,462 (holding tree & wrapping with burlap)

Flat bed Truck to haul trees at \$9.38/hr total cost + \$50.77/hr operator = \$60.15/hr * 300 hrs= \$18,045 (assume truck needed about half-time)

Supervisor cost = \$78.92/hr x 600 hrs = \$47,352

Supplies @ \$5/tree for burlap and plastic containers: 3000 x \$5 = \$15,000

Contingency figured at 15% of contractor's costs = [\$71,376 + \$18,045 + \$47,352 + \$15,000] x 0.15 = \$22,766

Therefore the total harvesting cost would be on the order of: \$71,376 digging + \$30,462 field hand + \$18,045 hauling + \$47,352 supervisor + \$15,000 supplies + \$22,766 contingency = 205001

Harvesting and Hauling Trees			
	Equipmt	Labor	Material
Sub-Total	\$ 71,376.00	\$ 18,045.00	\$ 15,000.00
	\$ 22,766.00		
chk =	\$ 112,187.00	\$ 77,814.00	\$ 15,000.00

3.3 Maintenance of Trees at Nursery

Assume trees can be "cared for" at a cost of approximately \$10 / yr per tree for a total of 4 yrs (arbitrary), then the cost of maintenance would be 3000 trees x \$10 / yr x 4 yrs = \$120,000.

Total Maint. \$ for Harvested Trees at Commercial Nursery = 120000

Nursery Maintenance			
	Equipmt	Labor	Material
Sub-Total	\$ 80,000.00	\$ 25,000.00	\$ 15,000.00
chk =	\$ 120,000.00		

3.4 Retrieving Trees from Nursery, Hauling to Site, and Installing Gator Bags (water release), Buying 3000 additional trees from Nursery, Re-planting in Reclaimed Areas (Source: Equipment Costs and Labor Rates tabs, except where noted)

Buying 3000 nursery trees at \$27.25/ tree x 3000 trees = \$81,750 from Heidrich's Colorado Tree Farm Nursery at www.coloradotreefarmnursery.com

Planting rate for trees is 4 trees per hour for salvaged trees and 5 trees per hour for purchased trees.

Therefore, it will take (3000 trees / 4 per hour) + (3000 trees / 5 per hour) = 1350 hours with a 4 man crew and an excavator to dig holes and a truck to haul them to the site.

320C Excavator \$59.53/hr total cost + \$50.77/hr operator = \$110.53/hr

Flat bed Truck to haul trees at \$9.38/hr total cost + \$50.77/hr operator = \$60.15/hr for half the total hours or roughly 700 hours

2 Extra Hands on Ground to Plant and Position Trees @ \$50.77/hr

Supervisor @ \$78.92/hr

20 gallon Gator Bag Cost (\$21 each) from Sprinkler Supply Store at www.sprinklersupplystore.com.

Cost Estimate = (3000 new trees x \$27.25/tree) + (1350 hrs x \$110.53/hr planting) + (700 hrs x \$60.15/hr trucking) + (1350 x \$78.92 supervisor) + (\$21 each gator bags x 6000 trees) + (water truck to charge gator bags at 700 @ \$50.77/hr) + (cost of water is 0.00287/gal * 1,056,000 gallons) = \$681,262

New Trees = \$81,750

Planting = \$149,216

Trucking = \$42,105

Field labor = \$137,079

Supervision = \$106,542

Gator bags = \$126,000

Water Truck = \$35,539

Water cost = \$3,031

Contingency @15% = (\$681,262 x 0.15) = \$102,189

Total Tree Planting Cost & Purchasing All Supplies & Watering = 783451

Planting on Reclaimed Areas			
	Equipmt	Labor	Material
Sub-Total	\$ 149,216.00	\$ 137,079.00	\$ 81,750.00
	\$ 42,105.00	\$ 106,542.00	\$ 126,000.00
		\$ 35,539.00	\$ 3,031.00
		\$ 102,189.00	
Sub-Total =	\$ 191,321.00	\$ 381,349.00	\$ 210,781.00
chk =	\$ 783,451.00		

4.1 Consultation and Oversight of Tree Planting Effort

Assume a professional will need to be consulted and be in the field a total of 50 days during the required 1350 man-hours for planting to provide guidance and oversight.

Cost of consultation = (50 days x 8 hrs/day x \$150/hr labor) + (\$250/day x 50 days expenses) = \$72,500

4.2 Re-planting at 10% of 6000 Trees

Using the above cost per tree for planting and watering for 60 trees

(10% of 6000 originally planted) =

60 x \$129.98 = \$7,799

4.3 Evaluation of Tree Stands, Meetings with DRMS, and Report Preparation

Assume a professional will need 100 hours of additional work time to prepare reports and meet with DRMS in the field to evaluate and explain the tree planting exercise.

100 hours x \$150/hour = \$15,000

Oversight of Planting Effort			
	Equipmt	Labor	Material
Sub-Total =	\$ -	\$ 60,000.00	\$ 12,500.00
chk =	\$ -	\$ 60,000.00	\$ 12,500.00

Re-Planting Effort			
	Equipmt	Labor	Material
Sub-Total =	\$ -	\$ 3,032.00	\$ 4,767.00
chk =	\$ -	\$ 3,032.00	\$ 4,767.00

Evaluation, Meetings, and Reports			
	Equipmt	Labor	Material

<tbl_r cells

**Closure Cost Estimate
User 16 Tree Cost Calc**

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Sheet Name: Tree Cost Calc

												2023	2024
Gooseberry Currant	6.777940848	50 per acre	338.90	359.23	366.42	377.41	388.7302	396.5048	406.4174				
Rosa Woodsii (wild rose)	4.105379464	50 per acre	205.27	217.59	221.94	228.59	235.4528	240.1618	246.1659				
Englemann Spruce	5.822728795	25 per acre	145.57	154.30	157.39	162.11	166.9733	170.3128	174.5706				
Bristlecone Pine	9.237103795	25 per acre	230.93	244.78	249.68	257.17	264.8844	270.182	276.9366				
	Cost of Shrub/Tree Planting per acre =		920.66	975.90	995.42	1025.28	1056.04	1077.16	1104.09				

Closure Cost Estimate
User 18 perf Liner

Project Name: AM-14 Financial Warranty Update - Reclamation Plan

Date of Submittal: April 2024

File Name: SRCE_2.0_FW_AM14_April 2024.xlsm

Model Version: Version 2.0

Cost Data: User Data

Cost Data File: AM-14_Newmont_CCV_FW_CDF.xlsm

Cost Estimate Type: ARO **Cost Basis:** AM-14 CC&V - US

Sheet Name: perf Liner

- Minimum of five holes are needed to perforate each of the PSSAs liners at the base of all Phases in VLFs.
- Assuming one extra hole for contingency we plan for (six) 1,000 foot holes to be drilled, at a cost of \$60/ft = \$360,000
- Number of casing lengths needed to complete (six) 1,000 ft holes is $6,000/20 = 300$ sticks of casing needed. $300*207 = \$62,100$
- Adding casing and drilling costs = \$422,100
- If we want contingency of 15% total equals = \$485,415

	2017	2018	BP2020	BP2021	2023	2024
Cost of drilling VLF liner perforation =	\$ 485,415.00	\$ 495,123.30	\$ 509,977.00	\$ 526,296.26	\$ 536,822.19	\$ 550,242.74
Materials =	\$ 2,017.00	\$ 2,018.00	\$ 2,078.54			
Labor =	\$ 71,415.00	\$ 72,843.30	\$ 75,028.60	\$ 77,429.51	\$ 78,978.10	\$ 80,952.56
Equipment =	\$ 207,000.00	\$ 211,140.00	\$ 217,474.20	\$ 224,433.37	\$ 228,922.04	\$ 234,645.09
Costs	\$ 485,415.00	\$ 495,123.30	\$ 509,977.00	\$ 526,296.26	\$ 536,822.19	\$ 550,242.74