



# Environmental Works, Inc.

## LOCATIONS ACROSS THE CENTRAL US

1455 E. Chestnut Expressway, Springfield, MO 65802

417.890.9500 | [www.environmentalworks.com](http://www.environmentalworks.com)

**Drill Rig Type:** Auger

**Rig Setup:** Track

**Scope:** Replace one well to ~35', 4" steel stickup completion

## PROJECT PROPOSAL

<b>Date:</b>	5.29.24
<b>Company:</b>	Holcim
<b>Contact:</b>	Wyatt Webster
<b>Email:</b>	<a href="mailto:wyatt.webster@holcim.com">wyatt.webster@holcim.com</a>
<b>Street Address:</b>	1687 Cole Blvd, Suite 300
<b>City/State/Postal:</b>	Golden, CO
<b>Tel:</b>	
<b>Cell:</b>	702-379-4623
<b>Project:</b>	Holcim - Well Replacement
<b>Street Address:</b>	13000 O St. Greeley, CO 80631
<b>City/State/Postal:</b>	Greeley, CO
<b>Estimated Duration:</b>	1 day

No.	Item	Unit	Quantity	Unit Price	Unit Total
1	Mobilization/ Demobilization	LS	1	\$ 750.00	\$ 750.00
2	Auger rig and crew	Day	1	\$ 2,750.00	\$ 2,750.00
5	2" SCH40 PVC Well material (15' - 0.010" slot screen)	FT	35	\$ 30.00	\$ 1,050.00
6	4" Steel stickup completion	EA	1	\$ 400.00	\$ 400.00
7	55-gallon soil drum	EA		\$ 125.00	\$ -
9					\$ -
10					\$ -
11					\$ -
Total Cost Estimate:					\$ 4,950.00

**Prepared By:** Adam Kubat

**E-mail:** [Akubat@environmentalworks.com](mailto:Akubat@environmentalworks.com)

**Phone:** 507-475-2825



### Assumptions:

Work will be completed during standard business hours  
Soil will be thin-spread around the well, drums can be provided at the rate listed above.  
EWI is not responsible for damaged utilities or unmarked locations  
Well will be drilled with 3.25" or 4.25" hollow-stem augers  
Access to borehole locations will not be limited by facility infrastructure or site conditions  
Quote is good for 90 days and material cost are good for 14 days due to market  
PWP NTE 45 days is requested for this project.