



## LEGEND

SECTION CONTROL MONUMENT

NO.5 REBAR W/ ALUM. I.D. CAP "MAP SURVEYS-PLS 11980"

---- OVERHEAD POWERLINE OR ELEC. TRANSMISSION LINE

RECLAMATION DIRECTION

- - BOUNDARY OF AFFECTED AREA

----5000--- CONTOUR LINE (CONTOUR INTERVAL=2 FEET) VERTICAL DATUM = NAVD88

AFFECTED AREA

Record bearings rotated to fit Mesa County Local Coordinate System(MCLCS)

NOTES:

ALL SOILS WITHIN AFFECTED AREA IS CLASSIFIED AS CLAPPER STONEY LOAM VEGETATION WITHIN AFFECTED AREA IS RANGE GRASSES AND SALT BRUSH.

MINING OPERATIONS WILL COMMENCE IN PHASES

THE REMOVAL OF 18" OF TOP SOIL WILL BE STOCKPILED FOR RECLAMATION PURPOSES. AFTER APPROXIMATELY 5 ACRES OF AREA HAS BEEN MINED TO AN AVERAGE DEPTH OF 27 FEET PUS OR MINUS, THE AREA WILL BE RECLAIMED.

AS OPERATIONS MOVE TO FURTHER PHASES, TOP SOIL PILES WILL ALSO BE MOVED.

WHEN MINING OPERATIONS IS COMPLETE, RECLAMATION SLOPES SHALL NOT EXCEED 3:1.

ALL AFFECTED LANDS WILL BE REVEGETATED.

NO MINING EQUIPMENT WILL REMAIN ON RECLAIMED LAND.

Dovid Max Morris, Q.E.D. Surveying Systems Inc.

M1996076 AUS

APR 012021

DIVISION OF RECLAMATION

(112) PERMIT - NORTH MINING AREA MAP SITUATED IN THE SEC.34 & 35, T10S, R98W, 6th P.M. Surveying Western Colorado Since 1979 SURVEYED BY: Q.E.D. DRAWN BY: DMM ACAD ID: FONTANARI-MINE SURVEYING SYSTEMS, Inc. CHECKED BY: MEM 2718 Sierra Vista Rd Grand Junction, CO 81503-2232 SHEET NO. 3 OF 7

NOTICE:

ACCORDING TO COLORADO LAW YOU MUST COMMENCE ANY LEGAL ACTION BASED UPON ANY DEFECT IN THIS SURVEY WITHIN THREE YEARS AFTER YOU FIRST DISCOVER SUCH DEFECT. IN NO EVENT MAY ANY ACTION BASED UPON ANY DEFECT IN THIS SURVEY BE COMMENCED MORE THAN TEN YEARS FROM THE DATE OF THE CERTIFICATION SHOWN HEREON.

1" = 100'DATE: 3/29/2021

SCALE:

FOR: FONTANARI

(970) 241-2370 Fax: 241-7025

FILE: 2021-059